

256 South Pine Street, Burlington, WI 53105 • 262.763.7834 • baxterwoodman.com

January 13, 2021

Adam T. Freihoefer Water Use Section Chief Wisconsin Department of Natural Resources 101 South Webster Street Madison, WI 53703

Subject: Village of Somers Water Diversion - Response to 12-15-21 Questions

Dear Mr. Freihoefer:

On behalf of the Village of Somers, we are responding to your enclosed December 15, 2021 letter; the numbering format below matches your letter.

- 1. Updated customer information: Page 24 (Appendix C) of the Water Conservation and Efficiency Plan contains a table of the historical customers served by customer class from 2006-2019. The following data is for 2020:
 - Residential 1,010
 - Commercial 76
 - Industrial 2
 - Public Authority 22
 - Multifamily Residential 114
 - Total = 1,224 Customers
- 2. Enclosed is a concept plan and a cost for a groundwater supply and treatment system for the City of Elkhorn, Wisconsin, similar to what would be required to serve the area west of the Divide in Somers; the concept is from year 2012; the costs are updated to year 2022. The Village of Somers would need to use this same aquifer and would likely need to treat for similar contaminants including radium, arsenic, hydrogen sulfide, iron and manganese. The current capital cost of this type of groundwater supply and treatment system is \$27,000,000. The operational cost would increase by approximately \$300,000 per year to cover the additional labor, salt, waste treatment, and chemicals. This concept provides three wells (each 1000 gallons per minute) with a treatment system containing 8 filter units, 3 softener units, two clearwells, two booster pumps, and emergency power; the firm capacity of the system is 2000 gallons per minute (2.88 MGD). See Response 3 below; both this groundwater supply option and the Lake Michigan supply option require the same distribution system, therefore we removed the distribution system from the comparison.
- 3. The total cost to provide Lake Michigan water to the Diversion Area is the cost of the water transfer station on 18th Street and the connections to the system, which is expected to be \$1.4M.
- 4. The onsite work for the Sheridan Road Water Main Replacement is complete; the last water main went into service in late November of 2021. See the enclosed summary sheet.



Please call if you have any questions.

Sincerely,

BAXTER & WOODMAN, INC. CONSULTING ENGINEERS

Winques M. L di

Douglas R. Snyder

DRS:lrj Attachment C: Jason J. Peters JD/MPA, Administrator (email)

 $I:\Burlington\SOMEV\161104-Water\Diversion\30-ReportStudy\Work\Letter\ to\ DNR.docx$

State of Wisconsin DEPARTMENT OF NATURAL RESOURCES 101 S. Webster Street Box 7921 Madison WI 53707-7921

Tony Evers, Governor Preston D. Cole, Secretary Telephone 608-266-2621 Toll Free 1-888-936-7463 TTY Access via relay - 711



December 15, 2021

Jason Peters Village Administrator P.O. Box 197 Somers WI 53171

Subject: Great Lakes Diversion Application - Request for Additional Information

Dear Mr. Peters:

The Department of Natural Resources (DNR) is reviewing the Village of Somers (Village) diversion application. The DNR held a public hearing and a public comment on the Village diversion application. Our goal of this review continues to be to determine if the Village's application and supplemental information meets the Great Lakes Compact and state statutory criteria for a diversion to a straddling community. The DNR is requesting additional information in response to the public comments that were received.

We require the following information:

- 1. The number of customers of the Somers Water Utility by PSC customer class.
- 2. Additional information on the cost of groundwater wells to provide the water to the diversion area including estimated costs for construction, operation, and maintenance.
- 3. Additional parallel information for costs to implement the proposed diversion.
- 4. An update on the project to replace water main on Sheridan Road, including the timeline for completion of the project and the length of water main replaced.

Thank you for providing the requested information. Please contact me if you have questions related to this request.


Sincerely,

flan treihoef


Adam Freihoefer Chief, Water Use Section Bureau of Drinking Water and Groundwater

cc. Steve Elmore, Director, Bureau of Drinking Water and Groundwater Bureau (email only) Jim Zellmer, Deputy Director, Environmental Management Division (email only) Doug Snyder, Baxter and Woodman (email only)






'Burlington'ELKR's(100356)GIS/MXD):Concept Plan - Viell No 9 North Well Field n 2 March 2011 - DKS



energiantion (income - provide melle 9 than 11/09-21-09 strony date transmissional control and incontinue as 41 The strain 942 and 10-1425



נוצים המונה (בונון 1913) - אונה המסבר לוויד 1/19/2011 הנו או אין היי המסבר

North Well Field City of Elkhorn, WI

<u>ITEM</u>	<u>UNIT</u>	<u>QUANTITY</u>	<u>UNIT COST</u>	<u>AMOUNT</u>	
Land Acquisition	EA	3	\$80,000	\$240,000	
Well Construction	EA	3	\$1,100,000	\$3,300,000	
Remote Well Building	EA	2	\$800,000	\$1,600,000	
Raw Water Main	LF	10,000	\$120	\$1,200,000	
Boring & Jacking	LF	500	\$1,000	\$500,000	
Treatment Equipment	EA	2	\$1,600,000	\$3,200,000	
Treatment Equipment Installation	EA	2	\$500,000	\$1,000,000	
Reservoir / Backwash Tank	EA	3	\$800,000	\$2,400,000	
Treatment Building	EA	1	\$2,000,000	\$2,000,000	
Well / Booster Pumps / Piping	EA	3	\$800,000	\$2,400,000	
Chemical Feed	EA	3	\$200,000	\$600,000	
Site Work	EA	3 \$200,000		\$600,000	
Sanitary Sewer Service	EA	1	\$150,000	\$150,000	
HVAC & Electric	EA	3	\$300,000	\$900,000	
Generator	EA	3	\$300,000	\$900,000	
Water Main/Hydrants/Valves	LF	4,400	\$140	\$616,000	

Construction Cost = \$21,606,000

Engineering & Contingency (25%) = \$5,394,000

Project Cost = \$27,000,000

Note: This study was originally done in 2012; the individual costs were updated to 2022.

Summary Sheet

Sheridan Road Area Water Main Improvements Village of Somers

						Existing				
	Total Water	Length	New	Estimated	Services	Main		No.		
	Main Length	Replaced in	Length	Number of	Size	Size	Proposed	Hydrants	No. Exist.	Abandon
Segment	(feet)	2006 (feet)	(feet)	Services	(inch)	(inch)	Size (inch)	Final	Hydrants	only length
6th Place	680	188	492	9	1 1/4	3	8	2	2	N/A
6th Street	524	167	357	7	1 1/4	6	8	3	2	N/A
7th Place	252	100	152	5	1 1/4	6	8	2	2	N/A
7th St to 8th St	0	0	0	0	N/A	6	N/A	1	1	1590
8th Place	706	203	503	14	1 1/4	6	8	3	3	N/A
8th Street	766	194	572	15	1 1/4	6	8	3	2	N/A
9th Place	784	150	634	13	1 1/4	6	8	3	2	N/A
9th Street	770	203	567	15	1 1/4	3	8	2	3	N/A
10th Place	787	177	610	11	1 1/4	3	8	3	2	N/A
10th Street	851	269	582	12	1 1/4	6	8	4	3	N/A
10th St to 11th Pl	0	0	0	0	N/A	6	N/A	0	0	1175
11th Place	873	164	709	17	1 1/4	6	8	3	2	N/A
11th Street	865	182	683	13	1 1/4	3	8	3	2	N/A
12th Place	456	77	379	7	1 1/4	6	8	3	3	N/A
12th Street	1011	141	870	12	1 1/4	8	12	2	1	N/A
13th Street	386	122	264	10	1 1/4	6	8	2	2	N/A
13th Place	629	150	479	13	1 1/4	6	8	3	3	N/A
14th Place	744	152	592	20	1 1/4	6	8	3	3	N/A
15th Place	813	142	671	16	1 1/4	6	8	3	2	N/A
16th Street	775	0	775	26	1 1/4	6	8	4	3	N/A
16th Place	756	0	756	23	1 1/4	3	8	4	3	N/A
17th Street	754	0	754	28	1 1/4	3	8	4	3	N/A
Total			11401	286				60	49	2765

