


Flambeau River State Forest and other State Lands Sustainable Forestry Timber Sales

Includes sales from
Flambeau River State Forest – 11 sales
(including 2 salvage sales)
Other State Lands in Sawyer County - 3 sales

August 14, 2008



Flambeau River State Forest Sale Locator Map



Tract 14-06 (Spring Beauty)

Parts of: S1/2 NW, NWNW, SW Sec. 4, N1/2NW Sec. 9 T38N-R3W Sawyer County

132 Acres

<u>Species</u>	<u>Estimated Volume</u>	<u>Advertised Value/Unit</u>	
Mixed Pulp*	950 cds	17.60	
Basswood Pulp	120 cds	2.00	<u>Bid for Entire Sale</u>
Aspen	325 cds (30% damage)	16.80	\$35,732.00
Hard Maple	44 MBF	240.00	
Red Maple	4 MBF	96.00	
Basswood	16 MBF	88.00	
Yellow Birch	4 MBF	152.00	
Mixed Saw**	4 MBF	88.00	

*Mixed pulp includes approx. 65% hard maple, 10% yellow birch, 15% red maple, 10% ash, white birch, elm, fir, and ironwood.

**Mixed saw includes 55% white birch, 40% ash, and 5% elm.

The bid bond will be 15% of the total sale value. This will also be used as the performance bond. Contract length is approximately two years.


SPECIAL SALE CONDITIONS:

1. No logging April 1st through June 30th in select cut area. Logging allowed during frozen conditions only except by special permission during very dry conditions.
2. Existing woods roads will be used. New road construction is optional, and is limited to proposed road layout shown on prospectus map. Modifications can be made with approval from Forester. A small segment goes through private property in which permission has been granted. It will be the responsibility of the contractor to repair any damage done to the road.
3. Cutting will not be allowed in the Birch area until scarification is completed by WDNR during non-frozen conditions. Harvest shall be completed within one year of scarification.
4. Contractor is required to close road at the location designated on the map by placing logging debris, per sale prospectus.
5. Pole skidding may be required and will be allowed in aspen area and on steep slopes in the select cut areas. Pole skidding in the steep terrain of the select cut area will be restricted to a maximum stringer length of 25 feet. The steeper slopes are primarily located in the northern 1/3 of the sale.
6. Areas marked with an "A" have the wettest soil conditions on this sale. These areas need to be properly "froze-down" before any harvesting can be done.
7. Wheeled or tracked harvesting equipment will only operate within 15 feet of wetlands when the ground is frozen or dry.
8. Watch for small wetlands throughout the sale. No slash is to be left in any non-forested wetland.
9. Culverts may be needed. Culvert placement and removal are the responsibility of the contractor.
10. TePaske Road is also a snowmobile trail. 3" of packed snow will be maintained on snowmobile trail, weather permitting. The trail will be kept free of debris.
11. **All additional restrictions listed in the prospectus and standard contract apply unless specified.**


Sale Tract 14-06 (Spring Beauty)



Select cut Area (111 acres) – Bounded by red paint lines. Harvest orange marked trees within the designated boundaries. Do not cut trees with an orange “X”. These are leave trees. **Sever all orange marked unmerchantable stems (canopy gaps).**




Aspen Area (18 acres) – Bounded by yellow. Cut all trees greater than 2” except for: 1) hemlock, 2) white pine, and 3) oak. Approx. 10 acres have some wind damage.



Birch Scarification area (approx. 3 acres) – Bounded by red. Harvest all merchantable trees except for: 1) hemlock and white pine, 2) aspen, and 3) green marked trees. All unmerchantable stems, except for aspen, shall be severed.

- x x x x Proposed woods road
- - - Existing woods road
- = = = = Snowmobile trail
- Berm to be placed
- + Survey monument



Scale 1:15840
Approx. 4"=1Mile

approx. 2 miles from
Cty Rd W to Sale

Tract 1-08 (South Flambeau Rd. Sale)

Parts of: N1/2 NE, N1/2 NW Sec. 24, T36N-R5W, Rusk County

52 Acres

Species	Estimated Volume	Advertised Value/Unit	
Mixed Pulp ¹	350 cds	\$ 18.10	
Basswood Pulp	150 cds	\$ 2.00	
Aspen	190 cds	\$ 16.10	Minimum Acceptable
Red Pine Pulp	75 cds	\$ 13.30	<u>Bid for Entire Sale</u>
Basswood	13 MBF	\$ 81.00	\$12,684.50
Ash	4 MBF	\$ 67.00	
Misc. Saw ²	7 MBF	\$ 96.00	

¹Mixed pulp is approx. 70% sugar maple, 20% red maple, 10% ash, and a small amount of yellow birch and red oak.


²Misc. saw includes 5 MBF of sugar maple, 2 MBF of red maple, and a small amount of red oak. Any other species not mentioned will be charged the mixed pulp price or the misc. saw price.


The bid bond will be 15% of the total sale value. This will also be used as the performance bond. Contract length is approximately two years.

SPECIAL SALE CONDITIONS:

- Area A** - Equipment use will be restricted to very dry or frozen ground conditions due to wet soil conditions. **Area B** - Equipment use will be restricted to **frozen conditions only**, due to the stream bed that runs through and parallels this area. General operational period will most likely be December through March. No cutting can be done during the months of April, May and June in the select cut area and the red pine thinning area.
- No pole length skidding will be allowed in the select cut area.
- New road construction is limited to proposed road layout shown on prospectus. Existing roads can be used. Any decking on Flambeau Road must have prior written approval from the Town of Cedar Rapids.
- Slash that is within 100 feet of Flambeau Road will be lopped and scattered to within 2 feet of the ground by contractor.
- The wildlife opening around the red pine can be used for decking. The topsoil shall not be disturbed and this opening is to be free of all logging debris at the end of the sale.
- Contractor will be required to close roads at locations designated on the map by placing logging debris(berm), per sale prospectus.
- All additional restrictions listed in prospectus and standard contract apply unless specified.**

 Select Cut Area (31 acres) – Bounded by red paint lines and road. Harvest all trees marked with orange paint (leave snag/cull trees marked with orange X). **Sever all orange marked unmerchantable stems (canopy gaps). Harvest only marked aspen.**

 Red pine plantation thinning (9 acres) – Bounded by wildlife openings and aspen. This is a 1st thinning with 2 sticks/tree average. This plantation is not marked. Contractor is to leave 4 rows on the outside edges of plantation, then cut 2 rows, leave 4 rows and continue with cut 2, leave 4.

 Aspen Area (12 acres) – Bounded by red and yellow paint lines and road. Cut all trees greater than 2" except for: 1) hemlock, 2) white pine, and 3) oak.

----- Existing woods road.

X X X Proposed woods road

— Gate


— Berm to be placed at completion of sale

⤴ Dry stream bed

⊙ Potential turn-around



Scale 1: 15840
Approx 4" = 1mile



Tract 6-08 (Friendly Doe)

Parts of: SE¼SW¼, T-37-N, R-4-W, Sec 34 Sawyer County
 Parts of: NW¼, N½SW¼, T-36-N, R-4-W, Sec 3 Rusk County

68 Acres

Species	Estimated Volume	Advertised Value/Unit	
Aspen	300 cds.	19.10	
Tamarack*	100 cds	12.60	
Mixed pulp**	600 cds	19.10	
Basswood	20 cds	2.80	
Hard Maple	13 MBF	232.00	
Soft Maple	7 MBF	93.00	
Misc. saw ***	10 MBF	86.00	
			Minimum acceptable bid
			<u>Bid for entire sale</u>
			\$23,033.00


***Misc. saw approx. 50% basswood, 25% ash, and 15% yellow birch and 10% red oak
 **Mixed pulp includes approx. 50% hard maple, 40% soft maple, 8% ash and 2% yellow birch, cherry, oak, and elm
 *Tamarack volume includes approx. 70% tamarack, 20% balsam fir, and 10% black spruce
 - Any other species not mentioned will be charged the mixed pulp or misc. saw price, accordingly.


The bid bond will be 15% of the total sale value. This will also be used as the performance bond. Contract length is approximately two years.

SPECIAL SALE CONDITIONS:

- Equipment use will be restricted to frozen ground conditions only due to wet soil conditions. General operational period will most likely be December through March.
- No pole length skidding will be allowed in the select cut area.
- No slash will be left across the red line into the buffer next to the stream.
- Landing size will be restricted to a maximum size of 100 ft x 200 ft. No landings will be allowed within 150 ft. of the stream.
- Rutting will be cause for suspension of sale operations until such conditions change.
- Existing woods roads will be used. New road construction will be required and must be approved by Forester.
- Road shared with private landowners; gate shall remain closed (unlocked) during the working day and locked during non-working hours.
- All additional restrictions listed in prospectus and standard contract apply unless specified.

Y/R- denotes yellow and red paint lines - - - - Existing woods roads
 *** Approx location of tamarack strips X X X Proposed woods roads
 UB- Upland brush Leave- leave area; surrounded by red paint line

-  Select Cut Area (39 acres) – Bounded by red paint lines. Harvest all trees marked with orange paint. Sever all orange marked unmerchantable stems (canopy gaps). Harvest all merchantable aspen throughout the sale area.
-  Tamarack Area (7 acres) – Bounded by red paint line. Cut all trees greater than 2" except for hemlock, white pine, cedar, and red oak within 1 chain (66') on both sides of strip line (denoted by orange paint).
-  Aspen Area (22 acres) – Bounded by yellow paint. Harvest all trees greater than 2" except for hemlock, white pine, cedar, and red oak. Protect pockets of existing regeneration; do not drop trees or drive equipment through these pockets.



Tract 5-08 (Long Creek West)

Parts of: N1/2NE, SWNE, NENW, S1/2NW, N1/2SW, SWSW, SESW, SWSE Sec. 6 T38N-R3W

Parts of: NWNE, NENW Sec. 7, T38N-R3W Sawyer County

312 Acres

<u>Species</u>	<u>Estimated Volume</u>	<u>Advertised Value/Unit</u>	
Mixed Pulp ¹	3200 cds	17.00	
Basswood Pulp	135 cds	2.00	
Aspen ²	100 cds	17.00	
Sugar Maple	50 MBF	224.00	
Red Maple	40 MBF	90.00	Minimum Acceptable
Ash	44 MBF	62.00	<u>Bid for Entire Sale</u>
Basswood	15 MBF	76.00	\$77,632.00
Yellow Birch	17 MBF	142.00	
Misc. ³	2 MBF	90.00	

¹Mixed Pulp includes approximately 44% hard maple, 36% red maple, 8% yellow birch, 11% ash, and 1% cherry, ironwood, balsam, hemlock.

²Aspen volume includes 20% white birch. ³Misc. sawlogs are primarily white birch. Other species not mentioned will be charged the mixed pulp price or misc. saw price.

The bid bond will be 15% of the total sale value. This will also be used as the performance bond. Contract length is approximately two years.

SPECIAL SALE CONDITIONS:

1. Equipment use restricted to **frozen** ground conditions only.
2. No pole length skidding will be allowed in the select cut area.
3. Contractor is required to close roads at locations designated on map by placing logging debris per sale prospectus.
4. Existing roads will be used. New road construction will be limited to proposed road layout shown on prospectus map. Modifications can be made with approval from Forester. No landings will be built within 200' of Long Creek.
5. No crossing of Long Creek will be allowed. The sale will be accessed by 2 separate roads to avoid doing a stream crossing. A road use permit from the Forestland Group has been obtained. Conditions of the permit need to be followed by contractor.
6. This sale has special stream monitoring equipment near the old stream crossing. Extra caution will be required to protect the equipment from damage. No wheeled or tracked harvesting equipment will be operated within 50 feet of the ordinary high water mark of Long Creek. No slash to be left in Long Creek or any non-forested wetland.
7. Avoid damaging existing regeneration as much as possible through out the select cut area and the overstory removal area when harvesting. In the overstory removal area, place skid trails a minimum of 60 feet apart.
8. Watch for small wetlands and drainages throughout the sale.
9. Avoid survey monuments illustrated on prospectus map.
10. **All additional restrictions listed on the prospectus and standard contract apply unless specified.**

Tract 5-08 (Long Creek West)



Select Cut Area (299 acres) – Bounded by red paint lines. Ignore maroon paint line in the northwest part of sale. Harvest all trees marked with orange paint. **Sever all orange marked unmerchantable stems (canopy gaps).** Do not cut trees with an orange "X", these are leaves trees. Avoid damaging existing regeneration.





Aspen Area (4 acres) – Bounded by yellow paint lines. Cut all trees greater than 2" except for: 1) hemlock, 2) white pine, 3) oak, 4) cedar, and 5) balsam with 1 stick or less.



Overstory Removal (9 acres) – Bounded by yellow paint lines. Cut all merchantable trees except for: 1) hemlock, 2) white pine, 3) oak, and 4) balsam with 1 stick or less. Avoid damaging existing regeneration.

- Y Yellow paint facing aspen
- Existing woods road
- x x x Proposed woods road
- ▬ Berm to be placed
- ⊕ Turn around
- UB Upland brush
- ooo Maroon paint line (ignore)
- + Survey markers
- I Gate
- ↘ Wet



Tract 9-08 (Dave's Rock Creek Sale)

Parts of: SE1/4 Sec. 7, W1/2SW1/4 Sec 8 and NE1/4 Sec 18, T39N-R2W Price County

86 Acres

<u>Species</u>	<u>Estimated Volume</u>	<u>Advertised Value/Unit</u>	
Mixed Pulp ¹	780 cds.	21.40	
Basswood	125 cds	2.50	Minimum Acceptable
Aspen	575 cds	19.90	<u>Bid for Entire Sale</u>
Hard Maple	20 MBF	219.00	\$34,143.00
Basswood	11 MBF	81.00	
Misc. saw ²	5 MBF	85.00	

¹Mixed pulp is approx. 60% sugar maple, 30% red maple, 8% ash and 2% of yellow/white birch and white spruce. ²Misc. saw is approx. 60% red maple, 27% ash, and 13% yellow birch. Any species not mentioned will be charged the mixed pulp or misc. saw price.

The bid bond will be 15% of the total sale value. This will also be used as the performance bond. Contract length is approximately two years.

SPECIAL SALE CONDITIONS:

1. No logging April 1st through June 30th. Logging allowed during frozen conditions only except by special permission during very dry conditions.
2. No pole length skidding will be allowed in the select cut area.
3. The stand on the west side of Rock Creek Road has a significant amount of hard maple regeneration. The hard maple regeneration is located mostly in the northern half of the stand. **Extra caution** is needed to avoid damaging the existing pockets of regeneration. These pockets of regeneration should not have trees felled into them or skid trails run through them. This stand has rolling terrain.
4. The proposed roads will be the only access points allowed for the two stands. No new access points will be allowed off of Rock Creek Road. Any decking on Rock Creek Road must have prior written approval from Town of Lake.
5. No landings will be built within 200 feet of Rock Creek Road. Landing size will be limited to approximately 100' by 200'.
6. Slash that is within 100 feet of Rock Creek Rd. will be lopped and scattered to within 2 feet of the ground by contractor.
7. Contractor is required to close roads at the locations designated on the map by placing logging debris, per sale prospectus.
8. **All additional restrictions listed in the prospectus and standard contract apply unless specified.**

Tract 9-08 (Dave's Rock Creek)




Select Cut Area (34 acres) – Bounded by red paint lines. Harvest all trees marked with orange paint. Do not cut snags/cull trees marked with an orange X. Sever all orange marked unmerchantable stems (canopy gaps).




Aspen Area (52 acres) – Bounded by red paint lines and road. Cut all trees greater than 2" except for hemlock, white pine, and oak.

- Existing woods road
- x x x Proposed and existing woods road
- - - - Old skid trail
- ⊕ Potential turnaround
- YA Young aspen (23 yrs. old)
- Cable gate
- Berm to be placed by contractor
- ∨ Wetland



Scale 1:15840
Approx. 4"=1Mile



Tract 11-08 (Hervas CCC)

Parts of: NENE Sec. 8; SWNE, SENW Sec. 10, T36N-R4W

Parts of: NENE, NWNE, SWNE, SENE, NWNW Sec. 9, T36N-R4W, Rusk County

53 Acres

<u>Species</u>	<u>Estimated Volume</u>	<u>Advertised Value/Unit</u>	
Mixed Pulp ¹	190 cds	\$23.20	Minimum Acceptable
Basswood Pulp	50 cds	\$ 2.00	<u>Bid for Entire Sale</u>
Spruce ²	65 cds	\$19.10	\$25,864.50
Aspen	850 cds	\$23.20	
Misc. Saw ³	5 MBF	\$79.00	

¹Mixed pulp includes hard maple, red maple, ash, and a small amount of hickory and yellow birch. ²Spruce includes both white and Norway spruce. It also includes a small amount of balsam fir. ³Misc. saw includes 60% basswood, 25% ash, 15% maple, and a small amount of hickory. Any species not mentioned will be charged the mixed pulp price.

The bid bond will be 15% of the total sale value. This will also be used as the performance bond. Contract length is approximately two years.


SPECIAL SALE CONDITIONS:

1. No logging April 1st through September 30th due to recreational uses in the proximity of the sale. Logging allowed during frozen conditions only except by special permission during very dry conditions. However, the white spruce plantation and surrounding area will be restricted to frozen ground conditions only due to historical value.
2. No pole length skidding will be allowed in the select cut area or the white spruce plantation.
3. No slash will be left in town road right-of-way or within 33 feet of centerline.
4. Existing woods roads will be used. Road construction and landings must be approved by Forester. Any decking on River Road must have prior written approval from Cedar Rapids Township. Landing size will be limited to approximately 100 feet by 200 feet and will not be within 200 feet of the town road.
5. Slash that is within 100 feet of River Road will be lopped and scattered to within 2 feet of the ground by the contractor.
6. The opening north of the white spruce plantation will not be used for a landing to protect historical value in this area. No heavy equipment allowed in this opening.
7. Contractor is required to close roads at the locations designated on the map by placing logging debris, per sale prospectus.
8. **All additional restrictions listed in prospectus and standard contract apply unless specified.**


Tract 11-08 (Hervas CCC)



Select Cut Area (12 acres) – Bounded by red paint and road. Harvest all trees marked with orange paint. Sever all orange marked unmerchantable stems (canopy gaps).




Spruce Plantation (7 acres) – First thinning. Harvest all trees marked with orange paint.



Aspen Regeneration Area (34 acres) – Cut all trees greater than 2" except for: 1) hemlock, 2) white pine, 3) oak

- Potential turnaround and decking area
- Existing woods road
- Berm to be placed
- Gate

Scale 1:15840
Approx. 4"=1Mile



Tract 12-08 (Skinner Quick Sale)

Parts of the S ½ of SW ¼ Sec. 26, SW ¼ of SE ¼ Sec. 27, SE ¼ of NE ¼ and NE ¼ of SE ¼ Sec. 34 and E ½ of NW ¼ and NE ¼ of the NW ¼ Sec. 35 T36N-R3W Sawyer County

159 Acres

<u>Species</u>	<u>Estimated Volume</u>	<u>Advertised Value/Unit</u>	
Mixed Pulp ¹	1075 cds	\$ 23.00	
Aspen	900 cds	\$ 23.00	Minimum Acceptable
Basswood	120 cds	\$ 2.00	<u>Bid for Entire Sale</u>
Balsam Fir and spruce ²	230 cds	\$ 22.30	\$58,729.00
Hard Maple	22 MBF	\$222.00	
Red Maple	16 MBF	\$ 89.00	
Basswood	13 MBF	\$ 75.00	
Ash	4 MBF	\$ 61.00	
Misc. ³	4 MBF	\$102.00	

¹ Mixed pulp is approximately 46% Red Maple, 34% Hard Maple, 12% Ash, 5% Yellow Birch and 3% White Birch.

² Approximately 55% Balsam Fir and 45% White Spruce.

³ Misc. saw includes approximately 50% Yellow Birch and 50% White Birch.

The bid bond will be 15% of the total sale value. This will also be used as the performance bond. Contract length is approximately two years.


SPECIAL SALE CONDITIONS:

1. Equipment use will be restricted to **frozen ground only** due to wet soil conditions.
2. Existing snowmobile trail will be used for access to this sale. 3" of packed snow must be maintained on the snowmobile trail, weather permitting, and the trail will be kept free of debris. For safety reasons, decking along snowmobile trail should be avoided.
3. It will be the responsibility of the contractor to repair any damage on the snowmobile trail due to logging operations.
4. Use of designated wildlife openings for landing is permitted and proposed. The topsoil shall not be disturbed and the opening is to be free of all logging debris at the end of the sale.
5. No pole length skidding will be allowed in the select cut area.
6. Existing woods roads will be used to access landing areas. Road construction must be approved by Forester. Any decking on snowmobile trail must have prior approval from a Forester. See prospectus map for existing woods roads and proposed landing areas.
7. Avoid government survey monument illustrated on prospectus map.
8. Slash that is within 100 feet of the snowmobile trail will be lopped and scattered to within 2 feet of the ground by the contractor.
9. Contractor is required to close roads at locations designated on the map by placing either berms or logging debris.
10. No landings will be built within 200 feet of the snowmobile trail. Landing size restricted to approximately 100' x 200'.
11. **All additional restrictions listed in the prospectus and standard contract apply unless otherwise specified.**

Tract 12-08 (Skinner Quick Sale)




Select Cut Area (85 acres) – Bounded by red lines. Harvest all trees marked with orange paint. Sever all orange marked unmerchantable stems (canopy gaps). Leave, do not cut snags/cull trees marked with an orange X.



Aspen Area (74 acres) – Cut all trees greater than 2" except for 1)hemlock, 2)white pine, 3)cherry and 4) oak.

- Stream
- Snowmobile trail
- xxxxxx Proposed/existing woods road
- Y/R Yellow paint facing aspen areas, red paint facing select cut areas
- Berm to be placed
- Ⓛ Potential landing
- Ⓟ Survey Marker
- UB Upland brush
- SC Swamp conifer



Scale 1:15840
Approx. 4"=1Mile



Tract 13-08 (River Road East)

Parts of: SENE, SWNE, N1/2SE, SWSE, NESW, SESW, SWSW Sec. 9, T36N-R4W
 Parts of NWSW Sec. 10, T36N-R4W Rusk County

95 Acres

Species	Estimated Volume	Advertised Value/Unit
Mixed Pulp ¹	510 cds.	20.70
Basswood Pulp	110 cds	2.50
Aspen	1100 cds	20.70
Red Maple	15 MBF	100.00
Basswood	11 MBF	84.00
Ash	7 MBF	69.00
Misc. ²	3 MBF	100.00

Minimum Acceptable
Bid for Entire Sale
\$36,809.00


¹Mixed Pulp includes approximately 22% hard maple, 62% red maple, 14% ash, and 2% elm, cherry, oak, hickory, spruce. ²Misc. sawlogs are primarily hard maple with a small amount of oak and hickory.

The bid bond will be 15% of the total sale value. This will also be used as the performance bond. Contract length is approximately two years.

SPECIAL SALE CONDITIONS:

1. No logging April 1st through June 30th in the select cut areas. Logging allowed during frozen conditions only except by special permission during very dry conditions.
2. No pole length skidding will be allowed in the select cut area.
3. Contractor is required to close road at location designated on map by placing logging debris per sale prospectus.
4. New road construction will be limited to proposed road layout shown on prospectus map. Modifications can be made with approval from Forester. The existing "cut-out" road along the southern boundary of the forest may be used for decking. The "cut-out" road can only be expanded on the north side. Landing size will be limited to 100 by 200 feet.
5. Slash that is within 100 feet of River Road will be lopped and scattered to within 2 feet of the ground by the contractor. Decking in old gravel pit is permitted.
6. Any decking on River Road must have prior written approval from Cedar Rapids Township.
7. Watch for small wetlands throughout the sale.
8. All additional restrictions listed on the prospectus and standard contract apply unless specified.


 Select Cut Area (50 acres) – Bounded by red and blue paint lines. Harvest all trees marked with orange paint. Sever all orange marked unmerchantable stems (canopy gaps). Do not cut trees with an orange "X", these are leaves trees.

 Aspen Area (45 acres) – Bounded by yellow and blue paint lines. Cut all trees greater than 2" except for: 1) hemlock, 2) white pine, and 3) oak.

- Y/R Yellow paint facing aspen/ red paint facing hardwoods
- Existing woods road
- x x x Proposed woods road
- Berm to be placed
- Old gravel pit
- UB Upland brush
- ∨ Wet

N

 Scale 1:15840
 Approx. 4" = 1 mile




Species	Estimated Volume	Advertised Value/Unit	
Aspen	550 cds (75% damaged)	15.00	Minimum Acceptable
White Spruce	270 cds.(75% damaged)	12.00	<u>Bid for Entire Sale</u>
Balsam Fir	85 cds (75% damaged)	12.00	\$12,960.00
Mixed Hardwoods ¹	30 cds. (75% damaged)	15.00	

¹Mixed hardwoods include sugar maple, red maple, white birch, and some cherry. There is a very small amount of sawlogs included in the mixed pulp volume.

The bid bond will be 15% of the total sale value. This will also be used as the performance bond. Contract length is approximately one year.

SPECIAL SALE CONDITIONS:

- Equipment use will be restricted to very dry or frozen ground conditions north of the ravine shown on the map. Equipment use south of the ravine will be restricted to frozen ground conditions only due to wet soil conditions. Crossing the drainage in the ravine will require a temporary pole ford, timber mat, or similar structure. Removal of the structure by the contractor upon completion of the sale is required. Any road work done in this area will require the installation of erosion control practices.
- New road construction must be approved by Forester.
- No slash will be left across the cut line onto United States Forest Service (USFS) property or within 50 feet of the streams.
- Construction and maintenance of roads on USFS land will be done according to the USFS Special Use Permit and Operation/Management Plan. Specifications include, but are not limited to 1) a roadway no wider than 20' (12' running surface), 2) Logging Ahead signs to be appropriately posted on Cty. Rd. E and EE by contractor during hauling operations, 3) brushing along Cty. Rd. E and EE will be required for safety and visibility, and 4) a temporary gate will need to be placed by contractor no farther than 75' off of Highway "EE". The gate will need to be removed and the existing berm replaced at the present location upon completion of the sale. **The gate MUST remain closed (unlocked) during the work day and locked during non-working hours. Truckers will need to close the gate each time when entering and exiting through the gate.** For a complete copy of the Special Use Permit, contact the Flambeau River State Forest.
- Landings will be limited to sizes not exceeding 100' x 200', and will not be built within 200' of creeks or USFS boundary line.
- Contractor is required to close road on state land at the completion of the sale by placing a berm at location designated on map.
- All additional restrictions listed in prospectus and standard contract apply unless specified.




Aspen Regeneration Area, salvage (54 acres) – Bounded by yellow paint line and cut line. Cut all trees greater than 2" except for hemlock, white pine, white cedar, tamarack, and red oak.

- berm to be placed
- existing forest road (USFS)
- proposed road



Scale 1:15840
 Approx. 4" = 1 mile



Tract 15-08 (Turning Point Re-Do)

Parts of: N½NE¼, SW¼NE¼, E½NW¼ Sec. 32, T-37-N, R-4-W, Sawyer County

71 Acres

Species	Estimated Volume	Advertised Value/Unit	
Mixed Pulp *	285 cds.	\$21.70/cd	
Aspen	510 cds	\$21.70/cd	
Spruce	40 cds	\$15.30/cd	
Basswood	20 cds	\$ 2.10/cd	
Hard Maple	7 MBF	\$247.00/MBF	
Soft Maple	4 MBF	\$ 99.00/MBF	Minimum Acceptable
Basswood	8 MBF	\$ 84.00/MBF	<u>Bid for Entire Sale</u>
Misc. *	3 MBF	\$ 61.00/MBF	\$20,855.50

*Misc. saw includes approx. 80% ash with a small amount of red oak, hickory, and white birch. Mixed pulp includes hard & soft maple, ash, and white birch. Other species not mentioned will be charged the mixed pulp price or misc. saw price.

The bid bond will be 15% of the total sale value. This will also be used as the performance bond. Contract length is approximately two years.

SPECIAL SALE CONDITIONS:

1. Equipment use will be restricted to frozen ground conditions due to wet soil conditions. General operational period will most likely be December through March.
2. No pole length skidding will be allowed in the select cut or spruce area.
3. No slash shall be left across the blue paint onto Sawyer County Forest Land.
4. Landing size will be restricted to 100' x 200'.
5. Existing woods roads will be used. Road construction must be approved by Forester. Any decking on Haystack Road must have prior written approval from Winter Township.
6. The harvest of some spruce within the spruce area will be allowed for operational purposes, i.e. skid trails. Place skid trails a minimum of 60' apart.
7. Watch for small wetlands throughout the sale.
8. Care will be taken to avoid damaging hemlock.
9. **All additional restrictions listed in prospectus and standard contract apply unless specified.**

Tract 15-08 (Turning Point Re-Do)

 Spruce Area (5 acres)- Bound by red paint lines. Harvest all merchantable hardwoods and aspen. Some spruce may be harvested for operational purposes. Keep skid trails a minimum of 60' apart.

 Select Area (27 acres)- Bound by red and blue paint lines. Harvest all trees marked with orange paint. Sever all orange marked unmerchantable stems (canopy gaps).

 Aspen Area (39 acres) - Bound by yellow paint lines and recent clear-cut. Cut all trees greater than 2" except for hemlock, white pine, white spruce, tamarack, red oak, and cherry.

----- Existing woods roads


Y - Denotes yellow paint line

X X X X Proposed roads


R - Denotes red paint line

SW - Leave area consisting of young spruce

↓ - Wet areas



Scale 1:15840
Approx. 4"=1Mile



Sawyer Co.
Rush Co.

Tract 16-08 (Oxbo Salvage Re-do)

Parts of: SW Sec. 13; SE Sec. 14; NENE, NWNW Sec. 23; NWNW Sec. 24; NWNE Sec. 26
T39N-R3W , Sawyer County

118 Acres

<u>Species</u>	<u>Estimated Volume</u>	<u>Advertised Value/Unit</u>	
Mixed Pulp ¹	400 cds. (60% damaged)	10.00	
Aspen ²	1000 cds (50% damaged)	10.00	
Balsam Fir ³	120 cds (50% damaged)	10.00	
Red/White pine pulp ⁴	160 cds (10% damaged)	10.00	Minimum Acceptable
Sugar Maple	17 MBF (60% damaged)	100.00	<u>Bid for Entire Sale</u>
Yellow Birch	4 MBF (60% damaged)	100.00	\$19,236.00
Misc. Saw ⁵	7 MBF (60% damaged)	48.00	

¹Mixed pulp includes 90% hard maple, 7% red maple, 3% yellow birch, and includes a very small amount of basswood and cherry.

²Aspen includes approx. 15 cds of white birch.

³Balsam Fir volume includes approx. 5% spruce.

⁴Red/White pine pulp includes 11 MBF of red pine and 2 MBF of white pine. The pulp is 90% red pine.

⁵Misc. Saw includes approx. 3 MBF red maple, 3 MBF white birch, and 1 MBF of cherry and basswood.

The bid bond will be 15% of the total sale value. This will also be used as the performance bond. Contract length is approximately one year.

SPECIAL SALE CONDITIONS:

1. The majority of this sale was damaged from a wind storm that occurred in July 2006. All sound wood must be utilized to a 4" top diameter.
2. No logging April 1st through June 30th in select cut area and red pine plantations. Logging allowed during frozen conditions only except by special permission during very dry conditions.
3. No pole skidding will be allowed in the select cut area or the red pine plantations.
4. Existing woods roads will be used. New road construction is optional, and is limited to proposed layout shown on prospectus map. Modifications can be made with approval from Forester. Any decking on Lincoln Road or Snuss Blvd. must have prior written approval from Draper Township.
5. Slash along Hwy. 70, Lincoln Road, Snuss Blvd. and ATV/snowmobile trail shall be lopped and scattered to within 2 feet of the ground by the contractor. No slash or logging debris will be left across the blue line onto private land.
6. Wheeled or tracked harvesting equipment will only operate within 15 feet of wetlands when the ground is frozen or dry.
7. No landings to be built within 200 feet of the ATV/snowmobile trail in the aspen regeneration area. Landing size is to be limited to approximately 100' by 200'.
8. 3" of packed snow will be maintained on snowmobile trail, weather permitting. The ATV/Snowmobile trail will be kept free of debris. Wood will be decked far enough off of trail so as not to impede ATV/snowmobile traffic.
9. **All additional restrictions listed on prospectus and standard contract apply unless specified.**

Tract 16-08 (Oxbo Salvage Re-do)

 Northern Hardwood Area (20 acres) – Bounded by red paint lines and red/blue paint lines. Ignore old yellow paint line. Harvest all downed trees and trees marked with orange paint. Do not cut trees with an orange “X”. These are leave trees.


 Aspen Regeneration Area (67 acres) – Bounded by yellow paint. Cut all trees greater than 2” except for: 1) hemlock, 2) white pine, 3) red pine, and 4) spruce.

 Red Pine Plantations (29 acres) – Bounded by red paint lines and red/blue paint lines. Ignore old black paint line. Harvest all wind damaged trees and orange marked trees. Harvest all merchantable (marked and unmarked) aspen and hardwoods within the plantation areas.

 Red Pine Clearcut Area (2 acres) – Bounded by yellow and blue/red paint lines. Cut all trees greater than 2”.

 Red pine pockets – Bounded by aspen regeneration area. Harvest all wind damaged trees and orange marked trees. Harvest all aspen and hardwoods within the red pine pockets.

- Existing woods road
- - - - - ATV/snowmobile trail
- o o o Proposed trail
- ⊕ Proposed turnaround
- ↔ Wetlands
- YA Young aspen
- I Gate
- ... Old yellow paint line



State Owned Lands
 TIMBER SALE PROSPECTUS
 TRACT # H0507
 Section 19, 30 T 40N R 7W
 Hunter Township, Sawyer County

Contact for sale:
 Kim Lemke
 (715) 634-9658
 ext. 3506
 Hayward Service Center

Species	Estimated Volume	Comments	Minimum Bid/Unit	My Bid/Unit	My Total Bid/Species
Mixed Hdwd.	1400 Cd.	Includes 20 cd. Fir, 20 cd. Oak, 10 cd. Mx. pine	\$ 17.00		
Aspen	1400 Cd.		27.75		
White Birch	700 Cd.		21.20		
Oak	5 MBF		283.00		
Mixed Hardwood	4 MBF	75% S. Maple	118.00		
Wht. & Red Pine	2 MBF		134.00		

Total Bid _____

Harvesting Prescription:

CLEARCUT AREA: Cut all trees 2" diameter and larger except B. ash and unmarked pine. Crush slash and unmerchantable trees to 24" or less from ground.

SELECT CUT AREA: Harvest all trees marked with orange paint and all aspen, fir, white birch, and ironwood with 1 or more pulpwood sticks.

ENTIRE SALE AREA: Utilize all cut trees to a 5" top dia. Or less.

Integrated Resource Considerations:

This 119 acre sale includes an 83 acre regeneration harvest with an objective of regenerating aspen, birch and soft maple. The objective of the 36 acre selective harvest is to prepare the site for regeneration of oak and white pine.

This sale is restricted to operation during frozen ground conditions only to protect wet soils and the watershed, and to minimize concerns from the public who recreate on the adjacent Chippewa Flowage mostly in summer. Soil exposure is desirable on the uplands to encourage regeneration of even-aged tree species. Slash and logging debris produced on the uplands may not be deposited in any wetland.

All existing and future logging roads must be kept free of slash and logging debris. Any new forest road location or construction is subject to review and approval by the DNR forester. Decking of cut forest products is not permitted on the town road right-of-way. Upon completion of this timber sale, all skid trails and logging roads used in the harvesting operation must be graded and seeded.

The owner of the private land adjacent to this harvest area is agreeable to the use of his forest roads to access this sale area. This landowner and the State prefer to see new road construction kept to a minimum.


I hereby make application to purchase the above timber stumpage at the prices listed under ("My Total Bid/Species").

Applicant: _____ Date: _____


Application approved by: _____ Date: _____ Contract #: _____

(See map on back)

State Owned Lands
 TIMBER SALE PROSPECTUS
 TRACT # H0507
 Section 19, 30 T 40N R 7W
 Hunter Township, Sawyer County



Map Scale: 4" = 1 Mile
 Sale Acreage: 119 Ac.

Legend	
	Clearcut Area
	Select Cut Area
	Woods road/trail

STATE of WIS. DNR PROPERTIES
 TIMBER SALE PROSPECTUS
 TRACT # H 0108
 Sections 5,6,7,8 , T 37 N-R 7 W

Contact for Sale:
 Kim Lemke
 (715) 634-9658
 ext. 3506
 Hayward Service Center

<u>Species</u>	<u>Estimated Volume</u>	<u>Minimum Bid</u>	<u>My Bid By Species</u>	<u>Total</u>
White Pine	10 MBF	\$ 125.00/MBF	\$ _____/MBF	\$ _____.
Mixed Hardwood	95 cds	\$ 15.00/cd	\$ _____/cd	\$ _____.
Aspen	270 cds	\$ 20.00/cd	\$ _____/cd	\$ _____.
Red Pine	340 cds	\$ 29.10/cd	\$ _____/cd	\$ _____.
TOTAL BID VALUE				\$ _____.

The estimated red pine cordwood volume contains approximately 19 mbf of red pine logs, 15 cords of white pine, and 6 cords of balsam fir.

Harvesting Prescription Area A (select cut area)

Harvest all trees that have been individually marked with orange paint. In addition, harvest all aspen and white birch which are 5" or greater in diameter at D.B.H. Utilize all saw logs to a 9" top D.I.B., and all pulpwood to a 4" top D.I.B. Damage to the residual stand is also prohibited.


Harvesting Prescription Area B (Clear cut area)

Harvest all aspen, white birch, and mixed hardwoods. In addition sever all other remaining stems of these species greater than 2 inches. Cut any balsam fir with 3 or more sticks. Cut all orange marked red and white pine. Do not cut any oak. Utilize all pulpwood to 4 inch top D.I.B.

Integrated Resource Considerations

There will be a residual stand of evenly spaced, high quality northern hardwood and oak tree species to reduce the visual impact of this timber sale. All existing and future logging roads must be kept free of slash and logging debris. Any new forest road location or construction is subject to review and approval by the State Lands Forester. All slash or logging debris accumulated on the landings must be lopped and scattered. Equipment operation within any established Riparian Management Zone (RMZ), as indicated on the timber sale map, is prohibited. Depositing slash and/or logging debris in any wetland or RMZ is also prohibited. Decking of cut forest products will not be permitted on any town road right-of-way, unless prior approval by the town chairman has been granted. Care should be taken during the harvesting operation to minimize any detrimental effects to the soils. Before the timber sale is closed, all forest skid trails and logging roads used in the harvesting operation must be leveled.

State Lands Timber Sale
 Weigor Wildlife Area
 Sec. 5,6,7,8 T37N R7 W Sawyer County
 Tract H0108 Sale# _____ 47 Acres



TIMBER SALE PROSPECTUS
TRACT # H 03-08
Sections 1, 12, T 40 N-R 7

Contact for sale:
Kim Lemke
(715) 634-9658
ext. 3506

Species Bid/Unit	Estimated Volume	Minimum Bid	Cruiser Comments	Hayward Service Cen
aspen	1600 cds	\$20.00/cd		\$
Balsam fir	220 cds	\$20.00/cd		\$
Mixed hardwood	420 cds	\$15.00/cd		\$

Total Bid \$ _____

Harvesting Prescriptions:

Clear Cut Area Harvest all merchantable aspen, mixed hardwoods, with a DBH of 5 inches or greater, also harvest balsam fir with 2 or more sticks. In addition sever all residual stems 2 inches and larger of aspen and mixed hardwood types.


Aesthetic Zone Care should be taken during the harvesting operation to minimize any detrimental effects to the soils. Before the timber sale is closed, all forest skid trails and logging roads used in the harvesting operation must be leveled.

Integrated Resource Considerations -

All existing and future logging roads must be kept free of slash and logging debris. Any new forest road location or construction is subject to review and approval by the D.N.R. Forester. Depositing slash and/or logging debris in any wetland or RMZ is prohibited.

Special Note: Open all designated forest roads as indicated on map for future hiking and skiing trail.

State Lands Timber Sale
Chippewa Flowage Properties
Sec. 1, 12 T40N R7 W Sawyer County
Tract H0308 Sale# _____ 65 Acres



Open this section of road for future hiking and skiing trail

Legend

 Clearcut Area

4 inches = 1 mile

Eagles Nest Land

Popple Island

