

NH-ALSF TRACT NO. 29-16

Trout & Allequash Oak

Vilas County

Town 41 North, Range 7 East

Section 17 – SESW, SWSE

Section 19 – SESE

Section 20 – W1/2SW, SWNW, NENW, NWNE

Section 30 – NENE

No bid bond is required.

15% of the total sale bid value or \$1000.00, whichever is greater, will be required for performance bond.

The cutting area is approximately 100 acres.

The contract period is 3 years.

All trees that will yield one or more 100-inch sticks to a 4" top diameter will be cut and utilized.

ESTIMATED VOLUME (TONS)  
MINIMUM TOP DIAMETER

<u>Species</u>	<u>4"</u>	<u>Whole Tree</u>	<u>Advertised Price Per Unit</u>
White Pine <sup>1</sup>	200		\$ 17.60
Balsam Fir <sup>2</sup>	220		\$ 5.80
Red Oak	1000		\$ 9.90
Mixed Hardwood <sup>3</sup>	1100		\$ 12.40

ESTIMATED VOLUME (MBF)

Red Oak <sup>4</sup>	120	\$ 318.00
----------------------	-----	-----------

**Total Minimum Bid Value: \$ 66,496.00**

<sup>1</sup> Approximately 80% white pine, 20% red pine. Includes 17 MBF white pine and 5 MBF red pine sawtimber. (Wt. conv. 2.128 tons/cord)

<sup>2</sup> Approximately 67% balsam fir, 33% hemlock. Includes 2 MBF hemlock sawtimber. (Wt. conv. 2.209 tons/cord)

<sup>3</sup> Approximately 41% red maple, 25% hard maple, 21% white birch, 13% aspen, and less than 1% ironwood. (Wt. conv. 2.361 tons/cord)


<sup>4</sup> Approximately 96% red oak, 2% red maple, 1% hard maple, 1% white birch.

Note: Total sale volume equates to 32.5 tons/acre or 12.9 cords/acre.

Special Conditions:

1. **Harvest operations are not allowed in the Oak Recreation Area from April 15 through Labor Day weekend to minimize impacts to trail users as well as oak wilt risks. No harvesting activity allowed in the Oak Native Community Area from April 15 to July 15 to prevent oak wilt.**
2. Cutting must be concurrent for all species including non-merchantable trees where designated.
3. Do not cut, knock down or utilize any dead trees.
4. **Short-wood forwarding only within the entire sale.**
5. Slash must be lopped and/or scattered to lie within two feet of the ground and be pulled back 10' behind the tree line along all roads and trails concurrently with cutting.
6. Whole tree utilization or biomass harvesting is not allowed.
7. All pine products cut between May 1 and September 1 must be removed from the sale area within three weeks from time of cutting. Pine products cut during the remainder of the year must be removed prior to May 1 of each year.
8. **Skid trails crossing the blacktop bicycle trail must be kept to a minimum. Rubber tired equipment only on the bike trail where necessary. If using tracked equipment, protection of blacktop is required. Contractor will be responsible for any logging damage to the trail.**
9. Dense sapling pockets in some areas may be avoided during cutting operations with DNR forester approval.
10. Minimize damage of residual trees, saplings, and other brush within 25' of the bike trail for aesthetics.
11. No equipment allowed within any of the small wetlands to prevent soil compaction and rutting.

**WISCONSIN  
DEPARTMENT OF NATURAL RESOURCES  
TIMBER SALE  
TRACT 29-16 TROUT & ALLEQUASH OAK  
T41N R7E SECTIONS 17, 19, 20, & 30  
HARVEST ACRES - 100**



**Legend**

- Red Lines
- Blue Lines
- ⊗ Gates
- ⊕ Survey Markers
- ⊕ Section Corners
- Blacktop Bike Trail
- - - Woods Roads
- ▬ Town/County Roads
- Lakes
- Creeks
- Powerline



**Oak Recreation Area (66 acres):** Cut all merchantable aspen, white birch, balsam fir, maple, and orange marked trees. Cut all 2-5" maple concurrently and minimize damage to white pine saplings. Do not cut any green marked trees. No harvesting activity allowed from April 15 through Labor Day weekend.



**Oak Native Community Area (34 acres):** Cut all aspen, white birch, balsam fir, maple, and oak, except for those which are green marked. Also cut all trees marked with orange paint and all 1-5" aspen, white birch, and maple. Minimize damage to white pine and hemlock saplings. No harvesting activity allowed between April 15 & July 15.

N  
4" = 1 mile



Map produced by  
Adam Wallace, 8/16

This map is not a survey of  
the actual boundary of any  
property this map depicts.

This sale is contained within MgmL Area 3 - Vilas Sandy Plains North - Forest Production Area and  
MgmL Area 12 - Mixed Forest Native Community Area.