From: Timm P. Speerschneider <tps@dewittllp.com>

Sent: Tuesday, August 6, 2019 2:06 PM **To:** Schmoller, Michael R - DNR

Subject: RE: Hartmeyer Property- Recent soil sampling for lease obligations **Attachments:** REH Env Assessment Report Hartmeyer-Madison WI Final.pdf;

0582_001.pdf; 0584_001.pdf; 0585_001.pdf; All_Attachments().pdf(4)

Follow Up Flag: Follow up Flag Status: Completed

Here is the complete report—I have also attached the 2008 closure letters and a key map showing the areas where DRO exceeded 1000ppm(note that these areas are delineated in green on the Ramboll maps) from the closure request—it is not entirely clear as to the precise area to which the 2008 closure applies—I would note that it appears that there remain areas above industrial direct contact standards for the DRO constituents benzene and benzo-pyrene and benzo anthracene—I would also note the exceedances in the former coal storage area—I understand that these appear to be in areas that are not subject to the current closure request—I will give you a call to discuss-thanks, timm

Timm P. Speerschneider

Ph: 608.252.9319 tps@dewittllp.com

From: Schmoller, Michael R - DNR < <u>Michael.Schmoller@wisconsin.gov</u>>

Sent: Tuesday, August 06, 2019 10:09 AM

To: Timm P. Speerschneider < tps@dewittllp.com >

Subject: FW: Hartmeyer Property- Recent soil sampling for lease obligations

We are committed to service excellence.

Visit our survey at http://dnr.wi.gov/customersurvey to evaluate how I did.

R. Michael Schmoller Phone: 608-275-3303

Michael.schmoller@wisconsin.gov

From: Adam Streiffer <ASTREIFFER@ramboll.com>

Sent: Monday, June 17, 2019 8:52 AM

To: Schmoller, Michael R - DNR < Michael.Schmoller@wisconsin.gov

Cc: Adam Streiffer <ASTREIFFER@ramboll.com>; Susan Petrofske <SPETROFSKE@ramboll.com>; Erin

Veder <<u>ebantz@ramboll.com</u>>; Jennifer Nijman <<u>jn@nijmanfranzetti.com</u>> **Subject:** Hartmeyer Property- Recent soil sampling for lease obligations

Hi Mike,

In follow up to your recent email correspondence with Lynn Bradley with GEC, attached is the data from the recent soil sampling performed by Ramboll at the Hartmeyer site in April 2019. Also attached is a figure showing the boring locations. The sampling was conducted to satisfy terms of the lease between the John Hartmeyer Estate and Kraft Heinz. As such, the data in the attached table is only compared to applicable soil standards (i.e., industrial) based on zoning and land use during the lease term.

Two areas were assessed: the area of the 2008 AST closure (BRRTS #03-13-000053), and a previously unassessed area to the north and northwest that may have been historically filled and possibly associated with former coal storage. We did not further assess the area of the open AST case (BRRTS #02-13-580328) given the recent characterization work.

The April 2019 results appear to be generally consistent with soil data associated with the 2008 case closure and the open AST case. The compounds and concentrations appear to be generally consistent, and it does not appear that they are the result of a new release. Borings B-6 and B-7 are located a few hundred feet away from the nearest historic boring locations. However, these data also appear generally consistent with historic data, and may be attributed to the historic fill at the site. If deemed appropriate, Kraft Heinz would like to incorporate this data into one of the two existing BRRTS cases.

Please let us know if you have any questions or require any additional information at this time.

Thank you, **Adam Streiffer**

Senior Consultant 2

D 1-262-901-3506 M 1-504-723-0980 astreiffer@ramboll.com

Ramboll 175 North Corporate Drive Suite 160 Brookfield, WI 53045 USA

https://ramboll.com



State of Wisconsin \ DEPARTMENT OF NATURAL RESOURCES

Jim Doyle, Governor Matthew J. Frank, Secretary Lloyd L. Eagan, Regional Director South Central Region Headquarters 3911 Fish Hatchery Road Eltchburg, Wisconsin 53711-5397 Telephone 608-275-3266 FAX 608-275-3338 TTTY Access via relay - 711

January 23, 2008

File Ref: 03-13-00053

Mr. Robert Sherman Kraft Global - Oscar Mayer Foods 910 Mayer Avenue Madison, WI 53704-4287

Subject: Closure, Oscar Mayer - Hartmeyer Aboveground Storage Tank (AST), 2007 Roth Street & 1900 Commercial Street, Madison, WI

Dear Mr. Sherman:

On September 24, 2007, the South Central Region Closure Committee reviewed your request for closure of the case described above. The South Central Region Closure Committee reviews environmental remediation cases for compliance with state rules and statutes to maintain consistency in the closure of these cases. On October 4, 2007, you were notified that the Closure Committee had granted conditional closure to this case.

On December 3, 2007, the Department received correspondence indicating that you have complied with the requirements of closure. The groundwater monitoring wells (24) have been properly abandoned and the soil cuttings (8 drums) have been properly disposed of.

Based on the correspondence and data provided, it appears that your case meets the requirements of ch. NR 726, Wisconsin Administrative Code. The Department considers this case closed and no further investigation or remediation is required at this time.

Please be aware that this case may be reopened pursuant to s. NR 726.09, Wisconsin Administrative Code, if additional information regarding site conditions indicates that contamination on or from the site poses a threat to public health, safety or welfare, or the environment.

GIS Registry

The conditions of case closure set out below in this letter require that your site be listed on the Remediation and Redevelopment Program's GIS Registry. The specific reasons are summarized below:

- Residual soil contamination exists that must be properly managed should it be excavated or removed.
- Groundwater contamination is present above Chapter NR 140 enforcement standards.



Information that was submitted with your closure request application will be included on the GIS Registry. To review the sites on the GIS Registry web page, visit the RR Sites Map page at: http://dnr.wi.gov/org/aw/rr/gis/index.htm. If your property is listed on the GIS Registry because of remaining contamination and you intend to construct or reconstruct a well, you will need prior Department approval in accordance with s. NR 812.09(4)(w), Wis. Adm. Code. To obtain approval, Form 3300-254 needs to be completed and submitted to the DNR Drinking and Groundwater program's regional water supply specialist. This form can be obtained on-line http://dnr.wi.gov/org/water/dwg/3300254.pdf or at the web address listed above for the GIS Registry.

Remaining Residual Groundwater Contamination

Groundwater impacted by petroleum contamination greater than enforcement standards set forth in ch. NR140, Wis. Adm. Code, is present both on the contaminated property and off the contaminated property. Off-property owners have been notified of the presence of groundwater contamination. For more detailed information regarding the locations where groundwater samples have been collected (i.e., monitoring well locations) and the associated contaminant concentrations, refer to the Remediation and Redevelopment Program's GIS Registry at http://dnr.wi.gov/org/aw/rr/gis/index.htm.

The Department appreciates your efforts to restore the environment at this site. If you have any questions regarding this closure decision or anything outlined in this letter, please contact me at telephone number shown below.

Sincerely,

Dino Tsoris, P.G.

Hydrogeologist

Remediation & Redevelopment Program

South Central Region

Wisconsin Department of Natural Resources

Telephone: (608) 275-3299

CC:

Mr. John Tweddale, BT2, Inc., 2830 Dairy Drive, Madison, WI53718-6751

Ms. Andrea H. Johns, P.O. 833374, Richardson, TX 75083

John Hartmeyer Estate, C/O John Pike and J.R. Pike Corporation,

433 Woodward Drive, Madison, WI 53704-1529

Mr. Timm P. Speerschneider, DeWitt Ross & Stevens, Two East Mifflin Street,

Suite 600, Madison, WI 53703-2865

Mr. William M. Tuttle, Canadian Pacific Railway, 501 Marquette Avenue S.,

Minneapolis, MN 55402



State of Wisconsin \ DEPARTMENT OF NATURAL RESOURCES

Jim Doyle, Governor Matthew J. Frank, Secretary Lloyd L. Eagan, Regional Director

South Central Region Headquarters 3911 Fish Hatchery Road Fitchburg, Wisconsin 53711-5397 Telephone 608-275-3266 FAX 608-275-3338 TTY Access via relay - 711

October 4, 2007

File Ref: 03-13-000053

Mr. Robert Sherman Kraft Global Oscar Mayer Foods, Inc. 910 Mayer Avenue Madison, WI 54704-4287

Subject: Conditional Closure Decision with Requirements to Achieve Final Closure,
Oscar Mayer - Hartmeyer Aboveground Storage Tank Area,
2007 Roth Street & 1900 Commercial Street, Madison, WI

Dear Mr. Sherman:

On September 24, 2007, the South Central Region Closure Committee reviewed your request for closure of the case described above. The South Central Region Closure Committee reviews environmental remediation cases for compliance with state rules and statutes to maintain consistency in the closure of these cases. After careful review of the closure request, the Closure Committee has determined that the residual fuel oil petroleum contamination originating from the distribution lines associated with the aboveground storage tank area located on the Hartmeyer property appears to have been investigated and remediated to the extent practicable under site conditions. Your case has been remediated to Department standards in accordance with s. NR 726.05, Wis. Adm. Code and will be closed if the following conditions are satisfied:

MONITORING WELL ABANDONMENT

The monitoring wells and temporary wells at the site must be properly abandoned in compliance with ch. NR 141, Wis. Adm. Code. Documentation of well abandonment must be submitted to Dino Tsoris on Form 3300-5B found at www.dnr.state.wi.us/org/water/dwg/gw/ or provided by the Department of Natural Resources.

PURGE WATER, WASTE AND SOIL PILE REMOVAL

Any remaining purge water, waste and/or soil piles generated as part of site investigation or remediation activities must be removed from the site and disposed of or treated in accordance with Department of Natural Resources' rules. Once that work is completed, please send appropriate documentation regarding the treatment or disposal of the remaining purge water, waste and/or soil piles.

RIGHT-OF-WAY SOIL AND/OR GROUNDWATER CONTAMINATION

There is residual soil and/or groundwater contamination exists on the Hartmeyer property and the Canadian Pacific Railroad right-of-way at this site. Section NR 726.05(2)(a)4, Wis. Adm. Code, requires you to provide written notification of the presence of residual soil and



groundwater contamination to the Canadian Pacific Railroad where the right-of-way is located. Section NR 726.05(2)(b)4, Wis. Adm. Code, requires you to also provide written notice of the presence of residual groundwater contamination to the owner of any properties that you do not own within this site that do not have soil contamination if they are affected by groundwater contamination. These notifications were sent in October 2006. The affected property owners are advised that excavation of potentially contaminated soil or groundwater may pose inhalation or other direct contact hazards and will require soil and groundwater sampling and analysis, as well as proper storage, treatment, or disposal of any excavated materials, based upon the results of the analysis.

When the above conditions have been satisfied, please submit the appropriate documentation (for example, well abandonment forms, disposal receipts, copies of correspondence, etc.) to verify that applicable conditions have been met, and your case will be closed. Your site will be listed on the DNR Remediation and Redevelopment GIS Registry of Closed Remediation Sites. Information that was submitted with your closure request application will be included on the GIS Registry. To review the site on the GIS Registry web page, visit http://maps.dnr.state.wi.us/brrts.

Please be aware that the case may be reopened pursuant to s. NR 726.09, Wis. Adm. Code, if additional information regarding site conditions indicates that contamination on or from the site poses a threat to public health, safety, or welfare or to the environment.

We appreciate your efforts to restore the environment at this site. If you have any questions regarding this letter, please contact me at the telephone number shown below.

Sincerely.

Dino Tsoris, P.G.

Hydrogeologist

Remediation & Redevelopment Program

South Central Region

Wisconsin Department of Natural Resources

Telephone: (608) 275-3299

Mr. John Tweddale, BT2, Inc., 2830 Dairy Drive, Madison, WI53718-6751 CC:

Ms. Andrea H. Johns, P.O. 833374, Richardson, TX 75083

John Hartmeyer Estate, C/O John Pike and J.R. Pike Corporation,

433 Woodward Drive, Madison, WI 53704-1529

Mr. Timm P. Speerschneider, DeWitt Ross & Stevens, Two East Mifflin Street,

Suite 600, Madison, WI 53703-2865

Mr. William M. Tuttle, Canadian Pacific Railway, 501 Marquette Avenue S., Minneapolis, MN 55402


PARCEL IDENTIFICATION NUMBERS

Hartmeyer – Aboveground Storage Tank Area 2007 Roth Street, Madison, Wisconsin

Hartmeyer Estate Property – 0810-313-0099-0

Canadian Pacific Railways Property (right-of-way) - 0810-313-0081-7






HARTMEYER PROPERTY

- ABOVEGROUND FUEL OIL STORAGE TANK

FORMER ABOVEGROUND FUEL DIL STORAGE TANK (REMOVED 2001)





BENZENE > IND STO BO) P(& B(O) A) > IND STO(O)




Table C-1
DRO, GRO, and PVOC Concentrations in Soil
Hartmeyer AST Area / Project #1624

(Results are in µg/kg, except where noted otherwise)

Sample	Date	Depth (feet)	PID	Lab Notes	DRO (mg/kg)	GRO (mg/kg)	Benzene	Ethylbenzene	Toluene	Xylenes	1,2,4-TMB	1,3,5-TMB	МТВЕ
GB101 S1	6/12/01	2	1.9	(1)	612	NA	<36	42	42	<110	36	<36	<36
GB101 S5	6/12/01	9	0.3	<u> </u>	28	NA	NA	NA	NA	NA	NA	NA ^a	NA
GB102 S1	6/12/01	2	10.6	(2)	5,170	NA	270	1,250	886	1,220	443	210	<92
GB102 S4	6/12/01	8	1.9	**	9.6	NA	NA	NA	NA	NA	NA	NA	NA
GB103 S1	6/12/01	1	0.3		163	NA	45	80	39	<100	51	<34	<34
GB103 S6	6/12/01	12	18.5	***	78	NA	NA	NA	NA	NA	NA	NA	NA
GB104 S1	6/12/01	1	1.1	Visit	966	NA	79	152	67	178	99	57	<32
GB104 S5	6/12/01	9	4.3		<7.7	NA	NA	NA	NA	NA	NA	NA	NA
GB105 S1	6/12/01	1	1.9	(2)	713	NA	34	178	88	329	274	110	<34
GB105 S3	6/12/01	6	5.1		68	NA	NA	NA	NA	NA	NA	NA	NA
GB106 S2	6/12/01	4	1.1	(2)	1,850	NA	33	79	65	198	120	48	<33
GB106 S4	6/12/01	8	9.0		11	NA	NA	NA	NA	NA	NA	NA	NA
GB107 S2	6/12/01	4	0.3	1240	1,050	NA	<30	<30	<30	<89	<30	<30	<30
GB107 S4	6/12/01	8	82	*	1,320	NA	NA	NA	NA	NA	NA	NA	NA
GB108 S1	6/12/01	1	1.1		1,410	NA	32	46	54	128	66	<32	<32
GB108 S4	6/12/01	8	1.1	***	12	NA	NA	NA	NA	NA	NA	NA	NA
GB109 S1	6/12/01	2	72	(2)	1,610	NA	47	323	186	720	546	136	<31
GB109 S4	6/12/01	8	81	(3)	20	NA	NA	NA	NA	NA	NA	NA	NA
GB110 S2	6/13/01	4	0		9.1	NA	<40	<40	<40	<120	<40	<40	<40
GB110 S4	6/13/01	7	0.8	21	<6.2	NA	NA	NA	NA	NA	NA	NA	NA
GB111 S2	6/13/01	4	0	(1)	65	NA	65	140	234	315	110	<29	<29
GB111 S4	6/13/01	8	0	77	<6.4	NA	NA	NA	NA	NA	NA	NA	NA

Table C-1 (Continued)
DRO, GRO, and PVOC Concentrations in Soil

Sample	Date	Depth (feet)	PID	Lab Notes	DRO (mg/kg)	GRO (mg/kg)	Benzene	Ethylbenzene	Toluene	Xylenes	1,2,4-TMB	1,3,5-TMB	МТВЕ
GB112 S2	6/13/01	4	0	***	83	NA	<30	<30	<30	<89	<30	<30	<30
GB112 S4	6/13/01	8	0		<6.3	NA	NA	NA	NA	NA	NA	NA	NA
GB113 S2	6/13/01	4	0	(1)	58	NA	<29	46	<29	99	62	<29	<29
GB113 S4	6/13/01	8	0	-	<6.3	NA	NA	NA	NA	NA	NA	NA	NA
GB114 S2	6/13/01	4	152	(2)	168	NA	<65	323	<65	258	748	348	<65
GB114 S4	6/13/01	8	6	3 50 3	11	NA	NA	NA	NA	NA	NA	NA	NA
GB115 S2	6/13/01	4	47	(4)	4,060	NA	<148	1,720	172	530	2,590	<148	<148
GB116 S1	6/13/01	1	1.6	(1)	9,580	NA	72	126	120	189	110	48	<32
GB116 S4	6/13/01	8	2.4		<6.3	NA	NA	NA	NA	NA	NA	NA	NA
GB117 S2	6/13/01	4	1.6	(2)	5,010	NA	<626	3,250	<626	<1,880	12,300	5,010	<626
GB117 S4	6/13/01	8	152		10,200	NA	NA	NA	NA_	NA	NA	NA	NA
GB118 S1	6/13/01	1	1.6	(2)	2,410	NA	265	361	710	1,010	409	84	<30
GB118 S4	6/13/01	8	37		46	NA	NA	NA	NA	NA	NA	NA	NA
GB119 S1	6/13/01	1	0.8		39	NA	<35	<35	<35	<110	<35	<35	<35
GB119 S4	6/13/01	8	0.8	22	<6.6	NA	NA	NA	NA	NA	NA	NA	NA
GB120 S2	6/14/01	4	0.8	1	25	NA	<36	<36	<36	<110	<36	<36	<36
GB120 S4	6/14/01	8	55		1,910	NA	NA	NA	NA	NA	NA	NA	NA
GB121 S2	6/14/01	4	60	(2)	1,020	NA	<63	514	<63	<188	3,630	977	<63
GB121 S4	6/14/01	8	115	**	821	NA	NA	NA	NA	NA	NA	NA	NA
GB122 S2	6/14/01	4	0.8		<5.0	NA	<25	<25	<25	<75	<25	<25	<25
GB122 S4	6/14/01	8	0.8		<5.7	NA	NA	NA	NA	NA	NA	NA	NA
GB123 S2	6/14/01	4	0.8		<6.5	NA	<33	<33	<33	<98	<33	<33	<33
GB123 S4	6/14/01	8	0.8		<6.2	NA	NA	NA	NA	NA	NA	NA	NA

Table C-1 (Continued)
DRO, GRO, and PVOC Concentrations in Soil

Sample	Date	Depth (feet)	PID	Lab Notes	DRO (mg/kg)	GRO (mg/kg)	Benzene	Ethylbenzene	Toluene	Xylenes	1,2,4-TMB	1,3,5-TMB	МТВЕ
GB124 S2	6/14/01	4	10	(1)	130	NA	292	358	45	186	212	33	<33
GB124 S4	6/14/01	8	0.8		<5.9	NA	NA	NA	NA	NA	NA	NA	NA
GB125 S2	6/14/01	4	0.8	***	110	NA	65	285	298	570	130	<32	<32
GB125 S4	6/14/01	8	0		86	NA	NA	NA	NA	NA	NA	NA	NA
GB126 S2	6/14/04	4	120	(2)	13,100	NA	<594	1,190	<594	<1,780	903	<594	<594
GB126 S4	6/14/01	8	78		12,900	NA	NA	NA	NA	NA	NA	NA	NA
GB127 S1	6/14/01	2	0	(1)	68	NA	<32	<32	<32	<96	<32	<32	<32
GB127 S4	6/14/01	7.5	0		79	NA	NA	NA	NA	NA	NA	NA	NA NA
GB128 S1	6/15/01	1	1.3	(5)	516	NA	70	251	212	357	265	66	<33
GB128 S4	6/15/01	8	1.3	(6)	<5.9	NA	NA	NA	NA	NA	NA	NA	NA NA
GB129 S2	6/15/01	4	2.2	(6)	<8.9	NA	<45	<45	<45	<130	<45	<45	<45
GB129 S4	6/15/01	8	2.2	(6)	<6.1	NA	NA	NA	NA	NA	NA	NA	NA
GB130 S2	6/15/01	4	2.2	(7)	4,540	NA	58	71	57	100	45	<32	<32
GB130 S4	6/15/01	8	1.3	(6)	12	NA	NA	NA	NA	NA	NA	NA	NA
GB131 S2	6/15/01	4	0.8	7	160	NA	<29	110	33	94	50	<29	<29
GB131 S4	6/15/01	8	2.2	(6)	58	NA	NA	NA	NA	NA	NA	NA	NA NA
B132 S1	8/13/01	2	0.6		388	6.7	52	110	<32	155	100	41	44
B133 S1	8/13/01	3	8	(4)	2,640	7.4	<29	39	32	161	97	<29	<29
B134 S1	8/13/01	3	14	(8)	609	67	60	<31	35	634	<31	186	<31
B135 S1	8/13/01	3	327	(1)	255	267	911	729	960	1,460	583	<304	<304
MW10 S1	8/13/01	3	0.6	:77	<6.4	<6.4	<32	<32	<32	<96	<32	<32	<32
MW12 SI	8/13/01	3	15		649	169	<32	43	<32	<97	480	<52	<32
MW15 S3	8/14/01	8	0.6	277	<7.9	<7.9	<39	<39	<39	<120	<39	<39	<39

Table C-1 (Continued) DRO, GRO, and PVOC Concentrations in Soil

Sample	Date	Depth (feet)	PID	Lab Notes	DRO (mg/kg)	GRO (mg/kg)	Benzene	Ethylbenzene	Toluene	Xylenes	1,2,4-TMB	1,3,5-TMB	МТВЕ
MW16 S3	8/14/01	8	0.6		<6.8	<6.8	<34	<34	<34	<100	<34	<34	<34
MeOH	6/12/01				NA	NA	<25	<25	<25	<75	<25	<25	<25
Blank	6/14/01	#*:		**	NA	NA	<25	<25	<25	<75	<25	<25	<25
	6/15/01		#	44	NA	NA	<25	<25	<25	<75	<25	<25	<25
	8/13/01	(111)	4		NA	<5.0	<25	<25	<25	<75	<25	<25	<25
	8/14/01		<u>1200</u>	-	NA	<5.0	<25	<25	<25	<75	<25	<25	<25
NR 720 Gene	eric Soil Clear	up Standard	ds		100	100	5.5	2,900	1,500	4,100	NE	NE	NE
NR 746 Table in soil pores	e 1 - Indicator	s of residua	l petroleun	n product	NE	NE	8,500	4,600	38,000	42,000	83,000	11,000	NE
	e 2 - Protectio contaminated		health from	n direct	NE	NE	1,100	NE	NE	NE	NE	NE	NE

ABBREVIATIONS:

AST = Aboveground Storage Tank
TMB = Trimethylbenzene

PID = Photo-ionization Detector MTBE = Methyl-tert-butyl ether

DRO = Diesel Range Organics NA = Not Analyzed

GRO = Gasoline Range Organics
NE = No Standard Established

NOTE:

Bold values exceed NR 720 generic soil cleanup standards.

LABORATORY NOTES:

- (1) DRO analysis Late eluting hydrocarbons present.
- (2) PVOCs analysis Late eluting hydrocarbons present.
- (3) DRO analysis Improperly handled sample.
- (4) PVOCs and DRO analyses Late eluting hydrocarbons present.
- DRO and GRO analyses Late eluting hydrocarbons present. DRO analysis Received past hold time; this sample was extracted more than three days after sample collection. WDNR has extended the hold time for extraction to 10 days, but this has not yet been Codified.
- DRO analysis Received past hold time; this sample was extracted more than three days after sample collection. WDNR has extended the hold time for extraction to 10 days, but this has not yet been Codified.
- PVOCs analysis Late eluting hydrocarbons present. DRO analysis Received past hold time; this sample was extracted more than three days after sample collection. WDNR has extended the hold time for extraction to 10 days, but this has not yet been Codified.
- (8) PVOCs analysis Late eluting hydrocarbons present and does not match typical pattern.

By: LH Date: 7/12/01 Rev. By: LH Date: 8/31/01 Checked: JM Date: 7/16/01 I:\1624\Tables-General\Tables.wpd



ENVIRONMENT & HEALTH

Via E-Mail: jn@nijmanfranzetti.com

Ms. Jennifer T. Nijman Nijman Franzetti LLP 10 S. LaSalle Street, Suite 3600 Chicago, IL 60603 Privileged and Confidential

Prepared at the Request of Counsel

ENVIRONMENTAL ASSESSMENT REPORT HARTMEYER PROPERTY MADISON, WISCONSIN

Dear Ms. Nijman:

Ramboll US Corporation (Ramboll), on behalf of the Kraft Heinz Food Company (Kraft Heinz or the "Client"), conducted an environmental assessment, as specified in the Ground Lease by and between John Hartmeyer Estate ("Landlord") and Oscar Mayer Foods Corp., dated June 1, 1994, as amended ("Lease") at the Hartmeyer property located at 2007 Roth Street in Madison, Wisconsin (herein referred to as the "property" or "site"). The site location is depicted on Figure 1. The following provides a summary of the site background, subsurface assessment activities, investigation results, conclusions, and recommendations.

July 29, 2019

Ramboll 175 North Corporate Drive Suite 160 Brookfield, WI 53045 USA

T +1 262 901 0099 F +1 262 901 0079 www.ramboll.com

Ref. 1690012791

BACKGROUND

The Lease between Kraft Heinz and the Landlord requires that an environmental assessment be conducted to determine if any applicable State of Wisconsin soil clean-up standard is exceeded due to Kraft Heinz's use of the property. As such, in anticipation of the Lease termination on May 31, 2019, which was subsequently extended until November 30, 2019, Ramboll was asked to develop a scope of work as required in the Lease to "determine if any applicable State of Wisconsin soil clean-up standard is exceeded" due directly and solely to tenant's use of the property. The property is zoned M1/M2 (light manufacturing/heavy manufacturing). Thus, applicable soil clean-up standards are for industrial property. In preparing the sampling work plan, Ramboll conducted a review of available historical records and site investigation documents to identify potential areas of concern relating to tenant's use; the summary of which is provided below.

Site History

The site was marshland with railroad tracks present along the east and west property boundaries and a roadway traversing the property by 1892. By 1906, a farmstead with a farmhouse was present on the western portion of the property. There is no readily available information on the use of the site between the 1900s and early 1940s. Marshland is not apparent at the site on the aerial photograph from 1937 suggesting that the site was filled. By 1942, the northeastern portion of the property was in use as a slaughterhouse and feed warehouse. By 1962, the former slaughterhouse had been removed. According to the current Lease agreement, Oscar Mayer began leasing a portion of the site in 1954 and the remaining portion of the site in 1966.



Coal storage activities appear to have occurred in the location of the former slaughterhouse in the 1960s and may have continued in some form until approximately the 1980s or 1990s. By 1974, two fuel oil aboveground storage tanks (ASTs) were located on the southeast portion of the property; based on available information, the ASTs provided fuel oil for the adjacent Oscar Mayer facility. The western and central portions of the property were used as a park and baseball fields from the 1960s to the 1990s, and the northeastern portion of the property was used as a parking lot starting in the late 1960s. The fuel oil ASTs were removed in 2001 and 2016, respectively.

Prior Site Investigation and Assessment Activities

Based on the information provided to Ramboll, several site assessment, investigation, and remedial activities have been conducted on site, as discussed below.

• Bureau for Remediation and Redevelopment Tracking System (BRRTS) No. 03-13-000053 - Closed Leaking Underground Storage Tank (LUST): In February 1989, Oscar Mayer notified the Wisconsin Department of Natural Resources (WDNR) of a release of approximately 14,000 gallons of fuel oil from underground piping that serviced the ASTs located on the leased Hartmeyer property. Initial spill response activities included the recovery of approximately 8,000 gallons of fuel oil from the ground surface and trenches. A report describing the removal efforts was submitted to the WDNR in 1989 by Dames and Moore. A subsequent investigation was conducted to evaluate the extent of soil and groundwater contamination associated with releases of fuel from the AST piping.

Additional soil sampling and monitoring well installation was performed in 2001, including the advancement of 35 soil borings and 7 monitoring wells. These additional investigations were focused on evaluation of shallow soil impacts and delineation of the extent of free product. The primary indicator of impacts was determined to be total petroleum hydrocarbons-diesel range organics (TPH-DRO), which ranged from non-detect to 13,100 milligrams per kilogram (mg/kg). Some polycyclic aromatic hydrocarbons (PAHs) were also detected in this area, but because they did not correlate well with the TPH-DRO impacts, BT², Inc. (the consultant at the time) concluded that the PAH impacts were related to historical use of the property for coal storage and a railway. The 250,000-gallon fuel oil AST in this area was removed in 2001.

The most recent soil data (from June 2001) identified DRO, benzene, and ethylbenzene in soil above Wisconsin Administrative Code (WAC) NR 720 Generic Soil Cleanup Standards in place at the time. In addition, PAHs benzo(a)anthracene and benzo(a)pyrene were detected in soil above the interim generic industrial direct contact Residual Contaminant Level (RCLs), and PAHs 1-methylnaphthalene, 2-methylnaphthalene, naphthalene, phenanthrene, and pyrene exceeded the groundwater pathway RCL at the time.

Groundwater monitoring of 14 wells and removal of free product from MW-5 took place from 2000 to 2006. During that time, WAC NR 140 Enforcement Standards (ES) exceedances were only observed in MW-5. Based on the results of the groundwater monitoring and the closure of the production wells (on the adjacent Oscar Mayer property), Oscar Mayer requested closure in October 2006. In response to the closure request, the WDNR requested additional delineation. After performing additional monitoring and delineation, the WDNR approved final closure on January 23, 2008, with certain restrictions/conditions placed on the property, including listing in the WDNR GIS registry, proper management of any contaminated soil that is excavated or removed, and requirement for WDNR's approval prior to installing any wells at the property.



• BRRTS No. 02-13-580328 - Open Environmental Repair Program (ERP) Site: A Site Investigation was performed by General Engineering Company (GEC) at the site due to a release from the AST system discovered during the removal of the remaining (southern) AST and the associated pump house (formerly located beyond the northern portion of the berm area) in September 2016. Investigation activities to delineate the horizontal and vertical extent of affected soil and groundwater contamination were conducted in 2016 and 2017 and included the advancement of twenty test pits and six soil borings, four of which were converted to groundwater monitoring wells.

Eight test pits (TP-1 through TP-8) were installed at the site in September 2016. Soil samples were collected from each test pit and analyzed for petroleum-related volatile organic compounds (PVOCs) and naphthalene. Results indicated that benzene and naphthalene were present in several samples above the WAC NR 720 groundwater pathway RCLs. A remedial excavation was subsequently completed in October 2016 within the area of the former pump house and extended to the north and west. Approximately 464 tons of petroleum-contaminated soils were removed and sent for off-site disposal. Ten soil samples were collected from the sidewalls and bottom of the excavation and submitted for laboratory analysis of PVOCs and naphthalene. Results indicated concentrations of benzene, 1,2,4-trimethylbenzene and/or naphthalene exceeded the WAC NR 720 groundwater pathway RCLs in several samples.

Subsequently, in April and June 2017, six soil borings (B-1 to B-6) were advanced at the site, four of which were converted to monitoring wells (MW-1 to MW-4) and twelve additional test pits were installed (TP-1A to TP-12A). Soil and groundwater samples were collected from the borings, test pits, and wells, and a selection were submitted for laboratory analysis for PVOCs and naphthalene. Soil samples from three borings (B-3, B-4, and B-5) contained PVOCs and naphthalene at concentrations exceeding their respective WAC NR 720 groundwater pathway RCLs. The highest concentrations were detected in B-4 at a depth of 4 to 5 feet; namely benzene (1,260 micrograms per kilogram [μ g/kg]), ethylbenzene (4,100 μ g/kg), naphthalene (17,600 μ g/kg), 1,2,4 trimethylbenzene (7,200 μ g/kg), and 1,3,5 trimethylbenzene (1,800 μ g/kg), which exceeded their respective WAC NR 720 groundwater pathway RCLs. Test pit samples collected from TP-1A at a depth of 5 to 6 feet, TP-7A at a depth of 4 to 5 feet and TP-12A at a depth of 4 to 5 feet contained benzene and/or naphthalene above their groundwater pathway RCLs.

Groundwater was encountered in the monitoring wells at depths between 2.45 to 4.12 feet below ground surface (bgs), and groundwater flow in the vicinity of the former ASTs was determined to be toward the south/southeast.

Site investigation results were submitted to the WDNR in a report dated December 5, 2017. The report concludes that the extent of the impacts have been adequately defined based on the site investigation work performed to date, and the source has been removed. None of the confirmation samples collected from the upper 4 feet of soil contained PVOCs or naphthalene at concentrations exceeding the WAC NR 720 direct contact RCLs, and observed concentrations in groundwater did not exceed WAC NR 140 ESs.

Based on these results, Kraft Heinz is seeking regulatory closure for this former release. A closure request packet for this matter was submitted to the WDNR in May 2019, with proposed continuing obligations for the residual contamination.

In addition, two additional BRRTS cases are listed as associated with the property and appear to be related to Case No. 02-13-580328. Case No. 04-13-578986 is listed in BRRTS as a spill with closed status and was



opened in September 2016 and closed in March 2017. Case No. 02-13-579045 is listed in BRRTS as an ERP with open status related to a March 2017 notification of diesel fuel soil contamination.

Known and Potential Environmental Issues Associated with Lease Requirements

Based on the review of historical records and prior site investigation reports, the following known and potential areas of concern potentially associated with Kraft Heinz's Lease of the site were identified:

- **Historical Coal Storage:** Historical coal storage appears to have occurred on the eastern portion of the property from approximately the early 1960s until to the 1980s or 1990s. In 2002, fill containing cinders, coal, and fly ash was identified in soil borings advanced in the former AST area. Certain PAHs were detected in soil near the former AST area at concentrations above the criteria applicable at that time and were attributed to possible coal storage and the adjacent railway. The constituents in the railway area may not be related to Kraft Heinz's use of the property. Given the long-term use of this property, it is possible that coal storage activities took place prior to Kraft Heinz's use of the property.
- Areas of Known Soil Contamination as Part of Historical Closure Activities: As discussed above, TPH-DRO and PVOCs above then applicable WAC NR 720 Generic Soil Cleanup Standards and PAHs above the then applicable interim generic industrial direct contact RCLs and groundwater pathway RCLs were left in place following approval and closure from the WDNR in 2008. In addition, naphthalene and PVOCs remain in soil (below 4 feet depth) above the WAC NR 720 groundwater pathway RCLs associated with the 2016 incident. Residual soil contamination located in the railroad right-a-way are not related to Kraft Heinz and not of concern for this Environmental Assessment. Ramboll performed an updated assessment of the soil conditions from the 2008 closure to determine whether the contamination above current regulatory criteria remains present in these areas. Given the recent characterization of soils associated with the 2016 incident, additional assessment of this area was not required.

SUBSURFACE INVESTIGATION ACTIVITIES

Ramboll conducted a subsurface investigation in April 2019 to evaluate soil conditions in the 2008 historical closure area and the area of former coal storage activities.

The subsurface investigation activities consisted of advancing a total of eight soil borings (B-1 through B-8) and collecting soil samples for laboratory analysis. Soil borings B-1 through B-4 were advanced in the areas of known soil contamination that were granted regulatory closure by the WDNR in 2008 (i.e., the "2008 closure areas"). Soil borings B-5 through B-8 were advanced in the former coal storage area, as determined from historical sources. The soil boring locations are depicted on Figure 2.

Soil Boring Advancement

Soil borings B-1 through B-8 were advanced on April 16, 2019, utilizing direct push technology (DPT) with a Geoprobe® drill rig with a 2-inch diameter drive rod to depths of approximately 5 feet bgs. Soil samples were continuously collected from each soil boring and divided for field screening, laboratory analysis, and infield classification (noting soil types, moisture, and staining or odors, if any). The soil samples were field screened for organic vapors using a calibrated photoionization detector (PID) equipped with a 10.6 electron volt (eV) lamp. The PID was calibrated according to manufacturer's instructions, using 100 parts per million (ppm) isobutylene span gas and air (zero gas) and checked between each screening event for proper response. Up to two soil samples were collected from each soil boring for laboratory analysis. One soil sample was collected from each boring at the interval with the highest PID reading. If the highest PID



reading was measured at a depth at or just below the water table, a second (unsaturated) soil sample was collected from above the water table (within the direct contact zone of 0 to 4 feet bgs).

Soil descriptions and PID readings are presented on the soil boring logs, which are included as Attachment A. Following soil sample collection activities, each boring location was appropriately abandoned by backfilling with hydrated bentonite. Borehole abandonment forms are also included in Attachment A.

Soil Sampling and Analysis

Up to two soil samples were collected from each soil boring for laboratory analysis. All soil samples collected during the investigation were submitted following standard chain of custody procedures to Pace Analytical Services, Inc. (Pace), a Wisconsin certified laboratory, in Green Bay, Wisconsin, for laboratory analysis. Soil samples collected from the 2008 closure areas (B-1 through B-4) were analyzed for PVOCs using United States Environmental Protection Agency (USEPA) Method 8260 and PAHs using USEPA Method 8270. Soil samples collected from the former coal storage area (B-5 through B-8) were analyzed for PVOCs, PAHs, and 8 Resource Conservation and Recovery Act (RCRA) metals via USEPA Methods 6010/7471.

INVESTIGATION RESULTS

Geology and Hydrogeology

The site investigation area was underlain by approximately 2 to 4.5 feet of brown/black sand and gravely sand fill with a black, fine grained flat stone resembling shale intermixed in this layer at B-6 and B-7. This fill layer was underlain by brown/black silt and clayey silt fill with varying amounts of sand, gravel and organics to the terminal depth of each soil boring (approximately 5 feet bgs).

Areas of black soils and mild petroleum odors were observed in the black silty fill layer at depths of approximately 3 to 5 feet bgs in soil borings B-1, B-2, and B-3 located in the 2008 closure area. PID readings collected from this layer in these soil borings ranged from 4.9 to 12.9 instrument units (IU) with the highest PID reading recorded at approximately 4 to 5 feet bgs in soil boring B-2. No visual/olfactory evidence of contamination was observed in the remainder of the soil borings and maximum PID readings at these locations (B-4 to B-8) ranged from 2.6 to 5.2 IU. Saturated soils were encountered in all eight soil borings at approximately 2 to 4 feet bgs, indicating a shallow groundwater table, consistent with historical site investigations. The soil boring logs are provided in Attachment A.

Soil Results

Laboratory analytical results of soil samples collected in April 2019 are summarized in Table 1 and compared to the applicable WAC NR 720 RCLs. Sample locations are shown on Figure 2. The laboratory analytical report is provided in Attachment B.

PVOCs

PVOC were detected at concentrations exceeding groundwater pathway RCLs in three soil samples: B-2 (4-5'), B-3 (4-5'), and B-5 (4-5').



Specifically, benzene was detected above the groundwater pathway RCL of 5.1 μ g/kg in B-3 (4-5') and B-5 (4-5') at concentrations of 71.8 J¹ μ g/kg and 37.0 J μ g/kg, respectively. Five PVOCs were detected in B-2 (4-5') above groundwater pathway RCLs; namely ethylbenzene at 7,400 μ g/kg (above the RCL of 1,570 μ g/kg), naphthalene at 3,440 μ g/kg (above the RCL of 658.2 μ g/kg), 1,2,4-trimethylbenzene at 30,500 μ g/kg (above the RCL of 1,378.7 μ g/kg), 1,3,5-trimethylbenzene at 7,900 μ g/kg (above the RCL of 1,378.7 μ g/kg), and xylene at 38,500 μ g/kg (above the RCL of 3,960 μ g/kg). No other soil samples contained concentrations of PVOCs above the applicable groundwater pathway RCLs. Additionally, none of the detected PVOC concentrations exceeded the applicable WAC NR 720 industrial direct contact RCL in samples collected within the direct contact zone (0 to 4 feet bgs). PVOCs were not detected above laboratory detection limits in soil samples collected from B-3 (1-2'), B-5 (1-2.5'), and B-8 (1-2.5').

<u>PAH</u>s

Benzo(a)pyrene (BaP), benzo(b)fluoranthene (BbF), chrysene, and/or naphthalene² were detected above the groundwater pathway RCLs in 9 of the 13 soil samples collected: B-1 (1-2'), B-1 (4-5'), B-2 (4-5'), B-3 (1-2'), B-3 (4-5'), B-4 (4-5'), B-5 (1-2.5'), B-5 (4-5'), and B-7 (1-2.5'). In addition, BaP was detected above its industrial direct contact RCL in B-5 (1-2.5'). Specifically:

- BaP was detected above its groundwater pathway RCL (470 μg/kg) in six soil samples and above the industrial direct contact RCL (2,110 μg/kg) in one soil sample, at a maximum detected concentration of 4,280 μg/kg in B-3 (4-5').
- BbF was detected above its groundwater pathway RCL (478.1 μg/kg) in six samples with the highest concentration of 5,100 μg/kg detected in B-1 (4-5').
- Chrysene was detected above its groundwater pathway RCL (144.2 μ g/kg) in eight soil samples, with the highest concentration of 5,360 μ g/kg detected in B-3 (4-5').
- Naphthalene was detected above its groundwater pathway RCL (658.2 μg/kg) in four samples, at a maximum detected value of 4,040 μg/kg in B-2 (4-5′).

Metals

Samples collected from borings B-5 through B-8 were analyzed for RCRA metals. One or more RCRA metal was detected in concentrations above the applicable RCLs and/or Wisconsin background threshold values (BTVs) in four samples.

- Arsenic was detected above its BTV of 8.3 mg/kg in three samples, with a maximum detected concentration of 24.2 mg/kg observed in B-5 (1-2.5').
- Cadmium was detected above its BTV of 1.07 mg/kg in one sample, B-5 (1-2.5'), at a concentration of 2.3 mg/kg.
- Lead was detected above its BTV of 51.6 mg/kg in one sample, B-5 (4-5'), at a concentration of 81.5 mg/kg.

¹ "J-flagged" result represents an estimated concentration that is above the Method Detection Limit (MDL) (the concentration at which laboratory equipment can detect the presence of the specific chemical), but below the laboratory Reporting Limit (RL) (the lowest concentration at which the laboratory can provide precise quantification).

² Naphthalene is considered both a VOC and a PAH and is reported under both laboratory methods.



- Mercury was detected at a concentration slightly above the groundwater pathway RCL of 0.21 mg/kg in one sample, B-5 (4-5') at a concentration of 0.29 mg/kg. There is no established BTV for mercury.
- Selenium was detected above the groundwater pathway RCL of 0.52 mg/kg in one sample, B-8 (1-2.5') at an estimated concentration of 2.8 J mg/kg. There is no established BTV for selenium.

CONCLUSIONS AND RECOMMENDATIONS

Ramboll conducted a subsurface investigation to evaluate soil conditions in the 2008 historical closure areas and the area of former coal storage activities to "determine if any applicable State of Wisconsin soil clean up standard is exceeded," as required by the Lease terms. The soil sampling performed as part of this investigation revealed detections of PVOCs and PAHs at concentrations above the groundwater pathway RCLs, detections of metals above BTVs and/or groundwater pathway RCLs, and one detection of BaP above the industrial direct contact RCL.

According to available documentation, historical contamination in the 2008 closure areas was the result of a fuel oil release associated with the former ASTs located on the Hartmeyer property. Prior investigations evaluated TPH-DRO as the primary indicator of impacts to shallow soil, with additional documentation of benzene, ethylbenzene and PAHs in soil in the 2008 closure areas. Ramboll compared the results from the recent investigation to historical soil data from the 2008 closure. TPH-DRO is no longer a regulated soil constituent in Wisconsin, and as such was not evaluated during the recent investigation. The compounds detected during the recent investigations are generally consistent with those expected to be detected due to a historical fuel oil release and those compounds present at the time of the 2008 closure activities.

Boring locations B-1 through B-5 and B-8 are in the vicinity of historical boring/sample locations. The constituents detected during the April 2019 soil investigation appear to be generally consistent with soil data associated with the 2008 case closure and the open AST case. Borings B-6 and B-7 are located a few hundred feet away from the nearest historical boring locations. These data also appear generally consistent with historical data and may be attributed to the historical fill at the site. Kraft Heinz has submitted the results of this environmental assessment to the WDNR and indicated that Kraft Heinz would like to incorporate this data into one of the two existing BRRTS cases. To date, a response from the WDNR has not been received.

Additional sampling is recommended to further delineate the extent of the BaP detection in B-5 (1-2.5') above the industrial direct contact RCL, and to further delineate the extent of the arsenic detections in B-5 (1-2.5') and B-6 (1-2') above BTVs.

Thank you for opportunity to be of service. If you have any questions or need further information, please contact us.

Sincerely,

Erin E. Veder

Principal

D 312 288 3810 eveder@ramboll.com Susan Petrofske

Managing Consultant

D 262 901 3501 spetrofske@ramboll.com Adam Streiffer

Senior Consultant

D 262 901 3506 astreiffer@ramboll.com



TABLES

Table 1: Soil Analytical Results Hartmeyer Property 2007 Roth Street, Madison, Wisconsin Project 1690012791

	Soil F	RCLs		B-1 (1-2')	B-1 (4-5')	B-2 (1-2')	B-2 (4-5')	B-3 (1-2')	B-3 (4-5')	B-4 (1-2')	B-4 (4-5')
Parameters	Industrial Direct Contact	Groundwater Pathway	BTV	4/16/2019	4/16/2019	4/16/2019	4/16/2019	4/16/2019	4/16/2019	4/16/2019	4/16/2019
VOCs (µg/kg)											
Benzene	7,070	5.1		<25.0	<28.4	<25.5	<62.5	<25.0	71.8 J C	<25.0	<25.0
Ethylbenzene	35,400	1,570		<25.0	<28.4	<25.5	7,400 C	<25.0	129	<25.0	<25.0
Naphthalene	24,100	658.2		<40.0	<45.5	81.5 J	3,440 C	<40.0	416	<40.0	<40.0
Toluene	818,000	1,107.2		<25.0	51.4 J	<25.5	<62.5	<25.0	49.2 J	<25.0	72.3 J
1,2,4-Trimethylbenzene ¹	219,000	1,378.7		44.6 J	<28.4	60.7 J	30,500 C	<25.0	59.3 J	35.7 J	<25.0
1,3,5-Trimethylbenzene ¹	182,000	1,378.7		<25.0	<28.4	<25.5	7,900 C	<25.0	<25.0	<25.0	<25.0
o-Xylene	434,000			<25.0	<28.4	<25.5	7,850	<25.0	<25.0	34.9 J	<25.0
m-&p-Xylene ²	388,000			<50.0	<56.8	<51.0	30,600	<50.0	<50.0	<50.0	<50.0
Xylenes, total	260,000	3.960		<75.0	<85.2	<76.5	38,500 C	<75.0	<75.0	<75.0	<75.0
71,101.100, 1010.		5,555									
PAHs (μg/kg)											
Acenaphthene	45,200,000			48.4	<131	<5.7	<34.0	177 J	4,950	23.2	40.9
Acenaphthylene				31.0	313 J	<4.8	<28.8	<76.7	2,420	10.1 J	8.9 J
Anthracene	100,000,000	196,949.2		119	650	8.8 J	67.7 J	478	6,820	43.9	90.3
Benzo(a)anthracene	20,800			139	3,110	13.0 J	59.6 J	1,330	5,610	52.3	242
Benzo(a)pyrene	2,110	470		106	3,110 C	11.9 J	87.1	1,430 C	4,280 C	37.8	244
Benzo(b)fluoranthene	21,100	478.1		81.1	5,100 C	11.2 J	81.0 J	1,310 C	3,650 C	23.6	333
Benzo(ghi)perylene				65.3	2.020	9.3 J	64.9	1,110	1,870	24.4	166
Benzo(k)fluoranthene	211,000			91.0	2.080	10.6 J	83.5	1,270	1,400	29.1	140
Chrysene	2,110,000	144.2		160 C	4,480 C	14.6 J	94.8 J	1,470 C	5,360 C	59.2	260 C
Dibenzo(a,h,)anthracene	2,110			23.2	430	<3.3	<19.6	348	487	7.9 J	45.2
Fluoranthene	30,100,000	88,877.8		272	9,030	23.4 J	100 J	3,340	11,300	69.7	644
Fluorene	30,100,000	14,829.9		52.5	<140	<6.0	<36.2	159 J	2.680	24.5	39.2
Indeno(1,2,3-cd)pyrene	21,100			46.5	1,580	7.0 J	<19.2	942	1,370	13.1	128
1-Methylnaphthalene	72,700			759	<136	50.3	462	<93.6	2,260	214	31.7
	3,010,000			863	<169	74.0	1,120	<116	594	206	44.8
2-Methylnaphthalene	, ,	658.2		410	<284	28.5 J		<196	2,290 C	90.2	82.1
Naphthalene	24,100	1					,				
Phenanthrene				755	2,650	50.4 J	175 J	2,060	21,400	291	395
Pyrene	22,600,000	54,545.5		243	6,160	21.3 J	84.7 J	2,570	15,200	72.1	438
Metals (mg/kg)											
Arsenic ³	3.00	0.58	8.3	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A
Barium ³	100,000	164.8	364	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A
Cadmium ³	985	0.75	1.07	#N/A	#N/A	#N/A	#N/A	#N/A #N/A	#N/A	#N/A	#N/A
Chromium		360,000	43.5	#N/A	#N/A	#N/A	#N/A #N/A	#N/A #N/A	#N/A #N/A	#N/A #N/A	#N/A #N/A
Lead ³		· ·									
	800	27	51.6	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A
Mercury	3.13	0.21		#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A
Selenium	5,840	0.52		#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A
Silver	5,840	0.85		#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A	#N/A

Notes:

VOCs = Volatile Organic Compounds

PAHs = Polynuclear Aromatic Hydrocarbons

RCL = Residual Contaminant Level

BTV = Background Threshold Value μg/kg = micrograms per kilogram

mg/kg = milligrams per kilogram

- Groundwater Pathway RCL listed is for 1,2,4- and 1,3,5-Trimethylbenzenes combined.
- ² Direct Contact RCL listed is for the more stringent m-Xylene.
- $^{\rm 3}\,$ Parameter BTV is larger than one or more of the RCLs or is the only standard available.
- $^{\rm 4}$ Concentration above NR 720 RCL for Groundwater Pathway, but below BTV.
- Bolded value indicates an NR 720 Residual Contaminant Level (RCL) exceedance.
- **B** Parameter exceeds NR 720 RCL for Industrial Direct Contact.
- C Parameter exceeds NR 720 RCL for Groundwater Pathway.
- D Parameter exceeds Surficial BTV for metals.
- J Estimated concentration at or above the LOD and below the LOQ. -- No RCL or Surficial BTV established.
- #N/A = Not analyzed

0-4' used for direct contact determination

Soil RCLs and surficial BTVs established by the WDNR RR program using the EPA's RSL web-calculator with WAC NR 720 default parameters (WDNR PUB-RR-890, June 2014 - updated

Table 1: Soil Analytical Results Hartmeyer Property 2007 Roth Street, Madison, Wisconsin Project 1690012791

	Soil R	CLs		B-5 (1-2.5')	B-5 (4-5')	B-6 (1-2')	B-7 (1-2.5')	B-8 (1-2.5')
Parameters	Industrial Direct Contact	Groundwater Pathway	BTV	4/16/2019	4/16/2019	4/16/2019	4/16/2019	4/16/2019
VOCs (μg/kg)								
Benzene	7,070	5.1		<25.0	37.0 J C	<33.8	<26.9	<25.0
Ethylbenzene	35,400	1,570		<25.0	49.2 J	<33.8	90.3	<25.0
Naphthalene	24,100	658.2		<40.0	283 J	112 J	260 J	<40.0
Toluene	818,000	1,107.2		<25.0	48.2 J	61.3 J	223	<25.0
1,2,4-Trimethylbenzene ¹	219,000	1,378.7		<25.0	45.5 J	200	205	<25.0
1,3,5-Trimethylbenzene ¹	182,000	1,378.7		<25.0	<25.0	83.5 J	60.1 J	<25.0
o-Xylene	434,000			<25.0	<25.0	136	242	<25.0
m-&p-Xylene ²	388,000			<50.0	75.0 J	122 J	318	<50.0
Xylenes, total	260,000	3,960		<75.0	105 J	258 J	560	<75.0
PAHs (μg/kg) Acenaphthene	45,200,000			<99.2	145	35.8	100 J	7.7 J
Acenaphthylene				<84.2	486	4.9 J	327	5.4 J
Anthracene	100,000,000	196,949.2		579	330	29.6	383	22.4 J
Benzo(a)anthracene	20,800			2,300	502	32.2	924	33.6
Benzo(a)pyrene	2,110	470		2,540 B,C	702 C	23.4	1,040 C	24.1
Benzo(b)fluoranthene	21,100	478.1		2,670 C	758 C	18.3	1,080 C	25.7
Benzo(ghi)perylene	21,100	476.1		2,040	460	9.5 J	782	11.9
Benzo(k)fluoranthene	211,000			2,050	240	6.2 J	837	7.8 J
Chrysene	2,110,000	144.2		2,500 C	552 C	31.0	1,120 C	30.6
Dibenzo(a,h,)anthracene	2,110,000			698	126	<3.3	258	3.3 J
Fluoranthene	30,100,000	88,877.8		4,970	712	49.2	1,960	39.4
Fluorene	30,100,000	14,829.9		<106	201	43.3	163	<5.3
Indeno(1,2,3-cd)pyrene	21,100			1,760	346	3.6 J	690	6.3 J
1-Methylnaphthalene	72,700			<103	217	47.2	918	100
2-Methylnaphthalene	3,010,000			<128	324	50.2	825	85.5
Naphthalene	24,100	658.2		<215	757 C	40.3 J	2,960 C	29.7 J
Phenanthrene	24,100			2,020	468	234	1,920	122
Pyrene	22,600,000	54,545.5		3,610	890	44.4	1,670	37.0
Metals (mg/kg)								
Arsenic ³	3.00	0.58	8.3	24.2 B,C,D	4.9 ⁴ J C	10.5 B,C,D	<1.2	8.8 B,C,D
Barium ³	100,000	164.8	364	26.9	107	50.9	40.9	18.1
Cadmium ³	985	0.75	1.07	2.3 C,D	0.45 J	0.19 J	<0.15	<0.16
Chromium		360,000	43.5	13.6	17.4	9.3	16.3	7.9
Lead ³	800	27	51.6	24.4	81.5 C,D	11.3	8.2	3.6
Mercury	3.13	0.21		0.014 J	0.29 C	0.023 J	0.015 J	<0.012
Selenium	5,840	0.52		<1.6	<1.8	<1.8	<1.5	2.8 J C
Silver	5,840	0.85		0.78 J	0.54 J	0.55 J	0.54 J	< 0.42

VOCs = Volatile Organic Compounds PAHs = Polynuclear Aromatic Hydrocarbons

RCL = Residual Contaminant Level

BTV = Background Threshold Value μg/kg = micrograms per kilogram

mg/kg = milligrams per kilogram

- ¹ Groundwater Pathway RCL listed is for 1,2,4- and 1,3,5-Trimethylbenzenes combined.
- ² Direct Contact RCL listed is for the more stringent m-Xylene.
- $^{\rm 3}\,$ Parameter BTV is larger than one or more of the RCLs or is the only standard available.
- $^{\rm 4}$ Concentration above NR 720 RCL for Groundwater Pathway, but below BTV.
- Bolded value indicates an NR 720 Residual Contaminant Level (RCL) exceedance.
- **B** Parameter exceeds NR 720 RCL for Industrial Direct Contact.
- C Parameter exceeds NR 720 RCL for Groundwater Pathway.
- D Parameter exceeds Surficial BTV for metals.
- ${\bf J}\,$ Estimated concentration at or above the LOD and below the LOQ.
- -- No RCL or Surficial BTV established.

#N/A = Not analyzed

0-4' used for direct contact determination

Soil RCLs and surficial BTVs established by the WDNR RR program using the EPA's RSL web-calculator with WAC NR 720 default parameters (WDNR PUB-RR-890, June 2014 - updated




FIGURES



DRAFTED BY: HJW

DATE: 4/29/19

MADISON, WISCONSIN




DATE: 4/23/19

DRAFTED BY: HJW

SITE LAYOUT AND SAMPLING LOCATIONS

HARTMEYER PROPERTY 2007 ROTH STREET MADISON, WISCONSIN **FIGURE**


2



DATE: 6/4/19

PATHWAY SOIL RCL EXCEEDANCES - VOCs (APRIL 2019)


HARTMEYER PROPERTY 2007 ROTH STREET MADISON, WISCONSIN 3



DATE: 6/4/19

PATHWAY SOIL RCL EXCEEDANCES - PAHs (APRIL 2019)

4



DATE: 6/4/19

PATHWAY SOIL RCL EXCEEDANCES - METALS (APRIL 2019)

HARTMEYER PROPERTY 2007 ROTH STREET MADISON, WISCONSIN



ATTACHMENT A BORING LOGS

SOIL BORING LOG INFORMATION

Form 4400-122 Rev. 7-98

			Ro	oute To:	Watershed/W Remediation/			Waste Other	_	ement								
															Pag		of	1
	ty/Proje							License/	Permit	/Monito	oring N	umbei		Boring	Numb		1	
				estigatio		15:		N/A	11: 0	1		ID	D :11		1 .	B-1		
	_	-	Name	of crew c	hief (first, last)	and Firm		Date Dr	Illing S	tarted		Da	te Drilli	ing Coi	mpleted	1	Drill	ing Method
On-		Envir	onme	ntal					4/16	/2019			4	4/16/2	2019		Di	rect Push
WI Uı	nique W	ell N	0.	DNR V	Well ID No.	Common	Well Name				el :	Surfac	e Eleva	tion		Во		Diameter
									Feet 1	MSL				t MS			2.0	inches
	Grid O	rigin	☐ (e	stimated:	O or Bor			La	+	0	,	,,	Local (Brid Lo				
State	Plane						C/N				, —							□ E
F - 117	1/4	of]	1/4 of Sec		T N	, R	Lon		C::1 T	/C		1 7:11		S]	Feet W
Facilit	ly ID				County			County Co	ode	Civil T Madi		ity/ or	village					
C	1 .		1	<u> </u>	Dane			13		Madi	SOII			G . 11	D	· · · ·		
San	nple													Soil	Prope	erties		
	Length Att. & Recovered (in)	ts	set		Soil/R	ock Descri	ption						e e					
ے و	Att.	Blow Counts	Depth In Feet		And Ge	ologic Orig	gin For				ے ا		ssiv	. بو ا		<u> </u>		nts
nbei TyF	gth	× C	thI		Eac	h Major U	nit		CS	phic	l gran	ÆII	npre ngtl	stur	it it	ticii	0) / me
Number and Type	Length Att. Recovered (Blo	Dep						S D	Graphic Log	Well Diagram	PID/FID	Compressive Strength	Moisture Content	Liquid Limit	Plasticity Index	P 200	RQD/ Comments
1	60		+	Conci	rete.					P 6 4			0 02					
CS	54		F	FILL:	Gravelly sar	nd, moist.			FILL			0.2						
			-0.5	FII I	: Sand, some	graval bl	ools wat					0.3						
			E	FILL	Sand, some	graver, or	ack, wei.											
			-1.0															
			1.0															
			L															
			1.5															Soil sample
			F															collected at 1-2 ft bgs.
			-2.0						FILL			1.4						1-2 It 0gs.
			E									1.7						
			-2.5															
																		Water level 2.5 ft at time
			F															of drilling.
			-3.0															
			E															
			_3.5	FILL	Silt, trace or	roanics h	lack wet	mild										
			-	odor.	sin, nace of	guines, or	uck, wei,	iiiid										
			-4.0															
			ļ .						FILL									
			F						TILL			4.9						
			-4.5															Soil sample
			E															collected at 4-5 ft bgs.
			-5.0	End o	f boring at 5 f	t Ahanda	ned with											1 2 11 0 5 5.
				bentor		110and	**1111											
		0 1			4. 0				<u>. </u>									
	-	ty tha	t the inf	ormation	on this form is				y knov	ledge.								
Signat	ture							mboll									Tel: 2	262-901-2722
							175	North Cor	porate	Drive,	Suite 1	60 Br	ookfield	1, WI 5	3045			Fax:

SOIL BORING LOG INFORMATION

Form 4400-122 Rev. 7-98

			Ro	oute To:	Watershed/W Remediation			Waste Other	_	ement								
															Pag		of	1
	y/Proje							License	Permit	/Monito	oring N	umbei	•	Boring	Numb			
				estigatio		15.		N/A					. 5 . 11			B-2		
		-	Name	of crew c	chief (first, last)	and Firm		Date Dr	Illing S	tarted		Da	te Drilli	ing Coi	mpleted	1	Drill	ing Method
On-	ge Kap Site E	Envir							4/16	/2019				4/16/2	2019		Di	rect Push
WI Uı	nique W	ell N	0.	DNR V	Well ID No.	Common	Well Name				el :	Surfac	e Eleva			Во		Diameter
									Feet 1	MSL				t MS			2.0	inches
	Grid O	rıgın	☐ (e	stimated:	or Bor			La	ıt	0	,	,,	Local (irıd Lo				_
State	Plane						C/N			0	,				□ N			□ E
Facilit	1/4	of		1/4 of Sec	County	T N	, R	Lon County Co		Civil T	oxym/C	try/ on	Villaga					Feet W
гаспп	y ID				Dane Dane			13	ode	Madi		ity/ or	village	:				
C	1 .		1		Dane			13		Madi	SOII			G . 11	D	4.		
San	nple													Soil	Prope	erties		
	Length Att. & Recovered (in)	ts	g		Soil/R	ock Descri	ption						စ်					
. o	Att.	Blow Counts	Depth In Feet		And Ge	ologic Orig	gin For				_		Compressive Strength	b		>		RQD/ Comments
Number and Type	gth,	Ŭ	h Li		Eac	h Major Uı	nit		CS	Graphic Log	Well Diagram	PID/FID	Compres Strength	Moisture Content	it d	Plasticity Index	0)/
Jun nd '	Seco	3lov)epi						SO	Grap Log	Vel] Siag	Ď.	on	Aoi:	Liquid Limit	Plastic Index	P 200	RQD/ Comm
1	60		+ -	- Conci	rete, asphalt,	hlack roc	·k			0 II	<i>></i> 11	H	0 0	20		д	<u>н</u>	<u> </u>
CS	54		F		: Gravelly sai			/	FILL									
			-0.5						TILL			0.1						
			L 0.3	FILL	: Sand, some	gravel, bla	ack, wet.											
			E															
			1.0															
			-							\bowtie								
			-1.5															
			L 1.3															Soil sample
			E															collected at 1-2 ft. bgs.
			-2.0															Water level
			E						FILL			0.0						2 ft. at time
			F 2.5									0.3						of drilling
			2.5															
			F							\bowtie								
			-3.0															
			F															
			ļ.															
			_3.5															
			-															
			-4.0															
			F		: Silt, trace or	rganics, bl	ack, wet,	mild										
			E	odor.														
			-4.5						FILL			12.9						Soil sample
			L									12.7						collected at
			-5.0							\bowtie								4-5 ft. bgs.
			3.0		f boring at 5 f	t. Abando	oned with											
				bento	nıte.													
			<u> </u>						<u>. </u>						<u> </u>			
	-	ty tha	t the in	ormation	on this form is			e best of m	y knov	ledge.								
Signat	ure						Firm Ra	mboll									Tel: 2	262-901-2722
Signature Firm Ramboll 175 North Corporate Drive, Suite										Suite 1	60 Br	ookfield	1, WI 5	3045			Fax:	

SOIL BORING LOG INFORMATION

Form 4400-122 Rev. 7-98

Route To: Watershed/Wastewater Remediation/Redevelopme		aste Manag her $\ \square$	ement								
								Pag	e 1	of	1
Facility/Project Name		nse/Permit	/Monito	oring N	ımber	.]	Boring	Numb			
Hartmeyer Soil Investigation Boring Drilled By: Name of crew chief (first, last) and Firm	N/ Date	A Drilling S	tarted		Dat	e Drilli	ng Coi	nnletec	$\frac{B-3}{1}$		ling Method
Gage Kapugi		_						•			_
On-Site Énvironmental WI Unique Well No. DNR Well ID No. Common We	all Nama Eine	4/16 I Static Wa	/2019		humfood	e Elevat	1/16/2	2019	Do		Diameter
wi Unique wen No. Divide wen ib No. Common we	en Name Fina	Feet l		61 3	ourrace		t MS	L	BO		inches
Local Grid Origin (estimated:) or Boring Location			0	,	,,]	Local C	rid Lo	cation			
State Plane N, E S/C/I		Lat	0	<u> </u>			E4	□ N □ S		,	☐ E Feet ☐ W
		Long y Code	Civil T	own/Ci	<u></u> ty/ or `	Village	reet	□ 2			reet 🗀 w
Dane	13		Madi								
Sample							Soil	Prope	erties		-
⊗ (fi) g tj Soil/Rock Description						, e					
And Geologic Origin		N N	ပ	E	О	essiv	ire it		ity		ents
Number and Type and Type And Geologic Origin Blow Counts Blow Counts Blow Counts Each Major Unit Each Major Unit		SC	Graphic Log	Well Diagram	PID/FID	Compressive Strength	Moisture Content	Liquid Limit	Plasticity Index	P 200	RQD/ Comments
注意 五座 面 面		n	<u> </u>	i≱ Ö	<u> </u>	Ω Ω	<u>Σ ϋ</u>		Pl In	Ь	<u> </u>
CS 48	-4		// // //								
FILL: Gravelly sand, black, we	et.	FILE									
		FILL			1.8						
FILL: Gravelly sand, tan, wet.											
-1.5		FILL			1.6						Soil sample
											collected at 1-2 ft. bgs.
FILL: Sand and gravel, browni	ish black, wet										
		EH I									
		FILL			1.5						
3.0											
FILL Silt with trace organics, b	olack, mild										Water level 3 ft. at time
-3.5 Gdoi.											of drilling.
-4.0		FILL			- 4						
					5.4						
-4.5											Soil sample
Sand seams at 4.5 and 5 ft. bgs.											collected at
End of boring at 5 ft. Abandone	ed with										4-5 ft. bgs.
bentonite.	111111										
I hereby certify that the information on this form is true and correspond to the signature Fig. 1.			ledge.								
Signature FII	rm Ramboll 175 North		Drive. S	Suite 16	0 Bro	okfield	l, WI 5	3045		Tel:	262-901-2722 Fax:

SOIL BORING LOG INFORMATION

Form 4400-122 Rev. 7-98

			<u>Ro</u>		Vastewater □ /Redevelopment □	Waste I	_	ement								
г 11	/D ·	4 NT				T · /	D '	/N. f. · · ·	. ,	T 1		D .	Pag		of	<u>l</u>
	y/Proje			_4:4:		License/	Permit	Monito	oring N	lumbei		Boring	Numb	er B-4	1	
Borin	g Drille	d By:		stigation of crew chief (first, last)	and Firm	N/A Date Dri	lling S	tarted		Dat	te Drilli	ing Cor	mpleted			ling Method
On-		Envir	onmer					/2019				4/16/2	2019			irect Push
WI U	nique W	Vell N	0.	DNR Well ID No.	Common Well Name				el	Surfac	e Eleva		r	Bo		Diameter
Lassi	Grid O			stimated: or Bor	ing Lagation N		Feet 1	MSL			Fee Local (t MS			2.0	inches
	Olla O Plane	ngm	☐ (es		E S/C/N	La	t	0	<u> </u>		Local	JIIU LO				
	1/4	of	1	/4 of Section ,	T N, R	Long	g	0	<u>'</u>	<u>"</u>			□ N □ S]	E Feet W
Facili	y ID			County		County Co	ode			ity/ or	Village	:				
-	1			Dane		13		Madi	son			G '1	D.			
Sar	nple											Soil	Prope	erties		-
	& (in)	ıts	set		ock Description						é					
r Se	Att. red	ano	n F	And Ge	ologic Origin For		\sigma		g		essiv	e _		<u>₹</u>		snts
nbe Tyl	Length Att. Recovered (Blow Counts	Depth In Feet	Eac	h Major Unit		C	Graphic Log	Well Diagram	PID/FID	npre	Moisture Content	Liquid Limit	Plasticity Index	00	RQD/ Comments
Number and Type	Length Att. & Recovered (in)	Blo	De				n s	Grap Log	We Dia	PIL	Compressive Strength	° S	Liquid Limit	Plastic Index	P 200	RQD/ Comm
1 CS	60 48			Topsoil, black flat	rock.			711/2 7/11								
			-1.0	FILL: Sand with g	ravel, blackish brow	vn.				5.1						Soil sample collected at
			-2.0 -2.5 -3.0 -3.5	Wet at 2 ft.			FILL			1.3						1-2 ft. bgs. Water level 2 ft. at time of drilling.
			-4.0 -4.5 -5.0	FILL: Silt with sorblack, wet. End of boring at 5 f bentonite.		el,	FILL			5.2						Soil sample collected at 4-5 ft. bgs.
I here	by certi	fy tha	t the inf	ormation on this form is	true and correct to the	e best of my	y know	ledge.								
Signa	-				Firm Rai	mboll North Cor			Suite 1	60 Br	ookfield	d. WI 5	3045		Tel: 2	262-901-2722 Fax:

SOIL BORING LOG INFORMATION

Form 4400-122 Rev. 7-98

			Ro		Vastewater □ /Redevelopment □	Waste Other	_	gement								
													Pag		of	1
	y/Proje			, · ·		License	/Permit	t/Monite	oring N	lumber	•	Boring	Numb			
Har	tmeye	d By	Il Inve	estigation of crew chief (first, last)	and Firm	N/A Date Dr	illing S	Started		Dat	te Drill:	ing Cor	mnletec	B-5		ling Method
	ge Kap	-	Ivallic	of elew ellief (first, fast)	and Firm	Date Di	ming c	nancu		Da	ic Dilli	ing Coi	присис	ı	Din	ing Method
	Site E		onmer	ntal			4/16	/2019			4	4/16/2	2019		D	irect Push
	nique W			DNR Well ID No.	Common Well Nam	e Final St				Surfac	e Eleva			Во		Diameter
							Feet 1	MSL				t MS			2.0	inches
	Grid O	rigin	(es	stimated: or Bor				0	,	,,	Local (Grid Lo	cation			
State	Plane			*	E S/C/N		at						□ N			□ E
D 11.	1/4	of	1	/4 of Section ,	T N, R	Lon					X 7*11		\square S		-	Feet W
Facilit	y ID			County Dane		County C	ode	Civil T Madi		ity/ or	Village	;				
Com	1 ₋			Dane		13	T	Iviaui	SOII			Cail	Duomo	uti a a		
San	nple											5011	Prope	rues		_
	Length Att. & Recovered (in)	ıts	eet		ock Description						è					
r pe	Att	Blow Counts	Depth In Feet		ologic Origin For		N N	ွ	8		essi h	re t		ty		RQD/ Comments
mbe I Ty	ngth	<u></u>	pth]	Eac	h Major Unit		SC	Graphic Log	Well Diagram	PID/FID	mpr	Moisture Content	Liquid Limit	Plasticity Index	90)Q
Number and Type	Ler Rec	Blc	Dej				n	Grap Log	We	PII	Compressive Strength	So M	Liquid Limit	Plastic Index	P 200	RQ Co
1 CS	60 48			Topsoil.				71 1/1								
cs	48							1.7.								
Ш			-0.5	FILL: Gravelly san	nd with some silt, o	rangish										
Ш			F	brown, moist.		C										
Ш			-1.0													
Ш			E				FILL			2.5						
Ш			-1.5							2.5						
Ш			- 1.0													
Ш			F 20													Soil sample collected at
Ш			-2.0	FILL: Silt with sar	nd and gravel, tan, i	moist to										1-2.5 ft. bgs.
Ш			E	wet.												
Ш			-2.5													
Ш			-				FILL			2.1						
Ш			-3.0							2.1						
Ш			E													
Ш																
Ш			- 3.3	FILL: Silt, trace or brown, wet.	rganics and gravel,	blackish										Water level 3.5 ft. at
Ш			F	biowii, wet.												time of
Ш			-4.0							3.0						drilling.
Ш			E				FILL									
Ш			-4.5													Soil sample
Ш			_													collected at
Ц			-5.0	End of howing at 5 f	4 A la au d'au a d'avrittle			XXXX		l						4-5 ft. bgs.
				End of boring at 5 f bentonite.	t. Abandoned with	l										
			<u> </u>				<u> </u>	<u> </u>		<u> </u>						
	-	ty that	the inf	ormation on this form is	le.		y knov	vledge.								
Signat	ure					amboll									Tel:	262-901-2722
					17:	5 North Co	rporate	Drive,	Suite 1	60 Br	ookfiel	d, WI 5	3045			Fax:

State of Wisconsin Department of Natural Resources

should be sent.

SOIL BORING LOG INFORMATION

Form 4400-122 Rev. 7-98

			Ro		Vastewater □ /Redevelopment □	Waste Other	_	gement								
													Pag	e 1	of	1
	y/Proje					License/	Permit	/Monito	oring N	umbei	r .	Boring	Numb	er		
Har Borins	tmeye Drille	er Son	II Inve	stigation of crew chief (first, last)	and Firm	N/A Date Dri	illing S	Started		Da	te Drilli	ng Coi	npletec	B-6		ling Method
Gag	e Kar	ougi					_									_
	Site E		onmen	ntal DNR Well ID No.	Common Well Nam	e Final Sta		/2019		Surfac	e Eleva	1/16/2	2019	Ro		Diameter
WI OI	nque w	CII IN	J.	DINK WEII ID NO.	Common wen Nam		Feet]			Juliac		t MS	L	Во		nches
		rigin	(es	stimated:) or Bor		I.e	ıt	0	,	"	Local C	irid Lo		- 1		
State	Plane 1/4	of	1	N, /4 of Section ,	E S/C/N T N, R	Lon		0	,			Feet	□ N □ S		1	☐ E Feet ☐ W
Facilit		01	1	County	i N, K	County Co		Civil T		ity/ or	Village					reet 🗀 w
	4 1			Dane		13		Madi	son							T
San	nple											Soil	Prope	erties		
	t. & 1 (in)	nts	eet		ock Description						ive					, so
er ype	h At	Cou	In		ologic Origin For h Major Unit		S	ic	am	Д	ress	ure	-	city		nents
Number and Type	Length Att. & Recovered (in)	Blow Counts	Depth In Feet	Eac	ii Major Ollit		IS C	Graphic Log	Well Diagram	PID/FID	Compressive Strength	Moisture Content	Liquid Limit	Plasticity Index	200	RQD/ Comments
CS CS	60		-	Topsoil.			Þ	717 71	> 1	P	0 8	<u> </u>		P I	Ь	
CS	48			•				1/ 3/1/								
			-0.5	FILL: Gravelly cla	ny with some silt, bi	rown,										
				moist.			FILL			2.8						
			-1.0	FILL: Sand with g	ravel and black flat	stones,										
			- , ,	brownish black.												
			-1.5													Soil sample collected at
			2.0													1-2 ft. bgs.
			- 2.0	Wet at 2 ft.												Water level 2 ft. at time
			$\begin{bmatrix} -2.5 \end{bmatrix}$													of drilling.
							FILL									
			$\begin{bmatrix} -3.0 \end{bmatrix}$							3.1						
			-3.5													
			4.0													
			-													
			4.5	FILL: Clayey silt	with trace organics	and										
			-	gravel, wet.			FILL			2.6						
L			-5.0	End of boring at 5 f	t. Abandoned with											
				bentonite.												
honel	axy comti	fr that	the inf	ormation on this form is	true and compact to the	a bast of	v knov	rladas								
Signat	-	ıy ılldi	ane IIII	omation on this form is		ımboll	y KIIOV	rieuge.							T.1.	262 001 2722
<i>G</i>					110	ımboli 5 North Cor	porate	Drive,	Suite 1	60 Br	ookfield	1, WI 5	3045		rei:	262-901-2722 Fax:

This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be be used for any other purpose. NOTE: See instructions for more information, including where the completed form

State of Wisconsin Department of Natural Resources

SOIL BORING LOG INFORMATION

Form 4400-122 Rev. 7-98

			Ro	ute To:	Watershed/W	Vastewater		Waste	Manag	gement								
					Remediation	/Redevelop	ment \square	Other										
															Pag	ge 1	of	1
	y/Proje							License	/Permit	/Monit	oring N	lumber	r	Boring	Numb		_	
				stigatio		1.5.		N/A	.11	u 4 1		15	· D 111		1 /	B-7		
-		-	Name	of crew c	chief (first, last)	and Firm		Date Dr	illing S	tarted		Da	te Drilli	ing Coi	mpieteo	1	Drill	ling Method
	ge Kap Site F		onmer	ntal					4/16	/2019			4	4/16/2	2019		Di	irect Push
	nique W				Well ID No.	Common	Well Name		atic Wa	ater Lev		Surfac	e Eleva			Во		Diameter
									Feet 1	MSL				t MS			iı	nches
Local State	Grid O	rigin	(es	stimated:	O or Bor	_ ~	on ⊠ C/N	1.	at	0	•	"	Local (3rid Lo	_			
State	1/4	of	1	/4 of Sec			, R	Lon		0	,			Feet	∐ N : □ S		1	☐ E Feet ☐ W
Facilit		01	1		County	1 11	, K	County C		Civil T	own/C	ity/ or	Village					reet W
	-				Dane			13		Madi	son	-						
San	nple			·										Soil	Prope	erties		
	& in)	S	t e		Soil/R	ock Descri	ption						မ					
o	Ått. ed (ount	. Fe		And Ge	ologic Orig	gin For						SSIV	۵,		<u></u>		nts
Number and Type	Length Att. & Recovered (in)	Blow Counts	Depth In Feet		Eac	h Major U	nit		CS	Graphic Log	Well Diagram	PID/FID	Compressive Strength	Moisture Content	nid it	Plasticity Index	0	RQD/ Comments
Nun	Len	Blov	Dep						S O	Gray Log	Wel Diag	PD	Con	Moi	Liquid Limit	Plastic Index	P 200	RQI
1	60		_	Topso	oil.					7/ 1/2	4							
CS	36									1/ 71/								
			-0.5	FILL	: Clayey sand	l with som	ne gravel,	brown										
			E	black,	, moist.				FILL			3.7						
			-1.0	FILL	: Sand and gr	avel with	black flat	rock,										
			F	brown	black, wet, s	ome tan st	tone near	3 ft.										
			-1.5															
			_															Soil sample
			-2.0						FILL			4.3						collected at
			E									7.5						1-2.5 ft. bgs.
			-2.5															
			E															
			- -3.0															
			- "	FILL	: Clayey silt ics, brown bla	with trace	gravel an	d										Water level 3 ft. at time
				organi	ics, blowii bla	ck, moist.												of drilling.
			_3.3															
			F															
			-4.0						FILL			4.3						
 																		
			-4.5															
			-															
Ц			-5.0	Fnd o	f boring at 5 f	t Abando	ned with			XXXX								
				bento		. Moana	JICG WILL											
herel	ov certi	fy that	the inf	ormation	on this form is	true and co	orrect to th	e best of m	y knov	vledge.			1					
Signat	-	,						mboll									Tal. 1	262-901-2722
-							114	North Co	porate	Drive,	Suite 1	60 Br	ookfield	1, WI 5	3045		101. 2	202-901-2722 Fax:
_			_	_				_		_				_			_	

This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

State of Wisconsin Department of Natural Resources

SOIL BORING LOG INFORMATION

Form 4400-122 Rev. 7-98

Route To: Watershed/Wastewater Remediation/Redevelop								Waste Other	_	gement								
					remedia	ion react	опоринени 🗀	other							Pag	e 1	of	1
	ty/Proje							License	/Permit	/Monit	oring N	lumbe	r	Boring	Numb	er		1
Har	tmeye	er So	il Inve	stigati	on chief (first, l			N/A Date Dr	:11: С	44-1		D.	4 - D.:11	C	14	B-8		L. M.d. d
	g Drille ge Kaj	-	Name	oi crew	chief (first, l	ast) and Fii	rm	Date Dr	illing S	tarted		Da	te Drilli	ing Coi	npietec	1	Drill	ing Method
On-	Site I	Envir	onmei	ntal						/2019				4/16/2	2019			rect Push
WI Uı	nique W	Vell No	0.	DNR	Well ID No.	Comm	on Well Nam				/el	Surfac	e Eleva		r	Во		Diameter nches
Local	Grid O	rigin	(e:	stimated	: 🗌) or	Boring Loc	cation 🖂	1	Feet 1				Local	t MS Grid Lo			- 11	iches
State					N	, E	S/C/N	L	at	°	<u> </u>	"			□ N			□Е
Facilit	1/4	of	1	/4 of Se	County ,	T	N, R	Lon County C					Village		□ S]	Feet W
raciii	ly ID				Dane			13	oue	Madi		ity/ Oi	village					
San	nple													Soil	Prope	erties		
	& (iii)	S	et		So	il/Rock De	scription						ပ					
ر و	Att. red (ount	n Fe		And	Geologic (Origin For				g		sssiv	e		£1	ı	ents
Number and Type	Length Att. & Recovered (in)	Blow Counts	Depth In Feet			Each Majo	r Unit		SCS	Graphic Log	Well Diagram	PID/FID	Compressive Strength	Moisture Content	Liquid Limit	Plasticity Index	P 200	RQD/ Comments
	Re Le	ğ	D P	- TE					Ď	<u>77. 77</u>	N W	PII	Str	⊻ క	Lir	Pla Inc	P 2	<u>გ</u> ვ
1 CS	60 54		E	Tops	011.					1/ 1/							ı	
			-0.5	EII I	• Condon	1 amorral h	lackish brow	710									ı	
			E	moist		i graver, o	iackisii biow	/11,									ı	
			1.0														ı	
			F														ı	
			1.5						FILL			3.9					ı	
			F														ı	Soil sample
			-2.0														ı	collected at 1-2.5 ft. bgs
			E														ı	
			-2.5	FILL	: Clayey s	ilt with tra	ace organics	and									ı	
			E	grave	l, blackish	brown, w	et.										ı	
			3.0	Red b	orick at 3 ft							3.2					ı	
			F									3.2					ı	
			3.5														ı	
			F 40						FILL								ı	
			-4.0	Sand	and gravel	seam at 4	ft.										ı	Water level 4 ft. at time
			4.5									2.7					ı	of drilling.
			F 4.3									2.7					ı	
			5.0														ı	
				End of bento		5 ft. Aba	ndoned with										ı	
																	ı	
																	ı	
I here	by certi	fy that	the inf	ormation	n on this for	m is true an	d correct to th	e best of m	y know	vledge.								
Signature Fi						ımboll									Tel: 2	262-901-2722		
						175	5 North Co	porate	Drive,	Suite 1	60 Br	ookfield	1, WI 5	3045			Fax:	

This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

State of Wis., Dept. of Natural Resources dnr.wi.gov

175 N Corporate Drive, Suite 160

State

WI

ZIP Code

53045

City

Brookfield

Well / Drillhole / Borehole Filling & Sealing

Form 3300-005 (R 4/08)

Page 1 of 2

Notice: Completion of this report is required bychs. 160, 281, 283, 289, 291-293, 295, and 299, Wis. Stats., and ch. NR 141, Wis. Adm. Code. In accordance with chs. 281, 289, 291-293, 295, and 299, Wis. Stats., failure to file this form may result in a forfeiture of between \$10-25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. Return form to the appropriate DNR office and bureau. See instructions on reverse for more information.

form to the appropriate DIVR office	and bureau. S	_		more informa	ation.				_
Verification Only of Fill	and Seal	Ro	oute to: Drinking Water Waste Managemer	nt	Watershed/V	Vastewater (Remediation	Redevelor	oment
1. Well Location Information				2 Facilit	v/ Owner li	nformation			
	ique Well # of	Hica	ap #	Facility Nar					_
Dane	ved Well			Hartmeye	er Property				
Lattitude / Longitude (Degrees ar	nd Minutes) M	ethod Co	ode (see instructions	Facility ID (FID or PWS)			
	- N		`						
	'w			License/Pe	rmit/Monitori	ng #			
1/4/1/4 1/4	Section	Townsl	nip Range E	Original We	ell Owner				
or Gov't Lot#		X L	N w	D					
Well Street Address	-1			Present We	ell Owner				
2007 Roth Street									
Well City, Village or Town		IV	Vell ZIP Code	- Mailing Add	Iress of Pres	ent Owner			
Madison			53704	011 (0		- Ia	. 150		
Subdivision Name		L	ot#	City of Pres	sent Owner	Sta	ate ZIP	Code	
Reason For Removal From Servi	oo IWI I Iniquo	Moll # o	f Replacement Well	4. Pump,	Liner, Scre	en, Casing & Sealing	Material		_
Borehole Only	ce ivii onique	vvcii # O	Treplacement vveli	Dump and r	piping remove	Nd2	Yes	No	N/A
3. Well / Drillhole / Borehole	luda um ati a u			-	. •	ou :			
3. Well / Drillhole / Borenole		terettee F	Sala Variatidalita a A	Liner(s) rem			Yes	No	
Monitoring Well	4/16/2019	truction L	Date (mm/dd/yyyy)	Screen remo			Yes Yes	No No	
Water Well	If a Well Consti	ruction Re	eport is available,	Was casing	cut off below	/ surface?	Yes	No	(N/A)
Borehole / Drillhole	please attach.		,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	-	material rise		(es)	No	N/A
Construction Type:				1	settle after 2		Yes	No	N/A
Drilled Driven (\$	Sandpoint)		Dug		nole retopped		Yes	No	(N/A)
Other (specify):	ou.iopo.i.ty		9	If bentoni	te chips were	e used, were they hydrate	ed		
						n safe source?	Yes	No	W/A
Formation Type:				11.3		ing Sealing Material			
Unconsolidated Formation		Bedrock			tor Pipe-Graved & Poured		•		
Total Well Depth From Ground S	urface (ft.) Cas	sing Diar	meter (in.)	_		Other (Explain):			_
NA	N/	Ą		Sealing Mat	nite Chips) erials				
Lower Drillhole Diameter (in.)	Cas	sing Dep	th (ft.)	Neat Cement		Cla	ay-Sand Slui	rry (11 lb://	nal wt \
NA	N/	Α		1	ement (Conci		entonite-Sar	, ,	,
Was well annular space grouted?	Ye	c	No Unknown	Concret	•		ntonite Chip		
						d Monitoring Well Boreho			
If yes, to what depth (feet)?	Depth to	Water (fe	eet)	Bentonit	e Chips	Bentonite	- Cement G	rout	
NA	NA			Granula	r Bentonite	Bentonite	- Sand Slurr	у	
5. Material Used To Fill Well	/ Drillhole			From (ft.)	To (ft.)	No. Yards, Sacks Sea or Volume (circle o		Mix Ratio Mud Weig	
Ber	tonite Chips			Surface	5				
6. Comments						4			
Boring ID: 5-1									
7. Supervision of Work						DNF	R Use Only	/	
Name of Person or Firm Doing Fil	ling & Sealing	License	# Date of Fi	lling & Sealin	g (mm/dd/yy		Noted E		
Ramboll/On-Site Environme	Ramboll/On-Site Environmental								
Street or Route			Te	elephone Nur	nber	Comments	7		

(262)901-3506

Signature of Person Doing Work

Gage Kapugi

Date Signed

04/30/2019

Well Filling and Sealing

Wisconsin Administrative Code (NR81 1, NR 812, and NR 141 requires well owners to permanently fill and seal any unused wells/drillholes/boreholes on their property. As of June 1, 2008 water supply wells can only be filled and sealed by licensed well drillers and pump installers.

- 1. Remove any pump, pump piping, debris or other obstacles that could interfere with the sealing operation.
- 2. Except when bentonite chips are used, the sealing material must be placed with the use of a conductor (tremie) pipe to fill the entire well column to the top with required sealing material. Refer to NR 812 and NR 141 for more details on filling and sealing requirements.

General Instructions: Fill out Well/Drillhole/Borehole Filling & Sealing Form 3300-005 as completely as possible for each well or borehole filled and sealed. Information should be provided for every box on the form where available. Sign each form. Please note that these forms are subject to change. (Personally identifiable information on these forms is not intended to be used for any other purpose.)

Verification Only of Fill and Seal: If you are only verifying that filling and sealing has previously occurred on a well and are NOT performing any filling and sealing work on the well, check the box near the top of the form. Complete Parts 1 and 2 of the form completely and any information you can provide in Parts 3, 4 and 5. You must provide comments in Part 6 as to the method used to verify both the filling and sealing of the well. Complete Rart 7, excluding the date of Filling and Sealing. It will be implied that you did not do the filling and sealing work as stated in Part 7.

Route to: Check the appropriate routing box on the top of the form to assure proper routing to the DNR program requiring this well be filled and sealed. Mail the form and any attachments to the Department of Natural Resources, PO Box 7921, Madison, WI 53707-7921.

If you do any work to fill or seal the well, you must complete this form as intended and do not check the Verification Only of Fill and Seal box.

(1) WELL LOCATION INFORMATION

WI Unique Well #: Fill in the 2 alphabetic and 3 numeric Wisconsin Unique Well Number (WUWN) of the well being filled and sealed. Check the well, sample tap in the house or the fuse box for a WUWN if one has been assigned to the well.

Hicap #: If this was a high capacity well, enter the number assigned to the well by the Department.

Well Location: The well location can be determined by latitude and longitude coordinates in degrees and decimal minutes (to the thousandths, for example, latitude 43°04.347'N longitude 89°24.803'W) using a Global Positioning System (GPS) unit. If using GPS, check the method code for the GPS unit. The location can also be determined using Public Land Survey (Gov't Lot or 1/4 /1/4, 1/4, Section, Township and Range).

Method Code: This field lists data collection method codes for latitude and longitude coordinates. This field must be entered if a latitude/longitude coordinate is entered.

GPS006 - Mapping or recreational grade GPS receiver with no differential correction and selective availability off

GPS007 - Mapping or recreational grade GPS receiver with no differential correction and selective availability on

GPS008 - GPS receiver grade and or differential correction procedures unknown

(2) FACILITY / OWNER INFORMATION

If the well is located at a commercial or government facility, fill in the name of landfill, wastewater treatment facility, surface impoundment, spill or project.

Facility ID: Fill in the nine digits Facility ID (FID or PWS) assigned to the site by the Department.

License/Permit/Monitoring #: Fill in number assigned to facility by the Department. If unknown, leave blank.

Present Well Owner: Fill in the name, address, city, state and ZIP code of the present owner.

(3) WELL/DRILLHOLE/BOREHOLE INFORMATION

Original Construction Date: Fill in the original date of construction for the well or boring in mm/dd/yyyy format.

Depth to Water: Enter depth to water from ground surface.

- (4) PUMP, LINER, SCREEN, CASING, & SEALING MATERIAL: Check only one box where Yes, No or Not Applicable is indicated. Check all boxes which apply otherwise.
- (5) MATERIAL USED TO FILL THE WELL/DRILLHOLE: Enter the description of the filling material, the depth From and To, circle one measurement unit (Yards, Sacks or Volume), and enter the mix ratio or mud weight (in pounds per gallon).
- (6) COMMENTS: Describe any of the above boxes in more detail or add information as required to describe the filling and sealing procedures.
- (7) **NAME OF PERSON OR FIRM DOING SEALING WORK**: Enter the name (first and last) or firm name, address, and phone number of the person who supervised the work.

State of Wis., Dept. of Natural Resources

Street or Route

Brookfield

City

175 N Corporate Drive, Suite 160

State

WI

ZIP Code

53045

Well / Drillhole / Borehole Filling & Sealing

Form 3300-005 (R 4/08)

Page 1 of 2

Notice: Completion of this report is required bychs. 160, 281, 283, 289, 291-293, 295, and 299, Wis. Stats., and ch. NR 141, Wis. Adm. Code. In accordance with chs. 281, 289, 291-293, 295, and 299, Wis. Stats., failure to file this form may result in a forfeiture of between \$10-25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. Return form to the appropriate DNR office and bureau. See instructions on reverse for more information.

			R	oute t	ю:							
☐ Verification Only of	Fill and	Seal	- 1	Dı	rinking Water		Watershed/	Wastewater	Reme	diation/R	ledevelop	ment
				W	aste Managen	nent	Other:					
1. Well Location Informa	tion					2 Facilit	y/ Owner	nformation				
	/I Unique V		Hic	ар#		Facility Nan	пе					
Dane	emoved We	ell				Hartmeye						
Lattitude / Longitude (Degree	es and Min	utes)	Method C	ode (see instructio	ns) Facility ID (I	FID or PVV	>)				
		' N W				License/Per		ing #				
1/4/1/4 1/4	Sec	tion	Towns	ship	Range	E Original We	ell Owner					
or Gov't Lot #				N		w						
Well Street Address			-			Present We	II Owner					
2007 Roth Street												
Well City, Village or Town				Well Z	ZIP Code	— Mailing Add	ress of Pre	sent Owner				
Madison				5370)4	011 (12			loi i	Irun o		_
Subdivision Name				Lot#		City of Pres	ent Owner		State	ZIP C	ode	
						4 Pump I	iner Scr	een, Casing & Sea	ling Ma	terial		_
Reason For Removal From S	Service M	/I Uniqu	ie Well # o	of Rep	lacement We				inig ma	Cilai		_
Borehole Only						Pump and p	iping remov	ed?		Yes	No	WA
3. Well / Drillhole / Boreh	nole Infor	mation	1			Liner(s) remo	oved?			Yes	No	N/A
Manianian Well	Origin	nal Con	struction	Date	(mm/dd/yyyy)	Screen remo	ved?			Yes	No	
	Monitoring Vell 4/16/2019						n place?			Yes	No	(V/A)
Water Well	lf a W	/ell Con:	struction R	Report	is available,	Was casing	cut off belo	w surface?		Yes	No	(N/A)
Borehole / Drillhole	pleas	e attac	h.			Did sealing	material rise	e to surface?		(Yes)	No	N/A
Construction Type:						Did material				Yes	(No	N/A
Drilled Driv	ven (Sandpo	oint)		Dug		If yes, was h				Yes	No	(V/A)
Other (specify):						If bentonii with water	te chips wer	e used, were they hyewn safe source?	drated	Yes	No	€/A)
Formation Type:						Required Me	ethod of Pla	cing Sealing Material				$\overline{}$
Unconsolidated Formation			Bedrock			Conduct	tor Pipe-Gra	vity Conductor	Pipe-Pun	nped		
Total Well Depth From Groun	nd Surface	(ft.) C	asing Dia	mete	r (in.)	Screene	d & Poured	Other (Exp	lain):			
NA	12 Gar. 25.	4000	IA		. ()	(Benton	ite Chips)					
						Sealing Mate	erials					
Lower Drillhole Diameter (in. NA)		asing De IA	pth (ft	:.)	Neat Cement Sand-Ce	: Grout ement (Cond	crete) Grout			y (11 lb./ថ្ l Slurry" '	
Was well annular space grout	ed?	Υ	'es	No	Unknov	vn Concret			Bentoni		>	
If yes, to what depth (feet)?		Depth f	to Water (feet)			-	nd Monitoring Well Bo				
NA		NA		/		Bentonit Granula	e Unips r Bentonite		onite - Cer onite - Sar			
5. Material Used To Fill Well / Drillhole					From (ft.)	To (ft.)	No. Yards, Sacks or Volume (circ		N	lix Ratio	or	
	Bentonit	e Chip	s			Surface	5	or voiding form	310 01107		ida iroig	,,,,
6. Comments												
Boring ID: 3-3												
	-1-								DND			-
7. Supervision of Wor		Caclli	_ de:	_ 4/	15-4-	f Filling 0.0	a langua labat i	Deta Desail	DNR Us	_		
Name of Person or Firm Doir Ramboll/On-Site Enviro		sealing	g Licens	e#	4/16/	•	g (mm/ad/y	yyy) Date Received		loted By	/	

Telephone Number

262) 901-3506

Signature of Person Doing Work

Comments

Date Signed

04/30/2019

Well Filling and Sealing

Wisconsin Administrative Code (NR81 1, NR 812, and NR 141 requires well owners to permanently fill and seal any unused wells/drillholes/boreholes on their property. As of June 1, 2008 water supply wells can only be filled and sealed by licensed well drillers and pump installers.

- 1. Remove any pump, pump piping, debris or other obstacles that could interfere with the sealing operation.
- 2. Except when bentonite chips are used, the sealing material must be placed with the use of a conductor (tremie) pipe to fill the entire well column to the top with required sealing material. Refer to NR 812 and NR 141 for more details on filling and sealing requirements.

General Instructions: Fill out Well/Drillhole/Borehole Filling & Sealing Form 3300-005 as completely as possible for each well or borehole filled and sealed. Information should be provided for every box on the form where available. Sign each form. Please note that these forms are subject to change. (Personally identifiable information on these forms is not intended to be used for any other purpose.)

Verification Only of Fill and Seal: If you are only verifying that filling and sealing has previously occurred on a well and are NOT performing any filling and sealing work on the well, check the box near the top of the form. Complete Parts 1 and 2 of the form completely and any information you can provide in Parts 3, 4 and 5. You must provide comments in Part 6 as to the method used to verify both the filling and sealing of the well. Complete Rart 7, excluding the date of Filling and Sealing. It will be implied that you did not do the filling and sealing work as stated in Part 7.

Route to: Check the appropriate routing box on the top of the form to assure proper routing to the DNR program requiring this well be filled and sealed. Mail the form and any attachments to the Department of Natural Resources, PO Box 7921, Madison, WI 53707-7921.

If you do any work to fill or seal the well, you must complete this form as intended and do not check the Verification Only of Fill and Seal box.

(1) WELL LOCATION INFORMATION

WI Unique Well #: Fill in the 2 alphabetic and 3 numeric Wisconsin Unique Well Number (WUWN) of the well being filled and sealed. Check the well, sample tap in the house or the fuse box for a WUWN if one has been assigned to the well.

Hicap #: If this was a high capacity well, enter the number assigned to the well by the Department.

Well Location: The well location can be determined by latitude and longitude coordinates in degrees and decimal minutes (to the thousandths, for example, latitude 43°04.347'N longitude 89°24.803'W) using a Global Positioning System (GPS) unit. If using GPS, check the method code for the GPS unit. The location can also be determined using Public Land Survey (Gov't Lot or 1/4 /1/4, 1/4, Section, Township and Range).

Method Code: This field lists data collection method codes for latitude and longitude coordinates. This field must be entered if a latitude/longitude coordinate is entered.

GPS006 - Mapping or recreational grade GPS receiver with no differential correction and selective availability off

GPS007 - Mapping or recreational grade GPS receiver with no differential correction and selective availability on

GPS008 - GPS receiver grade and or differential correction procedures unknown

(2) FACILITY / OWNER INFORMATION

If the well is located at a commercial or government facility, fill in the name of landfill, wastewater treatment facility, surface impoundment, spill or project.

Facility ID: Fill in the nine digits Facility ID (FID or PWS) assigned to the site by the Department.

License/Permit/Monitoring #: Fill in number assigned to facility by the Department. If unknown, leave blank.

Present Well Owner: Fill in the name, address, city, state and ZIP code of the present owner.

(3) WELL/DRILLHOLE/BOREHOLE INFORMATION

Original Construction Date: Fill in the original date of construction for the well or boring in mm/dd/yyyy format.

Depth to Water: Enter depth to water from ground surface.

- (4) PUMP, LINER, SCREEN, CASING, & SEALING MATERIAL: Check only one box where Yes, No or Not Applicable is indicated. Check all boxes which apply otherwise.
- (5) MATERIAL USED TO FILL THE WELL/DRILLHOLE: Enter the description of the filling material, the depth From and To, circle one measurement unit (Yards, Sacks or Volume), and enter the mix ratio or mud weight (in pounds per gallon).
- (6) COMMENTS: Describe any of the above boxes in more detail or add information as required to describe the filling and sealing procedures.
- (7) **NAME OF PERSON OR FIRM DOING SEALING WORK**: Enter the name (first and last) or firm name, address, and phone number of the person who supervised the work.

State of Wis., Dept. of Natural Resources

Well / Drillhole / Borehole Filling & Sealing

Form 3300-005 (R 4/08)

Page 1 of 2

Notice: Completion of this report is required bychs. 160, 281, 283, 289, 291-293, 295, and 299, Wis. Stats., and ch. NR 141, Wis. Adm. Code. In accordance with chs. 281, 289, 291-293, 295, and 299, Wis. Stats., failure to file this form may result in a forfeiture of between \$10-25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. Return form to the appropriate DNR office and bureau. See instructions on reverse for more information.

Verification Only o	F	Route	to: Prinking Water Vaste Managemen		Watershed/M	/astewater	Reme	diation/F	Redevelop	ment		
1. Well Location Inform	ation					2 Facility	y/ Owner In	formation				
		ie Well#	of H	icap#		Facility Nam	ne .					$\overline{}$
Dane	Removed	d Well					r Property					
Lattitude / Longitude (Degr	ees and	Minutes)	Method	Code	(see instructions)	Facility ID (F	FID or PWS)					
		'N				License/Per	mit/Monitorir	ng #				-
7/411/4 1/4		Section	Towr	nship	Range E	Original We	ll Owner					
or Gov't Lot#				N	w							
Well Street Address						Present We	ll Owner					
2007 Roth Street						Mailing Add	rose of Proc	ant Owner				
Well City, Village or Town				Well	ZIP Code	Mailing Add	ress of Presi	ent Owner				
Madison				537	04	City of Pres	ent Owner		State	ZIPC	ode	
Subdivision Name				Lot #		City of Fres	ent Owner		State	2.1	oue	
Reason For Removal From	Service	- IWI Uni	ique Well #	of Re	placement Well	4. Pump, L	iner, Scre	en, Casing & Sea	ling Ma	terial		
Borehole Only	orehole Only					Pump and p	iping remove	d?		Yes	No	(VA)
3. Well / Drillhole / Bore	Well / Drillhole / Borehole Information					Liner(s) remo	ved?			Yes	No	N/A
Moll.	Original Constru				(mm/dd/yyyy)	Screen remo	ved?			Yes	No	
	Monitoring Well 4/16/2019					Casing left in	place?			Yes	No	
Water Well Borehole / Drillhole				Report	is available,	Was casing	cut off below	surface?		Yes	No	(N/A)
	р	lease att	ach			1 .	material rise			(es)	No	N/A
Construction Type:						Did material				Yes	(M)	N/A
Other (specify):	riven (Sar	ndpoint)		Dug		If yes, was h If bentonit with water	e chips were	? · used, were they hyo n safe source?	trated	Yes Yes	No No	
Formation Type:						Required Me	thod of Placi	ing Sealing Material				$\overline{}$
Unconsolidated Formation	on		Bedroc	k		Conduct	or Pipe-Gravi	Conductor	Pipe-Pun	nped		
Total Well Depth From Gro	und Surf	ace (ft.)	Casing D	iamete	er (in.)	Screene	d & Poured	Other (Exp	lain):			
NA			NA				ite Chips)					
Lower Drillhole Diameter (in	2.)		Casing D	enth (1	ft)	Sealing Mate Neat Cement			Clay Ca	nd Clus	/44 lb /a	-al+\
NA	1=)		NA	opui (i	u)		ement (Concr	ete) Grout			y (11 lb./g I Slurry" '	
Was well annular space grou	ıted?		Yes	No	Unknown	Concrete	,	•	Bentoni			
If yes, to what depth (feet)?		Dent	th to Water		OTIKITOWIT		-	f Monitoring Well Bo	reholes (only:		
NA		NA	II to water	(ICCL)		Bentonite	e Chips Bentonite		nite - Cer			
5. Material Used To Fill Well / Drillhole								No. Yards, Sacks		1 1	lix Ratio	or
- waterial Osed TO Fill	_					From (ft.)	To (ft.)	or Volume (circ	le one)	N	lud Weig	ht
	Bento	onite Ch	nips			Surface	5			-		-
6. Comments												
Boring ID: 13-3												
	> # lz							1	DND U-	o O-1		
 Supervision of Wo Name of Person or Firm Do 		n & Seal	ing licer	ise#	Date of Fil	lling & Sealing	n (mm/dd/w	vv) Date Received	DNR Us	oted B	,	

Ramboll/On-Site Environmental 4/16/2019 Street or Route Telephone Number (262) 901-350							
Licer	nse#			Date Received	Noted By		
			Telephone Number (262) 901-3506	Comments			
-	ZIP Code 53045				Date Signed 04/30/2019		
	g Licer State WI	State ZIP Code	4/16/2 State ZIP Code	4/16/2019 Telephone Number (262) 901-3506 State ZIP Code Signature of Person Doing V	4/16/2019 Telephone Number Comments (262) 901-3506 State ZIP Code Signature of Person Doing Work		

Well Filling and Sealing

Wisconsin Administrative Code (NR81 1, NR 812, and NR 141 requires well owners to permanently fill and seal any unused wells/drillholes/boreholes on their property. As of June 1, 2008 water supply wells can only be filled and sealed by licensed well drillers and pump installers.

- 1. Remove any pump, pump piping, debris or other obstacles that could interfere with the sealing operation.
- 2. Except when bentonite chips are used, the sealing material must be placed with the use of a conductor (tremie) pipe to fill the entire well column to the top with required sealing material. Refer to NR 812 and NR 141 for more details on filling and sealing requirements.

General Instructions: Fill out Well/Drillhole/Borehole Filling & Sealing Form 3300-005 as completely as possible for each well or borehole filled and sealed. Information should be provided for every box on the form where available. Sign each form. Please note that these forms are subject to change. (Personally identifiable information on these forms is not intended to be used for any other purpose.)

Verification Only of Fill and Seal: If you are only verifying that filling and sealing has previously occurred on a well and are NOT performing any filling and sealing work on the well, check the box near the top of the form. Complete Parts 1 and 2 of the form completely and any information you can provide in Parts 3, 4 and 5. You must provide comments in Part 6 as to the method used to verify both the filling and sealing of the well. Complete Rart 7, excluding the date of Filling and Sealing. It will be implied that you did not do the filling and sealing work as stated in Part 7.

Route to: Check the appropriate routing box on the top of the form to assure proper routing to the DNR program requiring this well be filled and sealed. Mail the form and any attachments to the Department of Natural Resources, PO Box 7921, Madison, WI 53707-7921.

If you do any work to fill or seal the well, you must complete this form as intended and do not check the Verification Only of Fill and Seal box.

(1) WELL LOCATION INFORMATION

WI Unique Well #: Fill in the 2 alphabetic and 3 numeric Wisconsin Unique Well Number (WUWN) of the well being filled and sealed. Check the well, sample tap in the house or the fuse box for a WUWN if one has been assigned to the well.

Hicap #: If this was a high capacity well, enter the number assigned to the well by the Department.

Well Location: The well location can be determined by latitude and longitude coordinates in degrees and decimal minutes (to the thousandths, for example, latitude 43°04.347'N longitude 89°24.803'W) using a Global Positioning System (GPS) unit. If using GPS, check the method code for the GPS unit. The location can also be determined using Public Land Survey (Gov't Lot or 1/4 /1/4, 1/4, Section, Township and Range).

Method Code: This field lists data collection method codes for latitude and longitude coordinates. This field must be entered if a latitude/longitude coordinate is entered.

GPS006 - Mapping or recreational grade GPS receiver with no differential correction and selective availability off

GPS007 - Mapping or recreational grade GPS receiver with no differential correction and selective availability on

GPS008 - GPS receiver grade and or differential correction procedures unknown

(2) FACILITY / OWNER INFORMATION

If the well is located at a commercial or government facility, fill in the name of landfill, wastewater treatment facility, surface impoundment, spill or project.

Facility ID: Fill in the nine digits Facility ID (FID or PWS) assigned to the site by the Department.

License/Permit/Monitoring #: Fill in number assigned to facility by the Department. If unknown, leave blank.

Present Well Owner: Fill in the name, address, city, state and ZIP code of the present owner.

(3) WELL/DRILLHOLE/BOREHOLE INFORMATION

Original Construction Date: Fill in the original date of construction for the well or boring in mm/dd/yyyy format.

Depth to Water: Enter depth to water from ground surface.

- (4) PUMP, LINER, SCREEN, CASING, & SEALING MATERIAL: Check only one box where Yes, No or Not Applicable is indicated. Check all boxes which apply otherwise.
- (5) MATERIAL USED TO FILL THE WELL/DRILLHOLE: Enter the description of the filling material, the depth From and To, circle one measurement unit (Yards, Sacks or Volume), and enter the mix ratio or mud weight (in pounds per gallon).
- (6) COMMENTS: Describe any of the above boxes in more detail or add information as required to describe the filling and sealing procedures.
- (7) **NAME OF PERSON OR FIRM DOING SEALING WORK**: Enter the name (first and last) or firm name, address, and phone number of the person who supervised the work.

State of Wis., Dept. of Natural Resources

Brookfield

WI

53045

Well / Drillhole / Borehole Filling & Sealing

Form 3300-005 (R 4/08)

Page 1 of 2

04/30/2019

Notice: Completion of this report is required bychs. 160, 281, 283, 289, 291-293, 295, and 299, Wis. Stats., and ch. NR 141, Wis. Adm. Code. In accordance with chs. 281, 289, 291-293, 295, and 299, Wis. Stats., failure to file this form may result in a forfeiture of between \$10-25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. Return form to the appropriate DNR office and bureau. See instructions on reverse for more information.

_		Route to:						-		_	
☐ Verification Only of F	ill and Se	al		king Water ste Manageme	nt	Watershed/W Other:	astewater	Remed	diation/R	edevelop	ment
1. Well Location Information	n				2 Facilit	y/ Owner In	formation				
County WIL	Inique Well #	# of	licap#		Facility Nan						
Dane	loved Well				Hartmeye	r Property					
Lattitude / Longitude (Degrees	and Minutos	a) Mothod	Codo (so	o inetructions	Facility ID (FID or PWS)					
) Welliou	Code (se	e il istructions							
· · ·	'W				License/Pe	rmit/Monitorin	g#				
1/41/4 1/4	Section	Town	nship R	lange E	Original We	ell Owner					-7
or Gov't Lot #	5 L		N	W							
Well Street Address	_				Present We	ell Owner					
2007 Roth Street					Mailing Add	roce of Broce	ant Ouman				_
Well City, Village or Town			Well ZIF	Code	- Ivialing Add	ress of Prese	in Owner				
Madison			53704		City of Pres	ent Owner		State	ZIP C	ode	_
Subdivision Name			Lot#		John of the	one owner		Oldic	-" 0	500	
Reason For Removal From Ser	vice WI U	nique Well #	of Replac	cement Well	4. Pump,	Liner, Scree	en, Casing & Sea	ling Mat	erial	_	
Borehole Only					Pump and p	iping removed	! ?		Yes	No	N/A
3. Well / Drillhole / Borehol	e Informa	tion			Liner(s) reme	oved?			Yes	No	N/A
)0/-II	Original (Construction	n Date (m	ım/dd/yyyy)	Screen remo	ved?			Yes	No	(N/A)
Monitoring Well	4/16/20	19			Casing left in	n place?			Yes	No	SA SA
Water Well	Report is a	available,	Was casing	cut off below	surface?		Yes	No	(N/A)		
Borehole / Drillhole	please a	ttach.				material rise t			(es)	No	N/A
Construction Type:					Did material	settle after 24	l hours?		Yes	No No	N/A
Drilled Driver	(Sandpoint)		Dug		If yes, was h	ole retopped?			Yes	No	(V/A)
Other (specify):					with water	te chips were from a knowr	used, were they hyd n safe source?	irated	Yes	No	(VA)
Formation Type:							ng Sealing Material				$\overline{}$
Unconsolidated Formation		Bedroo	k		Conduc	tor Pipe-Gravit	Conductor	Pipe-Pum	ped		
Total Well Depth From Ground	Surface (ft.)	Casing D	iameter (i	in.)	Screene	d & Poured	Other (Exp	lain):			
NA		NA	,	,	(Benton Sealing Mate	ite Chips) erials					
Lower Drillhole Diameter (in.)		Casing D	epth (ft.)		Neat Cement	Grout		Clay-Sar	nd Slurry	/ (11 lb./g	jal. wt.)
NA		NA			Sand-C	ement (Concre	ete) Grout	Bentoni	te-Sand	Slurry" "	
Was well annular space grouted	?	Yes	No	Unknown	Concret	е		Bentonit	e Chips	>	
If yes, to what depth (feet)?	Der	oth to Water	(feet)			-	Monitoring Well Bo		-		
NA	NA NA		(ICCL)		Bentonit			nite - Cen			
					-	r Bentonite	No. Yards, Sacks	nite - San	-	lix Ratio	05
5. Material Used To Fill We	II / Drillho	le			From (ft.)	To (ft.)	or Volume (circ			lud Weig	
Be	entonite C	hips			Surface	5					
6. Comments											_
Boring ID: 8-4											
7. Supervision of Work							1	DNR Use	Only		1
Name of Person or Firm Doing	Filling & Sea	aling Licer	nse#	Date of F	illing & Sealin	g (mm/dd/vvv	y) Date Received		oted By	,	
Ramboll/On-Site Environr				4/16/20		,,,,,					
Street or Route				T	elephone Nur	nber	Comments				
175 N Corporate Drive, S	uite 160		ZIP Cod	- 1	262) 901-3	506					
City					Signature of	Person Doing	g Work	D	ate Sign	ed	

Well Filling and Sealing

Wisconsin Administrative Code (NR81 1, NR 812, and NR 141 requires well owners to permanently fill and seal any unused wells/drillholes/boreholes on their property. As of June 1, 2008 water supply wells can only be filled and sealed by licensed well drillers and pump installers.

- 1. Remove any pump, pump piping, debris or other obstacles that could interfere with the sealing operation.
- 2. Except when bentonite chips are used, the sealing material must be placed with the use of a conductor (tremie) pipe to fill the entire well column to the top with required sealing material. Refer to NR 812 and NR 141 for more details on filling and sealing requirements.

General Instructions: Fill out Well/Drillhole/Borehole Filling & Sealing Form 3300-005 as completely as possible for each well or borehole filled and sealed. Information should be provided for every box on the form where available. Sign each form. Please note that these forms are subject to change. (Personally identifiable information on these forms is not intended to be used for any other purpose.)

Verification Only of Fill and Seal: If you are only verifying that filling and sealing has previously occurred on a well and are NOT performing any filling and sealing work on the well, check the box near the top of the form. Complete Parts 1 and 2 of the form completely and any information you can provide in Parts 3, 4 and 5. You must provide comments in Part 6 as to the method used to verify both the filling and sealing of the well. Complete Rart 7, excluding the date of Filling and Sealing. It will be implied that you did not do the filling and sealing work as stated in Part 7.

Route to: Check the appropriate routing box on the top of the form to assure proper routing to the DNR program requiring this well be filled and sealed. Mail the form and any attachments to the Department of Natural Resources, PO Box 7921, Madison, WI 53707-7921.

If you do any work to fill or seal the well, you must complete this form as intended and do not check the Verification Only of Fill and Seal box.

(1) WELL LOCATION INFORMATION

WI Unique Well #: Fill in the 2 alphabetic and 3 numeric Wisconsin Unique Well Number (WUWN) of the well being filled and sealed. Check the well, sample tap in the house or the fuse box for a WUWN if one has been assigned to the well.

Hicap #: If this was a high capacity well, enter the number assigned to the well by the Department.

Well Location: The well location can be determined by latitude and longitude coordinates in degrees and decimal minutes (to the thousandths, for example, latitude 43°04.347'N longitude 89°24.803'W) using a Global Positioning System (GPS) unit. If using GPS, check the method code for the GPS unit. The location can also be determined using Public Land Survey (Gov't Lot or 1/4 /1/4, 1/4, Section, Township and Range).

Method Code: This field lists data collection method codes for latitude and longitude coordinates. This field must be entered if a latitude/longitude coordinate is entered.

GPS006 - Mapping or recreational grade GPS receiver with no differential correction and selective availability off

GPS007 - Mapping or recreational grade GPS receiver with no differential correction and selective availability on

GPS008 - GPS receiver grade and or differential correction procedures unknown

(2) FACILITY / OWNER INFORMATION

If the well is located at a commercial or government facility, fill in the name of landfill, wastewater treatment facility, surface impoundment, spill or project.

Facility ID: Fill in the nine digits Facility ID (FID or PWS) assigned to the site by the Department.

License/Permit/Monitoring #: Fill in number assigned to facility by the Department. If unknown, leave blank.

Present Well Owner: Fill in the name, address, city, state and ZIP code of the present owner.

(3) WELL/DRILLHOLE/BOREHOLE INFORMATION

Original Construction Date: Fill in the original date of construction for the well or boring in mm/dd/yyyy format.

Depth to Water: Enter depth to water from ground surface.

- (4) PUMP, LINER, SCREEN, CASING, & SEALING MATERIAL: Check only one box where Yes, No or Not Applicable is indicated. Check all boxes which apply otherwise.
- (5) MATERIAL USED TO FILL THE WELL/DRILLHOLE: Enter the description of the filling material, the depth From and To, circle one measurement unit (Yards, Sacks or Volume), and enter the mix ratio or mud weight (in pounds per gallon).
- (6) COMMENTS: Describe any of the above boxes in more detail or add information as required to describe the filling and sealing procedures.
- (7) **NAME OF PERSON OR FIRM DOING SEALING WORK**: Enter the name (first and last) or firm name, address, and phone number of the person who supervised the work.

State of Wis., Dept. of Natural Resources

Street or Route

Brookfield

City

175 N Corporate Drive, Suite 160

Well / Drillhole / Borehole Filling & Sealing

Form 3300-005 (R 4/08)

Page 1 of 2

Notice: Completion of this report is required bychs. 160, 281, 283, 289, 291-293, 295, and 299, Wis. Stats., and ch. NR 141, Wis. Adm. Code. In accordance with chs. 281, 289, 291-293, 295, and 299, Wis. Stats., failure to file this form may result in a forfeiture of between \$10-25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. Return form to the appropriate DNR office and bureau. See instructions on reverse for more information.

_				o:							
Verification Only of	Fill and Sea	d		rinking Water 'aste Managemen		Watershed/V Other:		Reme	diation/F	Redevelop	ment
1. Well Location Informa	tion	-				y/ Owner II					
	/I Unique Well#	of Hic	ар#		Facility Nan		Homiation				_
_	emoved Well	01 1110	мр <i>п</i>		White Challenge and	r Property					
Dane						FID or PWS					_
Lattitude / Longitude (Degree	es and Minutes)) Method C	Code (see instructions)	Tr domity 15 (15 01 1 110					
	' N				License/Per	mit/Monitori	na #				-
	' w										
	Section	Towns	hin	Range E	Original We	ell Owner					
1/4/1/4 1/4	Section	TOWITS		Mange L	"						
or Gov't Lot#			N	"	Present We	ll Owner					
Well Street Address											
2007 Roth Street					Mailing Add	ress of Pres	ent Owner				
Well City, Village or Town				ZIP Code							
Madison			537	04	City of Pres	ent Owner		State	ZIP C	ode	_
Subdivision Name			Lot#					1			
Reason For Removal From S	Service IMI Uni	igue Well #	of Rer	placement Well	4. Pump, I	_iner, Scre	en, Casing & Sea	ling Mat	terial		
Borehole Only	SCI VICE IVII OIII	ique vven ir v	OI I (C)	Macchieff Wen	Pump and p	iping remove	d2		Yes	No	Q/A
3. Well / Drillhole / Boret	ala Informati	ion			Liner(s) remo	_			Yes	No	
3. Well / Drillinole / Borel			Data	(mana lalal la a a a l	1						
Monitoring Well Original Construction Date (mm/dd/yyy					Screen remo				Yes Yes	No	
Water Well							No				
Borehole / Drillhole	If a Well Co	onstruction F	Report	is available,	_	cut off below			Yes	No	(N/A)
Construction Type:	picase att	don				material rise			(es)	No	N/A
						settle after 2			Yes	(M)	N/A
	ven (Sandpoint)		Dug		If yes, was h	ole retopped	? Lused were they hyd	Irated	Yes	No	N/A
Other (specify):					with water	from a know	used, were they hyd n safe source?	nated	Yes	No	N/A
Formation Type:					Required Me	ethod of Plac	ing Sealing Material				
Unconsolidated Formation	\supset	Bedrock			Conduct	or Pipe-Grav	Conductor	Pipe-Pum	ıped		
Total Well Depth From Groun	nd Surface (ft.)	Casing Dia	mete	r (in.)	Screene	d & Poured	Other (Expl	ain):			
NA	` (NA		,		ite Chips)					
		-			Sealing Mate						
Lower Drillhole Diameter (in. NA)	Casing De NA	ptn (n	i)	Neat Cement					y (11 lb /g	
INA		INA				ement (Concr				Slurry" "	
Was well annular space grout	ed?	Yes	No	Unknown	Concret			Bentonit)	
If yes, to what depth (feet)?	Dept	th to Water (feet)		Bentonit		d Monitoring Well Bo	nite - Cen	-		
NA	NA					r Bentonite					
5. Material Used To Fill \							No. Yards, Sacks		l N	lix Ratio	
			_		From (ft.)	To (ft.)	or Volume (circ	le one)	N	lud Weig	ht
	Bentonite Ch	nps			Surface	5		-	-		_
							r		-		_
6. Comments									4		_
Boring ID: 3-5											
7. Supervision of Wor	·k							DNR Use	e Only		
Name of Person or Firm Doir		ling Licens	e#	Date of Fi	ling & Sealing	(mm/dd/vv	yy) Date Received		oted By		
Ramboll/On-Site Enviro				4/16/20		1					

Telephone Number

(262)901-3506

Signature of Person Doing Work

ZIP Code

53045

State

WI

Comments

Date Signed

04/30/2019

Well Filling and Sealing

Wisconsin Administrative Code (NR81 1, NR 812, and NR 141 requires well owners to permanently fill and seal any unused wells/drillholes/boreholes on their property. As of June 1, 2008 water supply wells can only be filled and sealed by licensed well drillers and pump installers.

- 1. Remove any pump, pump piping, debris or other obstacles that could interfere with the sealing operation.
- 2. Except when bentonite chips are used, the sealing material must be placed with the use of a conductor (tremie) pipe to fill the entire well column to the top with required sealing material. Refer to NR 812 and NR 141 for more details on filling and sealing requirements.

General Instructions: Fill out Well/Drillhole/Borehole Filling & Sealing Form 3300-005 as completely as possible for each well or borehole filled and sealed. Information should be provided for every box on the form where available. Sign each form. Please note that these forms are subject to change. (Personally identifiable information on these forms is not intended to be used for any other purpose.)

Verification Only of Fill and Seal: If you are only verifying that filling and sealing has previously occurred on a well and are NOT performing any filling and sealing work on the well, check the box near the top of the form. Complete Parts 1 and 2 of the form completely and any information you can provide in Parts 3, 4 and 5. You must provide comments in Part 6 as to the method used to verify both the filling and sealing of the well. Complete Rart 7, excluding the date of Filling and Sealing. It will be implied that you did not do the filling and sealing work as stated in Part 7.

Route to: Check the appropriate routing box on the top of the form to assure proper routing to the DNR program requiring this well be filled and sealed. Mail the form and any attachments to the Department of Natural Resources, PO Box 7921, Madison, WI 53707-7921.

If you do any work to fill or seal the well, you must complete this form as intended and do not check the Verification Only of Fill and Seal box.

(1) WELL LOCATION INFORMATION

WI Unique Well #: Fill in the 2 alphabetic and 3 numeric Wisconsin Unique Well Number (WUWN) of the well being filled and sealed. Check the well, sample tap in the house or the fuse box for a WUWN if one has been assigned to the well.

Hicap #: If this was a high capacity well, enter the number assigned to the well by the Department.

Well Location: The well location can be determined by latitude and longitude coordinates in degrees and decimal minutes (to the thousandths, for example, latitude 43°04.347'N longitude 89°24.803'W) using a Global Positioning System (GPS) unit. If using GPS, check the method code for the GPS unit. The location can also be determined using Public Land Survey (Gov't Lot or 1/4 /1/4, 1/4, Section, Township and Range).

Method Code: This field lists data collection method codes for latitude and longitude coordinates. This field must be entered if a latitude/longitude coordinate is entered.

GPS006 - Mapping or recreational grade GPS receiver with no differential correction and selective availability off

GPS007 - Mapping or recreational grade GPS receiver with no differential correction and selective availability on

GPS008 - GPS receiver grade and or differential correction procedures unknown

(2) FACILITY / OWNER INFORMATION

If the well is located at a commercial or government facility, fill in the name of landfill, wastewater treatment facility, surface impoundment, spill or project.

Facility ID: Fill in the nine digits Facility ID (FID or PWS) assigned to the site by the Department.

License/Permit/Monitoring #: Fill in number assigned to facility by the Department. If unknown, leave blank.

Present Well Owner: Fill in the name, address, city, state and ZIP code of the present owner.

(3) WELL/DRILLHOLE/BOREHOLE INFORMATION

Original Construction Date: Fill in the original date of construction for the well or boring in mm/dd/yyyy format.

Depth to Water: Enter depth to water from ground surface.

- (4) PUMP, LINER, SCREEN, CASING, & SEALING MATERIAL: Check only one box where Yes, No or Not Applicable is indicated. Check all boxes which apply otherwise.
- (5) MATERIAL USED TO FILL THE WELL/DRILLHOLE: Enter the description of the filling material, the depth From and To, circle one measurement unit (Yards, Sacks or Volume), and enter the mix ratio or mud weight (in pounds per gallon).
- (6) COMMENTS: Describe any of the above boxes in more detail or add information as required to describe the filling and sealing procedures.
- (7) **NAME OF PERSON OR FIRM DOING SEALING WORK**: Enter the name (first and last) or firm name, address, and phone number of the person who supervised the work.

State of Wis., Dept. of Natural Resources

Brookfield

WI

53045

Well / Drillhole / Borehole Filling & Sealing

Form 3300-005 (R 4/08)

04/30/2019

Notice: Completion of this report is required bychs. 160, 281, 283, 289, 291-293, 295, and 299, Wis. Stats, and ch. NR 141, Wis. Adm. Code. In accordance with chs. 281, 289, 291-293, 295, and 299, Wis. Stats., failure to file this form may result in a forfeiture of between \$10-25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. Return form to the appropriate DNR office and bureau. See instructions on reverse for more information.

_				Route to:								
Dane Removed W Lattitude / Longitude (Degrees and Mi A///	Sea			g Water Managemen	t	Watershed/Wa	astewater	Reme	diation/R	edevelop	ment	
1. Well I ocation Inform	ation						y/ Owner Inf	ormation				
		Vell #	of IH	icap#	_	Facility Nan		omitation .				_
	Removed W					/ 1000 mg - 1	r Property					
							FID or PWS)					
			Method	Code (see ii	nstructions)							
		, M				License/Per	mit/Monitoring	g #				
	Se	ction	Town	nship Ran	ge E	Original We	ell Owner					
				N	**	Present We	ll Owner					
N 125 + 2023 St. 125												
				MAIL ZID C	ada	Mailing Add	ress of Prese	nt Owner				
				Well ZIP C 53704	ode							
				Lot #		City of Pres	ent Owner		State	ZIP C	ode	
Subdivision Name				Lot #		1.0		0 : 00				
	Service V	VI Uni	que Well #	of Replacer	ment Well		iping removed	n, Casing & Sea	ling Mai	Yes	No	
	Well / Drillhole / Borehole Information Original Constru					Liner(s) remo		ŗ		Yes	No No	
3. Well / Drillilole / Bore	Manitoring Well Original Constr				(dd/saas)	Screen remo						
Monitoring Well				i Date (iiiii)	dd/yyyy)	Casing left in				Yes Yes	No No	
4/10/2019							Taraca.	fa==2				
Borehole / Drillhole		se atta		Report is ava	illable,	_	cut off belows			Yes	No	N/A N/A
Construction Type:						-	material rise to settle after 24			Yes Yes	No No	N/A N/A
	riven (Sando	oint)		Dug			ole retopped?	riodio.		Yes	No	(VA)
	Troi (Garap					If bentonil		used, were they hyd safe source?	rated	Yes	No	(A)
Formation Type:						Required Me	ethod of Placin	g Sealing Material				
Unconsolidated Formation	on		Bedroc	k			tor Pipe-Gravity		•	ped		
Total Well Depth From Gro	und Surface	(ft.)	Casing D	iameter (in.))		d & Poured	Other (Expl	ain):			_
NA			NA			(Benton Sealing Mate	ite Chips) erials					_
Lower Drillhole Diameter (in	1_)	- 7.7	Casing D	epth (ft.)		Neat Cement			Clay-Sa	nd Slurry	/ (11 lb./g	gal_wt_)
NA		-	NA			Sand-Co	ement (Concre	•	Benton	ite-Sand	Slurry" "	
Was well annular space grou	uted?		Yes	No	Unknown	Concret		Monitoring Well Bo	Bentonit		>	
If yes, to what depth (feet)?		Dept	h to Water	(feet)		Bentonit	_	-	nite - Cer		ıut	
NA		NA					r Bentonite		nite - San			
5. Material Used To Fill	Well / Dri	llhole)			From (ft.)	To (ft.)	No. Yards, Sacks or Volume (circ	Sealant	I M	lix Ratio	
	Bentonit	e Ch	ips			Surface	5					
6. Comments												_
Boring ID: %-6												
7. Supervision of Wo	ork								DNR Us	e Only		
	ame of Person or Firm Doing Filling & Sealing Licens			nse#	Date of Fi	lling & Sealin	g (mm/dd/yyy	y) Date Received		oted By		-
					4/16/20	19						
Street or Route						elephone Nur		Comments				
175 N Corporate Drive	, Suite 16	0		ZIP Code	(2	262) 901-3						
City						Signature of	Person Doing	Work	D	ate Sign	ed	

Well Filling and Sealing

Wisconsin Administrative Code (NR81 1, NR 812, and NR 141 requires well owners to permanently fill and seal any unused wells/drillholes/boreholes on their property. As of June 1, 2008 water supply wells can only be filled and sealed by licensed well drillers and pump installers.

- 1. Remove any pump, pump piping, debris or other obstacles that could interfere with the sealing operation.
- 2. Except when bentonite chips are used, the sealing material must be placed with the use of a conductor (tremie) pipe to fill the entire well column to the top with required sealing material. Refer to NR 812 and NR 141 for more details on filling and sealing requirements.

General Instructions: Fill out Well/Drillhole/Borehole Filling & Sealing Form 3300-005 as completely as possible for each well or borehole filled and sealed. Information should be provided for every box on the form where available. Sign each form. Please note that these forms are subject to change. (Personally identifiable information on these forms is not intended to be used for any other purpose.)

Verification Only of Fill and Seal: If you are only verifying that filling and sealing has previously occurred on a well and are NOT performing any filling and sealing work on the well, check the box near the top of the form. Complete Parts 1 and 2 of the form completely and any information you can provide in Parts 3, 4 and 5. You must provide comments in Part 6 as to the method used to verify both the filling and sealing of the well. Complete Rart 7, excluding the date of Filling and Sealing. It will be implied that you did not do the filling and sealing work as stated in Part 7.

Route to: Check the appropriate routing box on the top of the form to assure proper routing to the DNR program requiring this well be filled and sealed. Mail the form and any attachments to the Department of Natural Resources, PO Box 7921, Madison, WI 53707-7921.

If you do any work to fill or seal the well, you must complete this form as intended and do not check the Verification Only of Fill and Seal box.

(1) WELL LOCATION INFORMATION

WI Unique Well #: Fill in the 2 alphabetic and 3 numeric Wisconsin Unique Well Number (WUWN) of the well being filled and sealed. Check the well, sample tap in the house or the fuse box for a WUWN if one has been assigned to the well.

Hicap #: If this was a high capacity well, enter the number assigned to the well by the Department.

Well Location: The well location can be determined by latitude and longitude coordinates in degrees and decimal minutes (to the thousandths, for example, latitude 43°04.347'N longitude 89°24.803'W) using a Global Positioning System (GPS) unit. If using GPS, check the method code for the GPS unit. The location can also be determined using Public Land Survey (Gov't Lot or 1/4 /1/4, 1/4, Section, Township and Range).

Method Code: This field lists data collection method codes for latitude and longitude coordinates. This field must be entered if a latitude/longitude coordinate is entered.

GPS006 - Mapping or recreational grade GPS receiver with no differential correction and selective availability off

GPS007 - Mapping or recreational grade GPS receiver with no differential correction and selective availability on

GPS008 - GPS receiver grade and or differential correction procedures unknown

(2) FACILITY / OWNER INFORMATION

If the well is located at a commercial or government facility, fill in the name of landfill, wastewater treatment facility, surface impoundment, spill or project.

Facility ID: Fill in the nine digits Facility ID (FID or PWS) assigned to the site by the Department.

License/Permit/Monitoring #: Fill in number assigned to facility by the Department. If unknown, leave blank.

Present Well Owner: Fill in the name, address, city, state and ZIP code of the present owner.

(3) WELL/DRILLHOLE/BOREHOLE INFORMATION

Original Construction Date: Fill in the original date of construction for the well or boring in mm/dd/yyyy format.

Depth to Water: Enter depth to water from ground surface.

- (4) PUMP, LINER, SCREEN, CASING, & SEALING MATERIAL: Check only one box where Yes, No or Not Applicable is indicated. Check all boxes which apply otherwise.
- (5) MATERIAL USED TO FILL THE WELL/DRILLHOLE: Enter the description of the filling material, the depth From and To, circle one measurement unit (Yards, Sacks or Volume), and enter the mix ratio or mud weight (in pounds per gallon).
- (6) COMMENTS: Describe any of the above boxes in more detail or add information as required to describe the filling and sealing procedures.
- (7) **NAME OF PERSON OR FIRM DOING SEALING WORK**: Enter the name (first and last) or firm name, address, and phone number of the person who supervised the work.

State of Wis., Dept. of Natural Resources

175 N Corporate Drive, Suite 160

State

WI

ZIP Code

53045

City

Brookfield

Well / Drillhole / Borehole Filling & Sealing

Form 3300-005 (R 4/08)

Page 1 of 2

Notice: Completion of this report is required bychs. 160, 281, 283, 289, 291-293, 295, and 299, Wis. Stats., and ch. NR 141, Wis. Adm. Code. In accordance with chs. 281, 289, 291-293, 295, and 299, Wis. Stats., failure to file this form may result in a forfeiture of between \$10-25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. Return form to the appropriate DNR office and bureau. See instructions on reverse for more information.

		1	Route	to:							
Verification Only of	Fill and Se	eal		Orinking Water Waste Managemen	t	Watershed/V		Remed	iation/R	edevelop	ment
1. Well Location Information	tion				2 Facilit	y/ Owner Ir					
	I Unique Well	# of H	licap#	1	Facility Nan						_
Re	emoved Well	111 01	iioap ii			r Property					
Dane						FID or PWS)					
Lattitude / Longitude (Degree	es and Minute	es) Method	Code	(see instructions)	Tracking her (
° ,	'	N			License/Per	mit/Monitoria	na #				_
	+W	/			18.36.47.36.57.	5.05 50 50 50					
1/4/1/4 1/4	Sectio	in I Tow	nship	Range E	Original We	ell Owner					
	Occio	,, 10W	'	J . J.	5						
or Gov't Lot #			N		Present We	ll Owner					
Well Street Address											
2007 Roth Street			h		Mailing Add	ress of Pres	ent Owner				
Well City, Village or Town			7	ZIP Code							
Madison			537		City of Pres	ent Owner		State	ZIP C	ode	
Subdivision Name			Lot #	#					1		
	No.				4. Pump. i	Liner. Scre	en, Casing & S	Sealing Mate	erial		
Reason For Removal From S	Service WIL	Jnique Well	of Re	eplacement Well	-						
Borehole Only					4	iping remove	d?		Yes	No	
3. Well / Drillhole / Boreh	Vell / Drillhole / Borehole Information Original Const				Liner(s) remo	oved?			Yes	No	(VA)
Monitoring Well	-		n Date	e (mm/dd/yyyy)	Screen remo	ved?			Yes	No	
Monitoring Well 4/16/2019					Casing left in	n place?			Yes	No	(N/A)
Water Well If a Well Construction Report is available					Was casing	cut off below	surface?		Yes	No	(N/A)
Borehole / Drillhole	please	attach.			Did sealing	material rise	to surface?		(es)	No	N/A
Construction Type:					Did material	settle after 2	4 hours?		Yes	No	N/A
Drilled Driv	en (Sandpoint	:)	Du	g	If yes, was h	ole retopped	?		Yes	No	(N/A)
Other (specify):					If bentoni	te chips were	used, were they n safe source?	hydrated	Von	No	_
									Yes	No	_(A)
Formation Type:	_					or Pipe-Gravi	ing Sealing Mate	itor Pipe-Pumr	d		
Unconsolidated Formation		Bedroo				d & Poured		stor Pip e- Pum. Explain):	Jeu		
Total Well Depth From Groun	nd Surface (ft) Casing D	iamet	er (in.)		ite Chips)	Other (Explain).			_
NA		NA			Sealing Mat	The second secon					_
Lower Drillhole Diameter (in.)		Casing D	epth (ft.)	Neat Cement			Clay-San	d Slurn	, (11 lb./c	ral set)
NA		NA	- (ement (Concr	rete) Grout	Bentonite	-	, -	
	10	.,			Concret	•	ete/ Grout	Bentonite			
Was well annular space groute	ed?	Yes	No	Unknown			d Monitoring Wel				
If yes, to what depth (feet)?	De	epth to Wate	r (feet)		Bentonit	_	_	entonite - Cem		out	
NA	N/	Α				r Bentonite		entonite - Sand			
5 Material Used To Fill V	Mall / Drillby	olo			From (ft.)	To (ft.)	No. Yards, Sa	icks Sealant	M	ix Ratio	or
5. Material Used To Fill Well / Drillhole							or Volume (circle one)	M	lud Weig	ht
	Bentonite (Chips			Surface	5					_
						1					
6. Comments											
Boring ID: 3-1											
7. Supervision of Wor	k							DNR Use	Only		
Name of Person or Firm Doin	g Filling & Se	ealing Lice	nse#	Date of Fi	lling & Sealin	g (mm/dd/yy	yy) Date Receiv		ted By	1	
Ramboll/On-Site Enviro	_			4/16/20							
Street or Route					elephone Nur	nber	Comments	-			

(262)901-3506

Signature of Person Doing Work

Date Signed

04/30/2019

Well Filling and Sealing

Wisconsin Administrative Code (NR81 1, NR 812, and NR 141 requires well owners to permanently fill and seal any unused wells/drillholes/boreholes on their property. As of June 1, 2008 water supply wells can only be filled and sealed by licensed well drillers and pump installers.

- 1. Remove any pump, pump piping, debris or other obstacles that could interfere with the sealing operation.
- 2. Except when bentonite chips are used, the sealing material must be placed with the use of a conductor (tremie) pipe to fill the entire well column to the top with required sealing material. Refer to NR 812 and NR 141 for more details on filling and sealing requirements.

General Instructions: Fill out Well/Drillhole/Borehole Filling & Sealing Form 3300-005 as completely as possible for each well or borehole filled and sealed. Information should be provided for every box on the form where available. Sign each form. Please note that these forms are subject to change. (Personally identifiable information on these forms is not intended to be used for any other purpose.)

Verification Only of Fill and Seal: If you are only verifying that filling and sealing has previously occurred on a well and are NOT performing any filling and sealing work on the well, check the box near the top of the form. Complete Parts 1 and 2 of the form completely and any information you can provide in Parts 3, 4 and 5. You must provide comments in Part 6 as to the method used to verify both the filling and sealing of the well. Complete Rart 7, excluding the date of Filling and Sealing. It will be implied that you did not do the filling and sealing work as stated in Part 7.

Route to: Check the appropriate routing box on the top of the form to assure proper routing to the DNR program requiring this well be filled and sealed. Mail the form and any attachments to the Department of Natural Resources, PO Box 7921, Madison, WI 53707-7921.

If you do any work to fill or seal the well, you must complete this form as intended and do not check the Verification Only of Fill and Seal box.

(1) WELL LOCATION INFORMATION

WI Unique Well #: Fill in the 2 alphabetic and 3 numeric Wisconsin Unique Well Number (WUWN) of the well being filled and sealed. Check the well, sample tap in the house or the fuse box for a WUWN if one has been assigned to the well.

Hicap #: If this was a high capacity well, enter the number assigned to the well by the Department.

Well Location: The well location can be determined by latitude and longitude coordinates in degrees and decimal minutes (to the thousandths, for example, latitude 43°04.347'N longitude 89°24.803'W) using a Global Positioning System (GPS) unit. If using GPS, check the method code for the GPS unit. The location can also be determined using Public Land Survey (Gov't Lot or 1/4 /1/4, 1/4, Section, Township and Range).

Method Code: This field lists data collection method codes for latitude and longitude coordinates. This field must be entered if a latitude/longitude coordinate is entered.

GPS006 - Mapping or recreational grade GPS receiver with no differential correction and selective availability off

GPS007 - Mapping or recreational grade GPS receiver with no differential correction and selective availability on

GPS008 - GPS receiver grade and or differential correction procedures unknown

(2) FACILITY / OWNER INFORMATION

If the well is located at a commercial or government facility, fill in the name of landfill, wastewater treatment facility, surface impoundment, spill or project.

Facility ID: Fill in the nine digits Facility ID (FID or PWS) assigned to the site by the Department.

License/Permit/Monitoring #: Fill in number assigned to facility by the Department. If unknown, leave blank.

Present Well Owner: Fill in the name, address, city, state and ZIP code of the present owner.

(3) WELL/DRILLHOLE/BOREHOLE INFORMATION

Original Construction Date: Fill in the original date of construction for the well or boring in mm/dd/yyyy format.

Depth to Water: Enter depth to water from ground surface.

- (4) PUMP, LINER, SCREEN, CASING, & SEALING MATERIAL: Check only one box where Yes, No or Not Applicable is indicated. Check all boxes which apply otherwise.
- (5) MATERIAL USED TO FILL THE WELL/DRILLHOLE: Enter the description of the filling material, the depth From and To, circle one measurement unit (Yards, Sacks or Volume), and enter the mix ratio or mud weight (in pounds per gallon).
- (6) COMMENTS: Describe any of the above boxes in more detail or add information as required to describe the filling and sealing procedures.
- (7) **NAME OF PERSON OR FIRM DOING SEALING WORK**: Enter the name (first and last) or firm name, address, and phone number of the person who supervised the work.

State of Wis., Dept. of Natural Resources dnr.wi.gov

Brookfield

WI

53045

Well / Drillhole / Borehole Filling & Sealing Form 3300-005 (R 4/08) Page 1 of 2

Notice: Completion of this report is required bychs. 160, 281, 283, 289, 291-293, 295, and 299, Wis. Stats, and ch. NR 141, Wis. Adm. Code. In accordance with chs. 281, 289, 291-293, 295, and 299, Wis. Stats, failure to file this form may result in a forfeiture of between \$10-25,000, or imprisonment for up to one

with chs. 281, 289, 291-293, 295, and 299, Wis. Stats., failure to file this form may result in a forfeiture of between \$10-25,000, or imprisonment for up to o	пе
year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. Retu	ırn
form to the appropriate DNP office and hursay. See instructions on reverse for more information	

form to the appropriate DNR				on reverse for			ot intended to be used	i for any o	mer pu	urpose r	Return
Verification Only of	Fill and Sea	al	Drin	king Water ste Managemer		Watershed/W		Remedia	ation/Re	edevelop	ment
1. Well Location Informa	tion				T-	y/ Owner In					
County	/I Unique Well #	# of	Hicap#		Facility Nam						
Dane	emoved Well				Hartmeye	r Property					
Lattitude / Longitude (Degree	os and Minutes	N Mothod	Codo (ao	e instructions		ID or PWS)					
		s) wethod	Code (se	e instructions,	V						
					License/Per	mit/Monitorin	ig#				
1/4/1/4 1/4	Section	Tow	nship R	lange E	Original We	ell Owner					
or Gov't Lot #			N	W							
Well Street Address					Present We	II Owner					
2007 Roth Street											
Well City, Village or Town			Well ZIF	2 Code	Mailing Add	ress of Prese	ent Owner				
Madison			53704								_
Subdivision Name			Lot#		City of Pres	ent Owner		State	ZIP Co	ode	
Cabarrision Hamic			Loca								
Reason For Removal From S	Service IV/III	nique Well	# of Reola	cement Well	4. Pump, L	iner, Scree	en, Casing & Seali	ng Mater	rial		
Borehole Only	Service Wirdi	iique vveii	" Of Inspiral	Cerrient Wen	Pump and pi	iping removed	12		Yes	No	N/A
3. Well / Drillhole / Boreh	ala Informat				Liner(s) remo	. •	u :				
3. Well / Drillilole / Borel			n Doto (m	on felial hanna A	1				Yes	No	
Monitoring Well	4/16/20		n Date (in	im/dd/yyyy)	Screen remo				Yes	No	NA NA
Water Well	4/16/20	119			Casing left in	place?			Yes	No	
Borehole / Drillhole	If a Well 0	Construction	Report is a	available,	Was casing	cut off below	surface?		Yes	No	(N/A
Construction Type:	please at	ilacii.				material rise t			(es)	No	N/A
						settle after 24			Yes	\bigcirc	N/A
Other (specify):	ven (Sandpoint)		Dug		If bentonit	ole retopped? e chips were from a knowr	vused, were they hydransafe source?	ated	Yes Yes	No No	Q/A
Formation Type:					Required Me	thod of Placi	ng Sealing Material				
Unconsolidated Formation		Bedro	ck		Conduct	or Pipe-Gravit	Conductor P	ipe-Pumpe	ed		
Total Well Depth From Groun				in)	Screene	d & Poured	Other (Explai	n):			
	id Gariage (it.)		Marriotor (,	(Bentoni	ite Chips)					
NA		NA			Sealing Mate	erials					
Lower Drillhole Diameter (in,)	_	epth (ft.)		Neat Cement	Grout	(Clay-Sand	Slurry	(11 lb /g	gal. wt.
NA		NA			Sand-Ce	ement (Concre	ete) Grout	Bentonite-	-Sand	Slurry" "	
Was well annular space groute	ed?	Yes	No	Unknown	Concrete			Bentonite (>	
If yes, to what depth (feet)?	Der	oth to Wate	r (foot)		For Monitori	ng Wells and	Monitoring Well Bore	holes Onl	y:		
			(loot)		Bentonite		Benton	ite - Ceme	nt Gro	ut	
NA	NA				Granular	Bentonite		ite - Sand			
5. Material Used To Fill \					From (ft.)	To (ft.)	No. Yards, Sacks S or Volume (circle		M	ix Ratio ud Weig	or ht
	Bentonite C	hips			Surface	5					
						- 19					
6. Comments		_									
Boring ID: R-%											
7. Supervision of Wor	k						D	NR Use (Only		
Name of Person or Firm Doir	ng Filling & Sea	aling Lice	nse#	Date of Fi	lling & Sealing	g (mm/dd/yyy	y) Date Received	Not	ed By		
Ramboll/On-Site Enviro	nmental			4/16/20	19						
Street or Route				Te	elephone Num	nber	Comments				
175 N Corporate Drive,	Suite 160			(2	262) 901-3	506					
City		State	ZIP Cod	de	Signature of	Person Doing	g Work	Date	e Sign	ed	

Gage Kapugi

04/30/2019

Well Filling and Sealing

Wisconsin Administrative Code (NR81 1, NR 812, and NR 141 requires well owners to permanently fill and seal any unused wells/drillholes/boreholes on their property. As of June 1, 2008 water supply wells can only be filled and sealed by licensed well drillers and pump installers.

- 1. Remove any pump, pump piping, debris or other obstacles that could interfere with the sealing operation.
- 2. Except when bentonite chips are used, the sealing material must be placed with the use of a conductor (tremie) pipe to fill the entire well column to the top with required sealing material. Refer to NR 812 and NR 141 for more details on filling and sealing requirements.

General Instructions: Fill out Well/Drillhole/Borehole Filling & Sealing Form 3300-005 as completely as possible for each well or borehole filled and sealed. Information should be provided for every box on the form where available. Sign each form. Please note that these forms are subject to change. (Personally identifiable information on these forms is not intended to be used for any other purpose.)

Verification Only of Fill and Seal: If you are only verifying that filling and sealing has previously occurred on a well and are NOT performing any filling and sealing work on the well, check the box near the top of the form. Complete Parts 1 and 2 of the form completely and any information you can provide in Parts 3, 4 and 5. You must provide comments in Part 6 as to the method used to verify both the filling and sealing of the well. Complete Rart 7, excluding the date of Filling and Sealing. It will be implied that you did not do the filling and sealing work as stated in Part 7.

Route to: Check the appropriate routing box on the top of the form to assure proper routing to the DNR program requiring this well be filled and sealed. Mail the form and any attachments to the Department of Natural Resources, PO Box 7921, Madison, WI 53707-7921.

If you do any work to fill or seal the well, you must complete this form as intended and do not check the Verification Only of Fill and Seal box.

(1) WELL LOCATION INFORMATION

WI Unique Well #: Fill in the 2 alphabetic and 3 numeric Wisconsin Unique Well Number (WUWN) of the well being filled and sealed. Check the well, sample tap in the house or the fuse box for a WUWN if one has been assigned to the well.

Hicap #: If this was a high capacity well, enter the number assigned to the well by the Department.

Well Location: The well location can be determined by latitude and longitude coordinates in degrees and decimal minutes (to the thousandths, for example, latitude 43°04.347'N longitude 89°24.803'W) using a Global Positioning System (GPS) unit. If using GPS, check the method code for the GPS unit. The location can also be determined using Public Land Survey (Gov't Lot or 1/4 /1/4, 1/4, Section, Township and Range).

Method Code: This field lists data collection method codes for latitude and longitude coordinates. This field must be entered if a latitude/longitude coordinate is entered.

GPS006 - Mapping or recreational grade GPS receiver with no differential correction and selective availability off

GPS007 - Mapping or recreational grade GPS receiver with no differential correction and selective availability on

GPS008 - GPS receiver grade and or differential correction procedures unknown

(2) FACILITY / OWNER INFORMATION

If the well is located at a commercial or government facility, fill in the name of landfill, wastewater treatment facility, surface impoundment, spill or project.

Facility ID: Fill in the nine digits Facility ID (FID or PWS) assigned to the site by the Department.

License/Permit/Monitoring #: Fill in number assigned to facility by the Department. If unknown, leave blank.

Present Well Owner: Fill in the name, address, city, state and ZIP code of the present owner.

(3) WELL/DRILLHOLE/BOREHOLE INFORMATION

Original Construction Date: Fill in the original date of construction for the well or boring in mm/dd/yyyy format.

Depth to Water: Enter depth to water from ground surface.

- (4) PUMP, LINER, SCREEN, CASING, & SEALING MATERIAL: Check only one box where Yes, No or Not Applicable is indicated. Check all boxes which apply otherwise.
- (5) MATERIAL USED TO FILL THE WELL/DRILLHOLE: Enter the description of the filling material, the depth From and To, circle one measurement unit (Yards, Sacks or Volume), and enter the mix ratio or mud weight (in pounds per gallon).
- (6) COMMENTS: Describe any of the above boxes in more detail or add information as required to describe the filling and sealing procedures.
- (7) **NAME OF PERSON OR FIRM DOING SEALING WORK**: Enter the name (first and last) or firm name, address, and phone number of the person who supervised the work.



ATTACHMENT B LABORATORY ANALYTICAL DATA





May 01, 2019

Adam Streiffer Ramboll Environ 175 North Corporate Drive Suite 160 Brookfield, WI 53045

RE: Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Dear Adam Streiffer:

Enclosed are the analytical results for sample(s) received by the laboratory on April 17, 2019. The results relate only to the samples included in this report. Results reported herein conform to the most current, applicable TNI/NELAC standards and the laboratory's Quality Assurance Manual, where applicable, unless otherwise noted in the body of the report.

If you have any questions concerning this report, please feel free to contact me.


Sincerely,

AVM

Steven Mleczko steve.mleczko@pacelabs.com (920)469-2436 Project Manager

Enclosures







CERTIFICATIONS

Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Green Bay Certification IDs

1241 Bellevue Street, Green Bay, WI 54302 Florida/NELAP Certification #: E87948 Illinois Certification #: 200050 Kentucky UST Certification #: 82 Louisiana Certification #: 04168 Minnesota Certification #: 055-999-334 New York Certification #: 12064

North Dakota Certification #: R-150

Virginia VELAP ID: 460263

South Carolina Certification #: 83006001 Texas Certification #: T104704529-14-1 Wisconsin Certification #: 405132750 Wisconsin DATCP Certification #: 105-444 USDA Soil Permit #: P330-16-00157

Federal Fish & Wildlife Permit #: LE51774A-0



SAMPLE SUMMARY

Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Lab ID	Sample ID	Matrix	Date Collected	Date Received
40185945001	B-1 (1-2')	Solid	04/16/19 08:35	04/17/19 09:30
40185945002	B-1 (4-5')	Solid	04/16/19 08:35	04/17/19 09:30
40185945003	B-2 (1-2')	Solid	04/16/19 08:15	04/17/19 09:30
40185945004	B-2 (4-5')	Solid	04/16/19 08:15	04/17/19 09:30
40185945005	B-3 (1-2')	Solid	04/16/19 08:55	04/17/19 09:30
40185945006	B-3 (4-5')	Solid	04/16/19 08:55	04/17/19 09:30
40185945007	B-4 (1-2')	Solid	04/16/19 09:10	04/17/19 09:30
40185945008	B-4 (4-5')	Solid	04/16/19 09:10	04/17/19 09:30
40185945009	B-5 (1-2.5')	Solid	04/16/19 09:25	04/17/19 09:30
40185945010	B-5 (4-5')	Solid	04/16/19 09:25	04/17/19 09:30
40185945011	B-6 (1-2')	Solid	04/16/19 10:00	04/17/19 09:30
40185945012	B-7 (1-2.5')	Solid	04/16/19 10:20	04/17/19 09:30
40185945013	B-8 (1-2.5')	Solid	04/16/19 09:40	04/17/19 09:30
40185945014	TRIP BLANK	Solid	04/16/19 00:00	04/17/19 09:30



SAMPLE ANALYTE COUNT

Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Lab ID	Sample ID	Method	Analysts	Analytes Reported
40185945001	B-1 (1-2')	EPA 8270 by SIM	ARO	20
		EPA 8260	MDS	13
		ASTM D2974-87	SKW	1
40185945002	B-1 (4-5')	EPA 8270 by SIM	ARO	20
		EPA 8260	MDS	13
		ASTM D2974-87	PCG	1
40185945003	B-2 (1-2')	EPA 8270 by SIM	ARO	20
		EPA 8260	MDS	13
		ASTM D2974-87	SKW	1
40185945004	B-2 (4-5')	EPA 8270 by SIM	ARO	20
		EPA 8260	MDS	13
		ASTM D2974-87	PCG	1
40185945005	B-3 (1-2')	EPA 8270 by SIM	ARO	20
		EPA 8260	MDS	13
		ASTM D2974-87	SKW	1
40185945006	B-3 (4-5')	EPA 8270 by SIM	ARO	20
		EPA 8260	MDS	13
		ASTM D2974-87	PCG	1
40185945007	B-4 (1-2')	EPA 8270 by SIM	ARO	20
		EPA 8260	MDS	13
		ASTM D2974-87	SKW	1
40185945008	B-4 (4-5')	EPA 8270 by SIM	ARO	20
		EPA 8260	MDS	13
		ASTM D2974-87	PCG	1
40185945009	B-5 (1-2.5')	EPA 6010	TXW	7
		EPA 7471	AJT	1
		EPA 8270 by SIM	ARO	20
		EPA 8260	MDS	13
		ASTM D2974-87	SKW	1
40185945010	B-5 (4-5')	EPA 6010	TXW	7
		EPA 7471	AJT	1
		EPA 8270 by SIM	ARO	20
		EPA 8260	MDS	13
		ASTM D2974-87	SKW	1
40185945011	B-6 (1-2')	EPA 6010	TXW	7
		EPA 7471	AJT	1
		EPA 8270 by SIM	ARO	20

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full, without the written consent of Pace Analytical Services, LLC.



SAMPLE ANALYTE COUNT

Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Lab ID	Sample ID	Method	Analysts	Analytes Reported
		EPA 8260	MDS	13
		ASTM D2974-87	SKW	1
40185945012	B-7 (1-2.5')	EPA 6010	TXW	7
		EPA 7471	AJT	1
		EPA 8270 by SIM	ARO	20
		EPA 8260	MDS	13
		ASTM D2974-87	SKW	1
40185945013	B-8 (1-2.5')	EPA 6010	TXW	7
		EPA 7471	AJT	1
		EPA 8270 by SIM	ARO	20
		EPA 8260	MDS	13
		ASTM D2974-87	SKW	1
40185945014	TRIP BLANK	EPA 8260	MDS	13



Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

Sample: B-1 (1-2') Lab ID: 40185945001 Collected: 04/16/19 08:35 Received: 04/17/19 09:30 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
8270 MSSV PAH by SIM	Analytical	Method: EPA	A 8270 by SIM	Preparatio	n Meth	nod: EPA 3546			
Acenaphthene	48.4	ug/kg	32.4	9.8	2	04/22/19 08:19	04/22/19 17:53	83-32-9	
Acenaphthylene	31.0	ug/kg	27.7	8.3	2	04/22/19 08:19	04/22/19 17:53	208-96-8	
Anthracene	119	ug/kg	47.8	14.4	2	04/22/19 08:19	04/22/19 17:53	120-12-7	
Benzo(a)anthracene	139	ug/kg	26.7	8.0	2	04/22/19 08:19	04/22/19 17:53	56-55-3	
Benzo(a)pyrene	106	ug/kg	21.0	6.3	2	04/22/19 08:19	04/22/19 17:53	50-32-8	
Benzo(b)fluoranthene	81.1	ug/kg	23.7	7.1	2	04/22/19 08:19	04/22/19 17:53	205-99-2	
Benzo(g,h,i)perylene	65.3	ug/kg	17.0	5.1	2	04/22/19 08:19	04/22/19 17:53	191-24-2	
Benzo(k)fluoranthene	91.0	ug/kg	21.0	6.3	2	04/22/19 08:19	04/22/19 17:53	207-08-9	
Chrysene	160	ug/kg	28.2	8.5	2	04/22/19 08:19	04/22/19 17:53	218-01-9	
Dibenz(a,h)anthracene	23.2	ug/kg	18.7	5.6	2	04/22/19 08:19	04/22/19 17:53		
Fluoranthene	272	ug/kg	43.8	13.1	2	04/22/19 08:19	04/22/19 17:53		
Fluorene	52.5	ug/kg	34.7	10.4	2	04/22/19 08:19	04/22/19 17:53		
Indeno(1,2,3-cd)pyrene	46.5	ug/kg	18.4	5.5	2	04/22/19 08:19			
1-Methylnaphthalene	759	ug/kg	33.7	10.1	2	04/22/19 08:19	04/22/19 17:53		
2-Methylnaphthalene	863	ug/kg ug/kg	42.0	12.6	2	04/22/19 08:19	04/22/19 17:53		
Naphthalene	410	ug/kg ug/kg	70.7	21.2	2	04/22/19 08:19	04/22/19 17:53		
Phenanthrene	755	ug/kg ug/kg	97.6	29.3	2	04/22/19 08:19	04/22/19 17:53		
Pyrene	243	ug/kg ug/kg	37.7	11.3	2	04/22/19 08:19	04/22/19 17:53		
Surrogates	2-13	ug/kg	57.7	11.5	_	04/22/10 00.10	04/22/13 17.55	123 00 0	
2-Fluorobiphenyl (S)	56	%	28-99		2	04/22/19 08:19	04/22/19 17:53	321-60-8	
Terphenyl-d14 (S)	43	%	10-107		2	04/22/19 08:19	04/22/19 17:53		
8260 MSV Med Level Normal List	Apolytical	Mothod: ED/	A 8260 Prepara	ation Moth					
	-					ч 3033/3030В			
1,2,4-Trimethylbenzene	44.6J	ug/kg	75.5	31.5	1	04/18/19 08:15	04/18/19 11:54		
1,3,5-Trimethylbenzene	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 11:54	108-67-8	W
Benzene	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 11:54	71-43-2	W
Ethylbenzene	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 11:54	100-41-4	W
Methyl-tert-butyl ether	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 11:54	1634-04-4	W
Naphthalene	<40.0	ug/kg	250	40.0	1	04/18/19 08:15	04/18/19 11:54	91-20-3	W
Toluene	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 11:54	108-88-3	W
Xylene (Total)	<75.0	ug/kg	180	75.0	1	04/18/19 08:15	04/18/19 11:54	1330-20-7	W
m&p-Xylene	<50.0	ug/kg	120	50.0	1	04/18/19 08:15	04/18/19 11:54	179601-23-1	W
o-Xylene	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 11:54	95-47-6	W
Surrogates									
Dibromofluoromethane (S)	94	%	57-146		1	04/18/19 08:15	04/18/19 11:54	1868-53-7	
Toluene-d8 (S)	90	%	64-134		1	04/18/19 08:15	04/18/19 11:54	2037-26-5	
4-Bromofluorobenzene (S)	93	%	54-126		1	04/18/19 08:15	04/18/19 11:54	460-00-4	
Percent Moisture	Analytical	Method: AS	ΓM D2974-87						
Percent Moisture	20.6	%	0.10	0.10	1		04/23/19 09:19		



Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

Sample: B-1 (4-5') Lab ID: 40185945002 Collected: 04/16/19 08:35 Received: 04/17/19 09:30 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
8270 MSSV PAH by SIM	Analytical	Method: EP	A 8270 by SIM	Preparation	n Meth	nod: EPA 3546			
Acenaphthene	<131	ug/kg	435	131	20	04/23/19 08:41	04/23/19 12:11	83-32-9	
Acenaphthylene	313J	ug/kg	371	111	20	04/23/19 08:41	04/23/19 12:11	208-96-8	
Anthracene	650	ug/kg	641	193	20	04/23/19 08:41	04/23/19 12:11	120-12-7	
Benzo(a)anthracene	3110	ug/kg	358	107	20	04/23/19 08:41	04/23/19 12:11	56-55-3	
Benzo(a)pyrene	3110	ug/kg	283	84.8	20	04/23/19 08:41	04/23/19 12:11	50-32-8	
Benzo(b)fluoranthene	5100	ug/kg	318	95.3	20	04/23/19 08:41	04/23/19 12:11	205-99-2	
Benzo(g,h,i)perylene	2020	ug/kg	229	68.6	20	04/23/19 08:41	04/23/19 12:11	191-24-2	
Benzo(k)fluoranthene	2080	ug/kg	282	84.7	20	04/23/19 08:41	04/23/19 12:11	207-08-9	
Chrysene	4480	ug/kg	378	114	20	04/23/19 08:41	04/23/19 12:11	218-01-9	
Dibenz(a,h)anthracene	430	ug/kg	251	75.5	20	04/23/19 08:41	04/23/19 12:11		
Fluoranthene	9030	ug/kg	587	176	20	04/23/19 08:41	04/23/19 12:11	206-44-0	
Fluorene	<140	ug/kg	466	140	20	04/23/19 08:41	04/23/19 12:11		
Indeno(1,2,3-cd)pyrene	1580	ug/kg	247	74.2	20	04/23/19 08:41	04/23/19 12:11		
1-Methylnaphthalene	<136	ug/kg	452	136	20	04/23/19 08:41	04/23/19 12:11		
2-Methylnaphthalene	<169	ug/kg	564	169	20	04/23/19 08:41	04/23/19 12:11		
Naphthalene	<284	ug/kg	948	284	20	04/23/19 08:41	04/23/19 12:11		
Phenanthrene	2650	ug/kg	1310	393	20	04/23/19 08:41	04/23/19 12:11		
Pyrene	6160	ug/kg	506	152	20	04/23/19 08:41	04/23/19 12:11		
Surrogates	0.00	~g/g	333	.02	_0	0 1/20/ 10 001 11	0 1/20/ 10 12111	.20 00 0	
2-Fluorobiphenyl (S)	44	%	28-99		20	04/23/19 08:41	04/23/19 12:11	321-60-8	
Terphenyl-d14 (S)	39	%	10-107		20	04/23/19 08:41	04/23/19 12:11	1718-51-0	
8260 MSV Med Level Normal List	Analytical	Method: EP	A 8260 Prepara	ation Meth	od: EP	A 5035/5030B			
1,2,4-Trimethylbenzene	<28.4	ug/kg	68.2	28.4	1	04/23/19 08:30	04/24/19 19:39	95-63-6	W
1,3,5-Trimethylbenzene	<28.4	ug/kg	68.2	28.4	1	04/23/19 08:30	04/24/19 19:39	108-67-8	W
Benzene	<28.4	ug/kg	68.2	28.4	1	04/23/19 08:30	04/24/19 19:39	71-43-2	W
Ethylbenzene	<28.4	ug/kg	68.2	28.4	1	04/23/19 08:30	04/24/19 19:39		W
Methyl-tert-butyl ether	<28.4	ug/kg	68.2	28.4	1	04/23/19 08:30	04/24/19 19:39		W
Naphthalene	<45.5	ug/kg	284	45.5	1	04/23/19 08:30	04/24/19 19:39		W
Toluene	51.4J	ug/kg	115	48.0	1	04/23/19 08:30	04/24/19 19:39	108-88-3	
Xylene (Total)	<85.2	ug/kg	205	85.2	1	04/23/19 08:30	04/24/19 19:39	1330-20-7	W
m&p-Xylene	<56.8	ug/kg	136	56.8	1	04/23/19 08:30	04/24/19 19:39		W
o-Xylene	<28.4	ug/kg	68.2	28.4	1	04/23/19 08:30	04/24/19 19:39		W
Surrogates		99			-				•
Dibromofluoromethane (S)	91	%	57-146		1	04/23/19 08:30	04/24/19 19:39	1868-53-7	
Toluene-d8 (S)	84	%	64-134		1	04/23/19 08:30	04/24/19 19:39	2037-26-5	
4-Bromofluorobenzene (S)	90	%	54-126		1	04/23/19 08:30	04/24/19 19:39	460-00-4	
Percent Moisture	Analytical	Method: AS	ГМ D2974-87						
Percent Moisture	40.8	%	0.10	0.10	1		04/24/19 19:37		



Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

Sample: B-2 (1-2') Lab ID: 40185945003 Collected: 04/16/19 08:15 Received: 04/17/19 09:30 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
8270 MSSV PAH by SIM	Analytical	Method: EPA	A 8270 by SIM	Preparation	n Meth	nod: EPA 3546			
Acenaphthene	<5.7	ug/kg	18.8	5.7	1	04/22/19 08:19	04/22/19 21:22	83-32-9	
Acenaphthylene	<4.8	ug/kg	16.1	4.8	1	04/22/19 08:19	04/22/19 21:22	208-96-8	
Anthracene	8.8J	ug/kg	27.7	8.3	1	04/22/19 08:19	04/22/19 21:22	120-12-7	
Benzo(a)anthracene	13.0J	ug/kg	15.5	4.6	1	04/22/19 08:19	04/22/19 21:22	56-55-3	
Benzo(a)pyrene	11.9J	ug/kg	12.2	3.7	1	04/22/19 08:19	04/22/19 21:22	50-32-8	
Benzo(b)fluoranthene	11.2J	ug/kg	13.7	4.1	1	04/22/19 08:19	04/22/19 21:22	205-99-2	
Benzo(g,h,i)perylene	9.3J	ug/kg	9.9	3.0	1	04/22/19 08:19	04/22/19 21:22	191-24-2	
Benzo(k)fluoranthene	10.6J	ug/kg	12.2	3.7	1	04/22/19 08:19	04/22/19 21:22	207-08-9	
Chrysene	14.6J	ug/kg	16.4	4.9	1	04/22/19 08:19	04/22/19 21:22	218-01-9	
Dibenz(a,h)anthracene	<3.3	ug/kg	10.9	3.3	1	04/22/19 08:19	04/22/19 21:22	53-70-3	
Fluoranthene	23.4J	ug/kg	25.4	7.6	1	04/22/19 08:19			
Fluorene	<6.0	ug/kg	20.1	6.0	1	04/22/19 08:19	04/22/19 21:22	86-73-7	
Indeno(1,2,3-cd)pyrene	7.0J	ug/kg	10.7	3.2	1	04/22/19 08:19	04/22/19 21:22	193-39-5	
1-Methylnaphthalene	50.3	ug/kg	19.6	5.9	1	04/22/19 08:19	04/22/19 21:22		
2-Methylnaphthalene	74.0	ug/kg	24.4	7.3	1	04/22/19 08:19	04/22/19 21:22		
Naphthalene	28.5J	ug/kg	41.0	12.3	1	04/22/19 08:19	04/22/19 21:22		
Phenanthrene	50.4J	ug/kg	56.6	17.0	1	04/22/19 08:19	04/22/19 21:22		
Pyrene	21.3J	ug/kg	21.9	6.6	1	04/22/19 08:19	04/22/19 21:22		
Surrogates		0 0							
2-Fluorobiphenyl (S)	52	%	28-99		1	04/22/19 08:19	04/22/19 21:22	321-60-8	
Terphenyl-d14 (S)	48	%	10-107		1	04/22/19 08:19	04/22/19 21:22	1718-51-0	
8260 MSV Med Level Normal List	Analytical	Method: EPA	A 8260 Prepara	ation Metho	od: EP/	A 5035/5030B			
1,2,4-Trimethylbenzene	60.7J	ug/kg	89.3	37.2	1	04/18/19 08:15	04/18/19 13:04	95-63-6	
1,3,5-Trimethylbenzene	<25.5	ug/kg	61.2	25.5	1	04/18/19 08:15	04/18/19 13:04	108-67-8	W
Benzene	<25.5	ug/kg	61.2	25.5	1	04/18/19 08:15	04/18/19 13:04	71-43-2	W
Ethylbenzene	<25.5	ug/kg	61.2	25.5	1	04/18/19 08:15	04/18/19 13:04	100-41-4	W
Methyl-tert-butyl ether	<25.5	ug/kg	61.2	25.5	1	04/18/19 08:15	04/18/19 13:04	1634-04-4	W
Naphthalene	81.5J	ug/kg	372	59.6	1	04/18/19 08:15			
Toluene	<25.5	ug/kg	61.2	25.5	1		04/18/19 13:04		W
Xylene (Total)	<76.5	ug/kg	184	76.5	1	04/18/19 08:15	04/18/19 13:04		W
m&p-Xylene	<51.0	ug/kg	122	51.0	1	04/18/19 08:15	04/18/19 13:04	179601-23-1	W
o-Xylene	<25.5	ug/kg	61.2	25.5	1	04/18/19 08:15			W
Surrogates		3 3							
Dibromofluoromethane (S)	93	%	57-146		1	04/18/19 08:15	04/18/19 13:04	1868-53-7	
Toluene-d8 (S)	90	%	64-134		1	04/18/19 08:15	04/18/19 13:04	2037-26-5	
4-Bromofluorobenzene (S)	99	%	54-126		1	04/18/19 08:15	04/18/19 13:04	460-00-4	
Percent Moisture	Analytical	Method: AS	ΓM D2974-87						
Percent Moisture	31.4	%	0.10	0.10	1		04/23/19 09:19		



Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

Sample: B-2 (4-5') Lab ID: 40185945004 Collected: 04/16/19 08:15 Received: 04/17/19 09:30 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
8270 MSSV PAH by SIM	Analytical	Method: EPA	A 8270 by SIM	Preparation	on Meth	nod: EPA 3546			
Acenaphthene	<34.0	ug/kg	113	34.0	4	04/25/19 08:41	04/25/19 14:41	83-32-9	
Acenaphthylene	<28.8	ug/kg	96.2	28.8	4	04/25/19 08:41	04/25/19 14:41	208-96-8	
Anthracene	67.7J	ug/kg	166	50.0	4	04/25/19 08:41	04/25/19 14:41	120-12-7	
Benzo(a)anthracene	59.6J	ug/kg	92.7	27.7	4	04/25/19 08:41	04/25/19 14:41	56-55-3	
Benzo(a)pyrene	87.1	ug/kg	73.2	22.0	4	04/25/19 08:41	04/25/19 14:41	50-32-8	
Benzo(b)fluoranthene	81.0J	ug/kg	82.3	24.7	4	04/25/19 08:41	04/25/19 14:41	205-99-2	
Benzo(g,h,i)perylene	64.9	ug/kg	59.2	17.8	4	04/25/19 08:41	04/25/19 14:41	191-24-2	
Benzo(k)fluoranthene	83.5	ug/kg	73.1	21.9	4	04/25/19 08:41	04/25/19 14:41	207-08-9	
Chrysene	94.8J	ug/kg	98.0	29.5	4	04/25/19 08:41	04/25/19 14:41	218-01-9	
Dibenz(a,h)anthracene	<19.6	ug/kg	65.2	19.6	4	04/25/19 08:41	04/25/19 14:41		
Fluoranthene	100J	ug/kg	152	45.6	4	04/25/19 08:41	04/25/19 14:41		
Fluorene	<36.2	ug/kg	121	36.2	4	04/25/19 08:41	04/25/19 14:41		
Indeno(1,2,3-cd)pyrene	<19.2	ug/kg	64.1	19.2	4	04/25/19 08:41	04/25/19 14:41		
1-Methylnaphthalene	462	ug/kg	117	35.2	4	04/25/19 08:41	04/25/19 14:41		
2-Methylnaphthalene	1120	ug/kg	146	43.8	4	04/25/19 08:41	04/25/19 14:41		
Naphthalene	4040	ug/kg ug/kg	246	73.7	4	04/25/19 08:41	04/25/19 14:41		
Phenanthrene	175J	ug/kg	339	102	4	04/25/19 08:41	04/25/19 14:41		
Pyrene	84.7J	ug/kg ug/kg	131	39.5	4	04/25/19 08:41	04/25/19 14:41		
Surrogates	04.70	ug/kg	101	55.5	7	04/23/13 00.41	04/25/15 14.41	123 00 0	
2-Fluorobiphenyl (S)	37	%	28-99		4	04/25/19 08:41	04/25/19 14:41	321-60-8	
Terphenyl-d14 (S)	30	%	10-107		4	04/25/19 08:41	04/25/19 14:41	1718-51-0	
8260 MSV Med Level Normal List	Analytical	Method: EPA	A 8260 Prepara	ation Meth	od: EP/	A 5035/5030B			
1,2,4-Trimethylbenzene	30500	ug/kg	328	137	2.5	04/23/19 08:30	04/24/19 03:50	95-63-6	
1,3,5-Trimethylbenzene	7900	ug/kg ug/kg	328	137	2.5	04/23/19 08:30	04/24/19 03:50		
Benzene	<62.5	ug/kg ug/kg	150	62.5	2.5	04/23/19 08:30	04/24/19 03:50		W
Ethylbenzene	7400	ug/kg ug/kg	328	137	2.5	04/23/19 08:30	04/24/19 03:50		VV
Methyl-tert-butyl ether	<62.5	ug/kg ug/kg	150	62.5	2.5	04/23/19 08:30	04/24/19 03:50		W
Naphthalene	3440	ug/kg ug/kg	1370	219	2.5	04/23/19 08:30	04/24/19 03:50		VV
Toluene	<62.5	ug/kg ug/kg	150	62.5	2.5	04/23/19 08:30	04/24/19 03:50		W
	38500		984	410	2.5				VV
Xylene (Total)		ug/kg		_	2.5 2.5	04/23/19 08:30	04/24/19 03:50		
m&p-Xylene	30600	ug/kg	656	273		04/23/19 08:30	04/24/19 03:50		
o-Xylene	7850	ug/kg	328	137	2.5	04/23/19 08:30	04/24/19 03:50	95-47-6	
Surrogates Dibromofluoromethane (S)	95	%	57-146		2.5	04/23/19 08:30	04/24/19 03:50	1868-52 7	
Toluene-d8 (S)	95 84	% %	64-134		2.5	04/23/19 08:30	04/24/19 03:50		
4-Bromofluorobenzene (S)	84 98	% %	54-134 54-126		2.5 2.5	04/23/19 08:30	04/24/19 03:50		
, ,					۷.5	04/23/19 00.30	04/24/19 03.30	700-00 - 4	
Percent Moisture	Analytical	Method: AS	ΓM D2974-87						
Percent Moisture	54.3	%	0.10	0.10	1		04/24/19 19:37		



Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

Sample: B-3 (1-2') Lab ID: 40185945005 Collected: 04/16/19 08:55 Received: 04/17/19 09:30 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
8270 MSSV PAH by SIM	Analytical	Method: EPA	A 8270 by SIM	Preparation	n Meth	nod: EPA 3546			
Acenaphthene	177J	ug/kg	300	90.3	20	04/30/19 09:47	04/30/19 15:39	83-32-9	
Acenaphthylene	<76.7	ug/kg	256	76.7	20	04/30/19 09:47	04/30/19 15:39	208-96-8	
Anthracene	478	ug/kg	442	133	20	04/30/19 09:47	04/30/19 15:39	120-12-7	
Benzo(a)anthracene	1330	ug/kg	247	73.8	20	04/30/19 09:47	04/30/19 15:39	56-55-3	
Benzo(a)pyrene	1430	ug/kg	195	58.5	20	04/30/19 09:47	04/30/19 15:39	50-32-8	
Benzo(b)fluoranthene	1310	ug/kg	219	65.7	20	04/30/19 09:47	04/30/19 15:39	205-99-2	
Benzo(g,h,i)perylene	1110	ug/kg	158	47.3	20	04/30/19 09:47	04/30/19 15:39	191-24-2	
Benzo(k)fluoranthene	1270	ug/kg	195	58.4	20	04/30/19 09:47	04/30/19 15:39	207-08-9	
Chrysene	1470	ug/kg	261	78.5	20	04/30/19 09:47	04/30/19 15:39	218-01-9	
Dibenz(a,h)anthracene	348	ug/kg	173	52.0	20	04/30/19 09:47	04/30/19 15:39	53-70-3	
Fluoranthene	3340	ug/kg	405	121	20	04/30/19 09:47	04/30/19 15:39		
Fluorene	159J	ug/kg	321	96.3	20	04/30/19 09:47			
Indeno(1,2,3-cd)pyrene	942	ug/kg	171	51.2	20	04/30/19 09:47			
1-Methylnaphthalene	<93.6	ug/kg	312	93.6	20	04/30/19 09:47			
2-Methylnaphthalene	<116	ug/kg	389	116	20	04/30/19 09:47	04/30/19 15:39		
Naphthalene	<196	ug/kg	654	196	20	04/30/19 09:47	04/30/19 15:39		
Phenanthrene	2060	ug/kg	903	271	20	04/30/19 09:47	04/30/19 15:39		
Pyrene	2570	ug/kg	349	105	20	04/30/19 09:47			
Surrogates	20.0	ug/itg	0.10	100		0 1/00/10 00:11	0 1/00/10 10:00	120 00 0	
2-Fluorobiphenyl (S)	48	%	28-99		20	04/30/19 09:47	04/30/19 15:39	321-60-8	
Terphenyl-d14 (S)	46	%	10-107		20	04/30/19 09:47	04/30/19 15:39	1718-51-0	
8260 MSV Med Level Normal List	Analytical	Method: EPA	A 8260 Prepar	ation Meth	od: EP	A 5035/5030B			
1,2,4-Trimethylbenzene	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 13:27	95-63-6	W
1,3,5-Trimethylbenzene	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 13:27	108-67-8	W
Benzene	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 13:27	71-43-2	W
Ethylbenzene	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 13:27	100-41-4	W
Methyl-tert-butyl ether	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 13:27	1634-04-4	W
Naphthalene	<40.0	ug/kg	250	40.0	1	04/18/19 08:15	04/18/19 13:27		W
Toluene	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 13:27	108-88-3	W
Xylene (Total)	<75.0	ug/kg	180	75.0	1	04/18/19 08:15	04/18/19 13:27	1330-20-7	W
m&p-Xylene	<50.0	ug/kg	120	50.0	1	04/18/19 08:15	04/18/19 13:27		
o-Xylene	<25.0	ug/kg	60.0	25.0	1		04/18/19 13:27		W
Surrogates		-9.1.9			•				
Dibromofluoromethane (S)	94	%	57-146		1	04/18/19 08:15	04/18/19 13:27	1868-53-7	
Toluene-d8 (S)	95	%	64-134		1	04/18/19 08:15	04/18/19 13:27	2037-26-5	
4-Bromofluorobenzene (S)	109	%	54-126		1	04/18/19 08:15	04/18/19 13:27	460-00-4	
Percent Moisture	Analytical	Method: AS	ΓM D2974-87						
Percent Moisture	14.2	%	0.10	0.10	1		04/23/19 09:19		



Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

Sample: B-3 (4-5') Lab ID: 40185945006 Collected: 04/16/19 08:55 Received: 04/17/19 09:30 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
8270 MSSV PAH by SIM	Analytical	Method: EPA	A 8270 by SIM	Preparation	n Meth	nod: EPA 3546			
Acenaphthene	4950	ug/kg	338	102	20	04/23/19 08:41	04/23/19 12:46	83-32-9	
Acenaphthylene	2420	ug/kg	288	86.3	20	04/23/19 08:41	04/23/19 12:46	208-96-8	
Anthracene	6820	ug/kg	497	149	20	04/23/19 08:41	04/23/19 12:46	120-12-7	
Benzo(a)anthracene	5610	ug/kg	277	83.0	20	04/23/19 08:41	04/23/19 12:46	56-55-3	
Benzo(a)pyrene	4280	ug/kg	219	65.8	20	04/23/19 08:41	04/23/19 12:46	50-32-8	
Benzo(b)fluoranthene	3650	ug/kg	246	73.9	20	04/23/19 08:41	04/23/19 12:46	205-99-2	
Benzo(g,h,i)perylene	1870	ug/kg	177	53.2	20	04/23/19 08:41	04/23/19 12:46	191-24-2	
Benzo(k)fluoranthene	1400	ug/kg	219	65.7	20	04/23/19 08:41	04/23/19 12:46	207-08-9	
Chrysene	5360	ug/kg	293	88.3	20	04/23/19 08:41	04/23/19 12:46	218-01-9	
Dibenz(a,h)anthracene	487	ug/kg	195	58.5	20	04/23/19 08:41	04/23/19 12:46		
Fluoranthene	11300	ug/kg	455	136	20	04/23/19 08:41	04/23/19 12:46	206-44-0	
Fluorene	2680	ug/kg	361	108	20	04/23/19 08:41	04/23/19 12:46		
Indeno(1,2,3-cd)pyrene	1370	ug/kg	192	57.6	20	04/23/19 08:41	04/23/19 12:46		
1-Methylnaphthalene	2260	ug/kg	351	105	20	04/23/19 08:41	04/23/19 12:46		
2-Methylnaphthalene	594	ug/kg	437	131	20	04/23/19 08:41	04/23/19 12:46		
Naphthalene	2290	ug/kg	736	220	20	04/23/19 08:41	04/23/19 12:46		
Phenanthrene	21400	ug/kg	1020	305	20	04/23/19 08:41	04/23/19 12:46		
Pyrene	15200	ug/kg	393	118	20	04/23/19 08:41	04/23/19 12:46		
Surrogates	10200	agritg	000	110	20	04/20/10 00.41	04/20/10 12:40	120 00 0	
2-Fluorobiphenyl (S)	48	%	28-99		20	04/23/19 08:41	04/23/19 12:46	321-60-8	
Terphenyl-d14 (S)	41	%	10-107		20	04/23/19 08:41	04/23/19 12:46	1718-51-0	
8260 MSV Med Level Normal List	Analytical	Method: EPA	A 8260 Prepara	ation Meth	od: EP	A 5035/5030B			
1,2,4-Trimethylbenzene	59.3J	ug/kg	78.4	32.7	1	04/23/19 08:30	04/24/19 15:14	95-63-6	
1,3,5-Trimethylbenzene	<25.0	ug/kg	60.0	25.0	1	04/23/19 08:30	04/24/19 15:14		W
Benzene	71.8J	ug/kg	78.4	32.7	1	04/23/19 08:30	04/24/19 15:14		••
Ethylbenzene	129	ug/kg	78.4	32.7	1	04/23/19 08:30	04/24/19 15:14		
Methyl-tert-butyl ether	<25.0	ug/kg	60.0	25.0	1	04/23/19 08:30	04/24/19 15:14		W
Naphthalene	416	ug/kg	327	52.3	1	04/23/19 08:30			••
Toluene	49.2J	ug/kg	78.4	32.7	1	04/23/19 08:30	04/24/19 15:14		
Xylene (Total)	<75.0	ug/kg	180	75.0	1	04/23/19 08:30	04/24/19 15:14		W
m&p-Xylene	<50.0	ug/kg	120	50.0	1	04/23/19 08:30	04/24/19 15:14		
o-Xylene	<25.0	ug/kg ug/kg	60.0	25.0	1	04/23/19 08:30	04/24/19 15:14		W
Surrogates	\Z5.0	ug/kg	00.0	20.0	'	0-//20/10 00.00	0-1/2 -1 /10 10.14	00 47 0	* *
Dibromofluoromethane (S)	100	%	57-146		1	04/23/19 08:30	04/24/19 15:14	1868-53-7	
Toluene-d8 (S)	99	%	64-134		1	04/23/19 08:30	04/24/19 15:14		
4-Bromofluorobenzene (S)	114	%	54-126		1	04/23/19 08:30	04/24/19 15:14		
Percent Moisture	Analytical	Method: AS	ΓM D2974-87						
Percent Moisture	23.5	%	0.10	0.10	1		04/24/19 19:37		



Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

Sample: B-4 (1-2') Lab ID: 40185945007 Collected: 04/16/19 09:10 Received: 04/17/19 09:30 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
8270 MSSV PAH by SIM	Analytical	Method: EPA	8270 by SIM	Preparatio	n Meth	nod: EPA 3546			
Acenaphthene	23.2	ug/kg	16.3	4.9	1	04/22/19 08:19	04/22/19 18:11	83-32-9	
Acenaphthylene	10.1J	ug/kg	13.9	4.2	1	04/22/19 08:19	04/22/19 18:11	208-96-8	
Anthracene	43.9	ug/kg	24.1	7.2	1	04/22/19 08:19	04/22/19 18:11	120-12-7	
Benzo(a)anthracene	52.3	ug/kg	13.4	4.0	1	04/22/19 08:19	04/22/19 18:11	56-55-3	
Benzo(a)pyrene	37.8	ug/kg	10.6	3.2	1	04/22/19 08:19	04/22/19 18:11	50-32-8	
Benzo(b)fluoranthene	23.6	ug/kg	11.9	3.6	1	04/22/19 08:19	04/22/19 18:11	205-99-2	
Benzo(g,h,i)perylene	24.4	ug/kg	8.6	2.6	1	04/22/19 08:19	04/22/19 18:11	191-24-2	
Benzo(k)fluoranthene	29.1	ug/kg	10.6	3.2	1	04/22/19 08:19	04/22/19 18:11	207-08-9	
Chrysene	59.2	ug/kg	14.2	4.3	1	04/22/19 08:19	04/22/19 18:11	218-01-9	
Dibenz(a,h)anthracene	7.9J	ug/kg	9.4	2.8	1	04/22/19 08:19	04/22/19 18:11	53-70-3	
Fluoranthene	69.7	ug/kg	22.1	6.6	1	04/22/19 08:19	04/22/19 18:11	206-44-0	
Fluorene	24.5	ug/kg	17.5	5.2	1	04/22/19 08:19	04/22/19 18:11		
Indeno(1,2,3-cd)pyrene	13.1	ug/kg	9.3	2.8	1	04/22/19 08:19	04/22/19 18:11		
1-Methylnaphthalene	214	ug/kg	17.0	5.1	1	04/22/19 08:19	04/22/19 18:11		
2-Methylnaphthalene	206	ug/kg	21.2	6.3	1	04/22/19 08:19	04/22/19 18:11		
Naphthalene	90.2	ug/kg	35.6	10.7	1	04/22/19 08:19	04/22/19 18:11		
Phenanthrene	291	ug/kg	49.2	14.8	1	04/22/19 08:19	04/22/19 18:11		
Pyrene	72.1	ug/kg	19.0	5.7	1	04/22/19 08:19	04/22/19 18:11		
Surrogates		ug/kg	10.0	0.1	'	04/22/10 00:10	0-1/22/10 10:11	120 00 0	
2-Fluorobiphenyl (S)	60	%	28-99		1	04/22/19 08:19	04/22/19 18:11	321-60-8	
Terphenyl-d14 (S)	50	%	10-107		1	04/22/19 08:19	04/22/19 18:11	1718-51-0	
8260 MSV Med Level Normal List	Analytical	Method: EPA	A 8260 Prepar	ation Metho	od: EP/	A 5035/5030B			
1,2,4-Trimethylbenzene	35.7J	ug/kg	76.1	31.7	1		04/18/19 15:45	05.62.6	
1,3,5-Trimethylbenzene	<25.0	ug/kg ug/kg	60.0	25.0	1	04/18/19 08:15 04/18/19 08:15	04/18/19 15:45		W
Benzene	<25.0 <25.0	0 0	60.0	25.0 25.0	1	04/18/19 08:15	04/18/19 15:45		W
		ug/kg							
Ethylbenzene	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 15:45		W
Methyl-tert-butyl ether	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 15:45		W
Naphthalene	<40.0	ug/kg	250	40.0	1	04/18/19 08:15			W
Toluene	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 15:45		W
Xylene (Total)	<75.0	ug/kg	180	75.0	1	04/18/19 08:15	04/18/19 15:45		W
m&p-Xylene	<50.0	ug/kg	120	50.0	1	04/18/19 08:15	04/18/19 15:45		VV
o-Xylene	34.9J	ug/kg	76.1	31.7	1	04/18/19 08:15	04/18/19 15:45	95-47-6	
Surrogates	00	0/	F7 440			0.4/4.0/4.0.00.4.5	04/40/40 45 45	4000 50 7	
Dibromofluoromethane (S)	93	%	57-146		1	04/18/19 08:15	04/18/19 15:45		
Toluene-d8 (S)	89	%	64-134		1	04/18/19 08:15	04/18/19 15:45		
4-Bromofluorobenzene (S)	94	%	54-126		1	04/18/19 08:15	04/18/19 15:45	400-00-4	
Percent Moisture	Analytical	Method: AS7	ΓM D2974-87						
Percent Moisture	21.1	%	0.10	0.10	1		04/23/19 09:19		



Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

Sample: B-4 (4-5') Lab ID: 40185945008 Collected: 04/16/19 09:10 Received: 04/17/19 09:30 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
8270 MSSV PAH by SIM	Analytical	Method: EPA	A 8270 by SIM	Preparatio	n Meth	nod: EPA 3546			
Acenaphthene	40.9	ug/kg	21.9	6.6	1	04/23/19 08:41	04/23/19 19:09	83-32-9	
Acenaphthylene	8.9J	ug/kg	18.7	5.6	1	04/23/19 08:41	04/23/19 19:09	208-96-8	
Anthracene	90.3	ug/kg	32.3	9.7	1	04/23/19 08:41	04/23/19 19:09	120-12-7	
Benzo(a)anthracene	242	ug/kg	18.0	5.4	1	04/23/19 08:41	04/23/19 19:09	56-55-3	
Benzo(a)pyrene	244	ug/kg	14.2	4.3	1	04/23/19 08:41	04/23/19 19:09	50-32-8	
Benzo(b)fluoranthene	333	ug/kg	16.0	4.8	1	04/23/19 08:41	04/23/19 19:09	205-99-2	
Benzo(g,h,i)perylene	166	ug/kg	11.5	3.5	1	04/23/19 08:41	04/23/19 19:09	191-24-2	
Benzo(k)fluoranthene	140	ug/kg	14.2	4.3	1	04/23/19 08:41	04/23/19 19:09	207-08-9	
Chrysene	260	ug/kg	19.0	5.7	1	04/23/19 08:41	04/23/19 19:09	218-01-9	
Dibenz(a,h)anthracene	45.2	ug/kg	12.7	3.8	1	04/23/19 08:41	04/23/19 19:09	53-70-3	
Fluoranthene	644	ug/kg	29.6	8.9	1	04/23/19 08:41	04/23/19 19:09		
Fluorene	39.2	ug/kg	23.5	7.0	1	04/23/19 08:41	04/23/19 19:09		
Indeno(1,2,3-cd)pyrene	128	ug/kg	12.5	3.7	1	04/23/19 08:41	04/23/19 19:09		
1-Methylnaphthalene	31.7	ug/kg	22.8	6.8	1	04/23/19 08:41	04/23/19 19:09		
2-Methylnaphthalene	44.8	ug/kg	28.4	8.5	1	04/23/19 08:41	04/23/19 19:09		
Naphthalene	82.1	ug/kg	47.8	14.3	1	04/23/19 08:41	04/23/19 19:09		
Phenanthrene	395	ug/kg	66.0	19.8	1	04/23/19 08:41	04/23/19 19:09		
Pyrene	438	ug/kg	25.5	7.7	1	04/23/19 08:41	04/23/19 19:09		
Surrogates	100	agritg	20.0	• • • •	•	0 1/20/10 00:11	0 1/20/10 10:00	120 00 0	
2-Fluorobiphenyl (S)	50	%	28-99		1	04/23/19 08:41	04/23/19 19:09	321-60-8	
Terphenyl-d14 (S)	45	%	10-107		1	04/23/19 08:41	04/23/19 19:09	1718-51-0	
8260 MSV Med Level Normal List	Analytical	Method: EPA	A 8260 Prepara	ation Metho	od: EP/	A 5035/5030B			
1,2,4-Trimethylbenzene	<25.0	ug/kg	60.0	25.0	1	04/23/19 08:30	04/24/19 02:41	95-63-6	W
1,3,5-Trimethylbenzene	<25.0	ug/kg	60.0	25.0	1	04/23/19 08:30	04/24/19 02:41	108-67-8	W
Benzene	<25.0	ug/kg	60.0	25.0	1	04/23/19 08:30	04/24/19 02:41	71-43-2	W
Ethylbenzene	<25.0	ug/kg	60.0	25.0	1	04/23/19 08:30	04/24/19 02:41	100-41-4	W
Methyl-tert-butyl ether	<25.0	ug/kg	60.0	25.0	1	04/23/19 08:30	04/24/19 02:41	1634-04-4	W
Naphthalene	<40.0	ug/kg	250	40.0	1	04/23/19 08:30			W
Toluene	72.3J	ug/kg	102	42.6	1	04/23/19 08:30	04/24/19 02:41	108-88-3	
Xylene (Total)	<75.0	ug/kg	180	75.0	1	04/23/19 08:30	04/24/19 02:41		W
m&p-Xylene	<50.0	ug/kg	120	50.0	1	04/23/19 08:30	04/24/19 02:41		
o-Xylene	<25.0	ug/kg	60.0	25.0	1	04/23/19 08:30	04/24/19 02:41		W
Surrogates	12010	~g/g	00.0	_0.0	•	0 1/20/ 10 00:00	0 1/2 1/10 02111		•••
Dibromofluoromethane (S)	106	%	57-146		1	04/23/19 08:30	04/24/19 02:41	1868-53-7	
Toluene-d8 (S)	100	%	64-134		1	04/23/19 08:30	04/24/19 02:41	2037-26-5	
4-Bromofluorobenzene (S)	111	%	54-126		1	04/23/19 08:30	04/24/19 02:41	460-00-4	
Percent Moisture	Analytical	Method: AS	ΓM D2974-87						
Percent Moisture	41.3	%	0.10	0.10	1		04/24/19 19:37		



Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

Sample: B-5 (1-2.5') Lab ID: 40185945009 Collected: 04/16/19 09:25 Received: 04/17/19 09:30 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual	
6010 MET ICP	Analytical Method: EPA 6010 Preparation Method: EPA 3050									
Arsenic	24.2	mg/kg	6.3	1.3	1	04/18/19 09:15	04/22/19 14:43	7440-38-2		
Barium	26.9	mg/kg	0.63	0.19	1	04/18/19 09:15	04/22/19 14:43	7440-39-3		
Cadmium	2.3	mg/kg	0.63	0.17	1	04/18/19 09:15	04/22/19 14:43	7440-43-9		
Chromium	13.6	mg/kg	1.3	0.35	1	04/18/19 09:15	04/22/19 14:43	7440-47-3		
Lead	24.4	mg/kg	2.5	0.75	1	04/18/19 09:15	04/22/19 14:43	7439-92-1		
Selenium	<1.6	mg/kg	5.5	1.6	1	04/18/19 09:15	04/22/19 14:43	7782-49-2		
Silver	0.78J	mg/kg	1.3	0.43	1	04/18/19 09:15	04/22/19 14:43	7440-22-4		
7471 Mercury	Analytical Method: EPA 7471 Preparation Method: EPA 7471									
Mercury	0.014J	mg/kg	0.040	0.012	1	04/22/19 12:08	04/23/19 10:57	7439-97-6		
8270 MSSV PAH by SIM	Analytical	Analytical Method: EPA 8270 by SIM Preparation Method: EPA 3546								
Acenaphthene	<99.2	ug/kg	330	99.2	20	04/22/19 08:19	04/22/19 16:26	83-32-9		
Acenaphthylene	<84.2	ug/kg	281	84.2	20	04/22/19 08:19	04/22/19 16:26	208-96-8		
Anthracene	579	ug/kg	486	146	20	04/22/19 08:19	04/22/19 16:26	120-12-7		
Benzo(a)anthracene	2300	ug/kg	271	81.0	20	04/22/19 08:19	04/22/19 16:26	56-55-3		
Benzo(a)pyrene	2540	ug/kg	214	64.2	20	04/22/19 08:19	04/22/19 16:26	50-32-8		
Benzo(b)fluoranthene	2670	ug/kg	240	72.2	20	04/22/19 08:19	04/22/19 16:26	205-99-2		
Benzo(g,h,i)perylene	2040	ug/kg	173	51.9	20	04/22/19 08:19	04/22/19 16:26	191-24-2		
Benzo(k)fluoranthene	2050	ug/kg	214	64.1	20	04/22/19 08:19	04/22/19 16:26	207-08-9		
Chrysene	2500	ug/kg	286	86.2	20	04/22/19 08:19	04/22/19 16:26	218-01-9		
Dibenz(a,h)anthracene	698	ug/kg	190	57.1	20	04/22/19 08:19	04/22/19 16:26	53-70-3		
Fluoranthene	4970	ug/kg	445	133	20	04/22/19 08:19	04/22/19 16:26	206-44-0		
Fluorene	<106	ug/kg	353	106	20	04/22/19 08:19	04/22/19 16:26	86-73-7		
Indeno(1,2,3-cd)pyrene	1760	ug/kg	187	56.2	20	04/22/19 08:19	04/22/19 16:26	193-39-5		
1-Methylnaphthalene	<103	ug/kg	342	103	20	04/22/19 08:19	04/22/19 16:26	90-12-0		
2-Methylnaphthalene	<128	ug/kg	427	128	20	04/22/19 08:19	04/22/19 16:26	91-57-6		
Naphthalene	<215	ug/kg	718	215	20	04/22/19 08:19	04/22/19 16:26	91-20-3		
Phenanthrene	2020	ug/kg	991	298	20	04/22/19 08:19	04/22/19 16:26	85-01-8		
Pyrene	3610	ug/kg	383	115	20	04/22/19 08:19	04/22/19 16:26	129-00-0		
Surrogates										
2-Fluorobiphenyl (S)	53	%	28-99		20	04/22/19 08:19	04/22/19 16:26	321-60-8		
Terphenyl-d14 (S)	49	%	10-107		20	04/22/19 08:19	04/22/19 16:26	1718-51-0		
2260 MSV Med Level Normal List Analytical Method: EPA 8260 Preparation Method: EPA 5035/5030B										
1,2,4-Trimethylbenzene	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 13:50	95-63-6	W	
1,3,5-Trimethylbenzene	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 13:50	108-67-8	W	
Benzene	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 13:50	71-43-2	W	
Ethylbenzene	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 13:50	100-41-4	W	
Methyl-tert-butyl ether	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 13:50	1634-04-4	W	
Naphthalene	<40.0	ug/kg	250	40.0	1	04/18/19 08:15	04/18/19 13:50	91-20-3	W	
Toluene	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 13:50	108-88-3	W	
Xylene (Total)	<75.0	ug/kg	180	75.0	1	04/18/19 08:15	04/18/19 13:50	1330-20-7	W	
m&p-Xylene	<50.0	ug/kg	120	50.0	1	04/18/19 08:15	04/18/19 13:50	179601-23-1	W	
o-Xylene	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 13:50	95-47-6	W	

(920)469-2436



ANALYTICAL RESULTS

Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

Sample: B-5 (1-2.5') Lab ID: 40185945009 Collected: 04/16/19 09:25 Received: 04/17/19 09:30 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
8260 MSV Med Level Normal List	Analytical	Method: EP/	A 8260 Prepara	ation Metho	od: EP/	A 5035/5030B			
Surrogates									
Dibromofluoromethane (S)	96	%	57-146		1	04/18/19 08:15	04/18/19 13:50	1868-53-7	
Toluene-d8 (S)	93	%	64-134		1	04/18/19 08:15	04/18/19 13:50	2037-26-5	
4-Bromofluorobenzene (S)	104	%	54-126		1	04/18/19 08:15	04/18/19 13:50	460-00-4	
Percent Moisture	Analytical	Method: AS	TM D2974-87						
Percent Moisture	21.7	%	0.10	0.10	1		04/23/19 09:19		



Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

Sample: B-5 (4-5') Lab ID: 40185945010 Collected: 04/16/19 09:25 Received: 04/17/19 09:30 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual	
6010 MET ICP	Analytical Method: EPA 6010 Preparation Method: EPA 3050									
Arsenic	4.9J	mg/kg	6.8	1.4	1	04/23/19 07:13	04/23/19 12:49	7440-38-2		
Barium	107	mg/kg	0.68	0.20	1	04/23/19 07:13	04/23/19 12:49	7440-39-3	M0,R1	
Cadmium	0.45J	mg/kg	0.68	0.18	1	04/23/19 07:13	04/23/19 12:49	7440-43-9		
Chromium	17.4	mg/kg	1.4	0.38	1	04/23/19 07:13	04/23/19 12:49	7440-47-3		
Lead	81.5	mg/kg	2.7	0.81	1	04/23/19 07:13	04/23/19 12:49	7439-92-1	M0,R1	
Selenium	<1.8	mg/kg	5.9	1.8	1	04/23/19 07:13	04/23/19 12:49	7782-49-2	•	
Silver	0.54J	mg/kg	1.4	0.47	1	04/23/19 07:13	04/23/19 12:49	7440-22-4		
7471 Mercury	Analytical Method: EPA 7471 Preparation Method: EPA 7471									
Mercury	0.29	mg/kg	0.044	0.013	1	04/24/19 08:52	04/25/19 09:19	7439-97-6		
8270 MSSV PAH by SIM	Analytical Method: EPA 8270 by SIM Preparation Method: EPA 3546									
Acenaphthene	145	ug/kg	17.5	5.3	1	04/23/19 08:41	04/23/19 19:26	83-32-9		
Acenaphthylene	486	ug/kg	15.0	4.5	1	04/23/19 08:41	04/23/19 19:26	208-96-8		
Anthracene	330	ug/kg	25.8	7.8	1	04/23/19 08:41	04/23/19 19:26	120-12-7		
Benzo(a)anthracene	502	ug/kg	14.4	4.3	1	04/23/19 08:41	04/23/19 19:26	56-55-3		
Benzo(a)pyrene	702	ug/kg	11.4	3.4	1	04/23/19 08:41	04/23/19 19:26	50-32-8		
Benzo(b)fluoranthene	758	ug/kg	12.8	3.8	1	04/23/19 08:41	04/23/19 19:26	205-99-2		
Benzo(g,h,i)perylene	460	ug/kg	9.2	2.8	1	04/23/19 08:41	04/23/19 19:26	191-24-2		
Benzo(k)fluoranthene	240	ug/kg	11.4	3.4	1	04/23/19 08:41	04/23/19 19:26	207-08-9		
Chrysene	552	ug/kg	15.2	4.6	1	04/23/19 08:41	04/23/19 19:26	218-01-9		
Dibenz(a,h)anthracene	126	ug/kg	10.1	3.0	1	04/23/19 08:41	04/23/19 19:26	53-70-3		
Fluoranthene	712	ug/kg	23.7	7.1	1	04/23/19 08:41	04/23/19 19:26	206-44-0		
Fluorene	201	ug/kg	18.8	5.6	1	04/23/19 08:41	04/23/19 19:26			
Indeno(1,2,3-cd)pyrene	346	ug/kg	10	3.0	1	04/23/19 08:41	04/23/19 19:26			
1-Methylnaphthalene	217	ug/kg	18.2	5.5	1	04/23/19 08:41	04/23/19 19:26			
2-Methylnaphthalene	324	ug/kg	22.7	6.8	1	04/23/19 08:41				
Naphthalene	757	ug/kg	38.2	11.4	1	04/23/19 08:41				
Phenanthrene	468	ug/kg ug/kg	52.7	15.8	1	04/23/19 08:41	04/23/19 19:26			
Pyrene	890	ug/kg	20.4	6.1	1	04/23/19 08:41				
Surrogates		~g/g		0	•	0 1/20/10 00111	0 1/20/ 10 10120	.20 00 0		
2-Fluorobiphenyl (S)	52	%	28-99		1	04/23/19 08:41	04/23/19 19:26	321-60-8		
Terphenyl-d14 (S)	51	%	10-107		1	04/23/19 08:41	04/23/19 19:26	1718-51-0		
8260 MSV Med Level Normal List	Analytical	Method: EPA	A 8260 Prepar	ation Metho	od: EP	A 5035/5030B				
1,2,4-Trimethylbenzene	45.5J	ug/kg	81.6	34.0	1	04/23/19 08:30	04/24/19 20:02	95-63-6		
1,3,5-Trimethylbenzene	<25.0	ug/kg	60.0	25.0	1	04/23/19 08:30	04/24/19 20:02	108-67-8	W	
Benzene	37.0J	ug/kg	81.6	34.0	1	04/23/19 08:30	04/24/19 20:02	71-43-2		
Ethylbenzene	49.2J	ug/kg	81.6	34.0	1	04/23/19 08:30	04/24/19 20:02	100-41-4		
Methyl-tert-butyl ether	<25.0	ug/kg	60.0	25.0	1	04/23/19 08:30			W	
Naphthalene	283J	ug/kg	340	54.4	1		04/24/19 20:02			
Toluene	48.2J	ug/kg	81.6	34.0	1		04/24/19 20:02			
Xylene (Total)	105J	ug/kg	245	102	1	04/23/19 08:30				
m&p-Xylene	75.0J	ug/kg	163	68.0	1	04/23/19 08:30				
o-Xylene	<25.0	ug/kg	60.0	25.0	1		04/24/19 20:02		W	
. ,		9 9	00.0		•			•		



ANALYTICAL RESULTS

Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

Sample: B-5 (4-5') Lab ID: 40185945010 Collected: 04/16/19 09:25 Received: 04/17/19 09:30 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual	
8260 MSV Med Level Normal List	Analytical	Method: EPA	A 8260 Prepar	ation Metho	od: EP/	A 5035/5030B				
Surrogates										
Dibromofluoromethane (S)	109	%	57-146		1	04/23/19 08:30	04/24/19 20:02	1868-53-7		
Toluene-d8 (S)	108	%	64-134		1	04/23/19 08:30	04/24/19 20:02	2037-26-5		
4-Bromofluorobenzene (S)	122	%	54-126		1	04/23/19 08:30	04/24/19 20:02	460-00-4		
Percent Moisture	Analytical Method: ASTM D2974-87									
Percent Moisture	26.4	%	0.10	0.10	1		04/23/19 09:19			



ANALYTICAL RESULTS

Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

Sample: B-6 (1-2') Lab ID: 40185945011 Collected: 04/16/19 10:00 Received: 04/17/19 09:30 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
6010 MET ICP	Analytical	Method: EPA	A 6010 Prepa	ration Meth	od: EP	A 3050			
Arsenic	10.5	mg/kg	7.0	1.5	1	04/18/19 09:15	04/22/19 14:46	7440-38-2	
Barium	50.9	mg/kg	0.70	0.21	1	04/18/19 09:15	04/22/19 14:46	7440-39-3	
Cadmium	0.19J	mg/kg	0.70	0.19	1	04/18/19 09:15	04/22/19 14:46	7440-43-9	
Chromium	9.3	mg/kg	1.4	0.39	1	04/18/19 09:15	04/22/19 14:46	7440-47-3	
Lead	11.3	mg/kg	2.8	0.83	1		04/22/19 14:46		
Selenium	<1.8	mg/kg	6.1	1.8	1	04/18/19 09:15	04/22/19 14:46	7782-49-2	
Silver	0.55J	mg/kg	1.4	0.48	1	04/18/19 09:15	04/22/19 14:46	7440-22-4	
7471 Mercury	Analytical	Method: EPA	A 7471 Prepa	ration Meth	od: EP	A 7471			
Mercury	0.023J	mg/kg	0.049	0.015	1	04/22/19 12:08	04/23/19 10:59	7439-97-6	
8270 MSSV PAH by SIM	Analytical	Method: EPA	A 8270 by SIM	Preparation	on Meth	nod: EPA 3546			
Acenaphthene	35.8	ug/kg	18.9	5.7	1	04/22/19 08:19	04/24/19 14:10	83-32-9	
Acenaphthylene	4.9J	ug/kg	16.2	4.8	1	04/22/19 08:19	04/24/19 14:10		
Anthracene	29.6	ug/kg	27.9	8.4	1	04/22/19 08:19			
Benzo(a)anthracene	32.2	ug/kg	15.6	4.7	1	04/22/19 08:19			
Benzo(a)pyrene	23.4	ug/kg	12.3	3.7	1		04/24/19 14:10		
Benzo(b)fluoranthene	18.3	ug/kg	13.8	4.1	1		04/24/19 14:10		
Benzo(g,h,i)perylene	9.5J	ug/kg	9.9	3.0	1		04/24/19 14:10		
Benzo(k)fluoranthene	6.2J	ug/kg	12.3	3.7	1	04/22/19 08:19			
Chrysene	31.0	ug/kg	16.4	5.0	1	04/22/19 08:19	04/24/19 14:10		
Dibenz(a,h)anthracene	<3.3	ug/kg ug/kg	10.9	3.3	1	04/22/19 08:19			
Fluoranthene	49.2	ug/kg ug/kg	25.6	7.6	1		04/24/19 14:10		
Fluorene	43.3	ug/kg ug/kg	20.3	6.1	1		04/24/19 14:10		
Indeno(1,2,3-cd)pyrene	3.6J	ug/kg ug/kg	10.8	3.2	1	04/22/19 08:19			
1-Methylnaphthalene	47.2	ug/kg ug/kg	19.7	5.2	1	04/22/19 08:19			
2-Methylnaphthalene	50.2	ug/kg ug/kg	24.5	7.3	1		04/24/19 14:10		
Naphthalene	40.3J	ug/kg ug/kg	41.3	12.4	1		04/24/19 14:10		
Phenanthrene	234	ug/kg ug/kg	57.0	17.1	1	04/22/19 08:19			
	44.4		22.0	6.6	1	04/22/19 08:19			
Pyrene Surrogates	44.4	ug/kg	22.0	0.0	'	04/22/19 00.19	04/24/19 14.10	129-00-0	
2-Fluorobiphenyl (S)	32	%	28-99		1	04/22/19 08:19	04/24/19 14:10	321-60-8	
Terphenyl-d14 (S)	18	%	10-107		1	04/22/19 08:19	04/24/19 14:10		
8260 MSV Med Level Normal List	Analytical	Method: EPA	A 8260 Prepa	ration Meth	od: EP	A 5035/5030B			
1,2,4-Trimethylbenzene	200	ug/kg	119	49.7	1	04/18/19 08:15	04/18/19 18:21	95-63-6	
1,3,5-Trimethylbenzene	83.5J	ug/kg	119	49.7	1	04/18/19 08:15	04/18/19 18:21	108-67-8	
Benzene	<33.8	ug/kg	81.1	33.8	1	04/18/19 08:15	04/18/19 18:21		W
Ethylbenzene	<33.8	ug/kg	81.1	33.8	1	04/18/19 08:15	04/18/19 18:21	100-41-4	W
Methyl-tert-butyl ether	<33.8	ug/kg	81.1	33.8	1	04/18/19 08:15	04/18/19 18:21		W
Naphthalene	112J	ug/kg ug/kg	497	79.6	1	04/18/19 08:15			
Toluene	61.3J	ug/kg	119	49.7	1	04/18/19 08:15			
Xylene (Total)	258J	ug/kg ug/kg	358	149	1		04/18/19 18:21		
m&p-Xylene	122J	ug/kg ug/kg	238	99.4	1	04/18/19 08:15			
o-Xylene	136	ug/kg ug/kg	119	49.7	1		04/18/19 18:21		
U-Aylette	130	ug/kg	119	49.7	ı	04/10/19 06:15	04/10/19 10:21	30-47-0	



ANALYTICAL RESULTS

Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

Sample: B-6 (1-2') Lab ID: 40185945011 Collected: 04/16/19 10:00 Received: 04/17/19 09:30 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual	
8260 MSV Med Level Normal List	Analytical	Method: EP/	A 8260 Prepai	ration Metho	od: EPA	A 5035/5030B				
Surrogates										
Dibromofluoromethane (S)	94	%	57-146		1	04/18/19 08:15	04/18/19 18:21	1868-53-7		
Toluene-d8 (S)	86	%	64-134		1	04/18/19 08:15	04/18/19 18:21	2037-26-5		
4-Bromofluorobenzene (S)	84	%	54-126		1	04/18/19 08:15	04/18/19 18:21	460-00-4		
Percent Moisture	Analytical Method: ASTM D2974-87									
Percent Moisture	32.0	%	0.10	0.10	1		04/23/19 09:19			



ANALYTICAL RESULTS

Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

Sample: B-7 (1-2.5') Lab ID: 40185945012 Collected: 04/16/19 10:20 Received: 04/17/19 09:30 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
6010 MET ICP	Analytical	Method: EPA	A 6010 Prepar	ation Meth	od: EP/	A 3050			
Arsenic	<1.2	mg/kg	5.8	1.2	1	04/18/19 09:15	04/22/19 14:48	7440-38-2	
Barium	40.9	mg/kg	0.58	0.17	1	04/18/19 09:15	04/22/19 14:48	7440-39-3	
Cadmium	<0.15	mg/kg	0.58	0.15	1	04/18/19 09:15	04/22/19 14:48	7440-43-9	
Chromium	16.3	mg/kg	1.2	0.32	1	04/18/19 09:15	04/22/19 14:48	7440-47-3	
Lead	8.2	mg/kg	2.3	0.69	1	04/18/19 09:15	04/22/19 14:48	7439-92-1	
Selenium	<1.5	mg/kg	5.0	1.5	1	04/18/19 09:15	04/22/19 14:48	7782-49-2	
Silver	0.54J	mg/kg	1.2	0.40	1	04/18/19 09:15	04/22/19 14:48	7440-22-4	
7471 Mercury	Analytical	Method: EPA	7471 Prepar	ation Metho	od: EP/	A 7471			
Mercury	0.015J	mg/kg	0.040	0.012	1	04/22/19 12:08	04/23/19 11:02	7439-97-6	
8270 MSSV PAH by SIM	Analytical	Method: EPA	\ 8270 by SIM	Preparation	n Meth	nod: EPA 3546			
Acenaphthene	100J	ug/kg	121	36.3	8	04/22/19 08:19	04/24/19 22:46	83-32-9	
Acenaphthylene	327	ug/kg	103	30.8	8	04/22/19 08:19	04/24/19 22:46	208-96-8	
Anthracene	383	ug/kg	178	53.4	8	04/22/19 08:19	04/24/19 22:46	120-12-7	
Benzo(a)anthracene	924	ug/kg	99.0	29.6	8	04/22/19 08:19	04/24/19 22:46	56-55-3	
Benzo(a)pyrene	1040	ug/kg	78.2	23.5	8	04/22/19 08:19	04/24/19 22:46	50-32-8	
Benzo(b)fluoranthene	1080	ug/kg	87.9	26.4	8	04/22/19 08:19	04/24/19 22:46	205-99-2	
Benzo(g,h,i)perylene	782	ug/kg	63.3	19.0	8	04/22/19 08:19	04/24/19 22:46	191-24-2	
Benzo(k)fluoranthene	837	ug/kg	78.1	23.4	8	04/22/19 08:19	04/24/19 22:46	207-08-9	
Chrysene	1120	ug/kg	105	31.5	8	04/22/19 08:19	04/24/19 22:46	218-01-9	
Dibenz(a,h)anthracene	258	ug/kg	69.6	20.9	8	04/22/19 08:19	04/24/19 22:46	53-70-3	
Fluoranthene	1960	ug/kg	163	48.7	8	04/22/19 08:19	04/24/19 22:46	206-44-0	
Fluorene	163	ug/kg	129	38.7	8	04/22/19 08:19	04/24/19 22:46	86-73-7	
Indeno(1,2,3-cd)pyrene	690	ug/kg	68.5	20.5	8	04/22/19 08:19	04/24/19 22:46	193-39-5	
1-Methylnaphthalene	918	ug/kg	125	37.6	8	04/22/19 08:19	04/24/19 22:46	90-12-0	
2-Methylnaphthalene	825	ug/kg	156	46.7	8	04/22/19 08:19	04/24/19 22:46	91-57-6	
Naphthalene	2960	ug/kg	263	78.7	8	04/22/19 08:19	04/24/19 22:46	91-20-3	
Phenanthrene	1920	ug/kg	363	109	8	04/22/19 08:19	04/24/19 22:46	85-01-8	
Pyrene	1670	ug/kg	140	42.2	8	04/22/19 08:19	04/24/19 22:46	129-00-0	
Surrogates									
2-Fluorobiphenyl (S)	54	%	28-99		8	04/22/19 08:19	04/24/19 22:46	321-60-8	
Terphenyl-d14 (S)	50	%	10-107		8	04/22/19 08:19	04/24/19 22:46	1718-51-0	
8260 MSV Med Level Normal List	Analytical	Method: EPA	N 8260 Prepar	ation Metho	od: EP/	A 5035/5030B			
1,2,4-Trimethylbenzene	205	ug/kg	75.4	31.4	1	04/18/19 08:15	04/18/19 14:13	95-63-6	
1,3,5-Trimethylbenzene	60.1J	ug/kg	75.4	31.4	1	04/18/19 08:15	04/18/19 14:13	108-67-8	
Benzene	<26.9	ug/kg	64.5	26.9	1	04/18/19 08:15	04/18/19 14:13	71-43-2	W
Ethylbenzene	90.3	ug/kg	75.4	31.4	1	04/18/19 08:15	04/18/19 14:13	100-41-4	
Methyl-tert-butyl ether	<26.9	ug/kg	64.5	26.9	1	04/18/19 08:15	04/18/19 14:13	1634-04-4	W
Naphthalene	260J	ug/kg	314	50.3	1	04/18/19 08:15	04/18/19 14:13	91-20-3	
Toluene	223	ug/kg	75.4	31.4	1	04/18/19 08:15	04/18/19 14:13	108-88-3	
Xylene (Total)	560	ug/kg	226	94.2	1	04/18/19 08:15	04/18/19 14:13	1330-20-7	
m&p-Xylene	318	ug/kg	151	62.8	1	04/18/19 08:15	04/18/19 14:13	179601-23-1	
o-Xylene	242	ug/kg	75.4	31.4	1	04/19/10 09:15	04/18/19 14:13	05 47 6	



ANALYTICAL RESULTS

Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

Sample: B-7 (1-2.5') Lab ID: 40185945012 Collected: 04/16/19 10:20 Received: 04/17/19 09:30 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual	
8260 MSV Med Level Normal List	Analytical	Method: EPA	A 8260 Prepara	ation Metho	od: EP/	A 5035/5030B				
Surrogates										
Dibromofluoromethane (S)	93	%	57-146		1	04/18/19 08:15	04/18/19 14:13	1868-53-7		
Toluene-d8 (S)	94	%	64-134		1	04/18/19 08:15	04/18/19 14:13	2037-26-5		
4-Bromofluorobenzene (S)	105	%	54-126		1	04/18/19 08:15	04/18/19 14:13	460-00-4		
Percent Moisture	Analytical Method: ASTM D2974-87									
Percent Moisture	14.4	%	0.10	0.10	1		04/23/19 09:19			



ANALYTICAL RESULTS

Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

Sample: B-8 (1-2.5') Lab ID: 40185945013 Collected: 04/16/19 09:40 Received: 04/17/19 09:30 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
6010 MET ICP	Analytical	Method: EP	A 6010 Prepar	ation Meth	od: EP	A 3050			
Arsenic	8.8	mg/kg	6.1	1.3	1	04/18/19 09:15	04/22/19 14:50	7440-38-2	
Barium	18.1	mg/kg	0.61	0.18	1	04/18/19 09:15	04/22/19 14:50	7440-39-3	
Cadmium	<0.16	mg/kg	0.61	0.16	1	04/18/19 09:15	04/22/19 14:50	7440-43-9	
Chromium	7.9	mg/kg	1.2	0.34	1	04/18/19 09:15	04/22/19 14:50	7440-47-3	
Lead	3.6	mg/kg	2.5	0.74	1	04/18/19 09:15	04/22/19 14:50	7439-92-1	
Selenium	2.8J	mg/kg	5.4	1.6	1	04/18/19 09:15	04/22/19 14:50	7782-49-2	В
Silver	<0.42	mg/kg	1.2	0.42	1		04/22/19 14:50		
7471 Mercury	Analytical	Method: EP	A 7471 Prepar	ation Meth	od: EP	A 7471			
Mercury	<0.012	mg/kg	0.040	0.012	1	04/22/19 12:08	04/23/19 11:04	7439-97-6	
8270 MSSV PAH by SIM	Analytical	Method: EP	A 8270 by SIM	Preparation	n Meth	nod: EPA 3546			
Acenaphthene	7.7J	ug/kg	16.6	5.0	1	04/22/19 08:19	04/24/19 14:27	83-32-9	
Acenaphthylene	5.4J	ug/kg	14.2	4.3	1	04/22/19 08:19	04/24/19 14:27	208-96-8	
Anthracene	22.4J	ug/kg	24.5	7.4	1	04/22/19 08:19	04/24/19 14:27	120-12-7	
Benzo(a)anthracene	33.6	ug/kg	13.7	4.1	1	04/22/19 08:19	04/24/19 14:27	56-55-3	
Benzo(a)pyrene	24.1	ug/kg	10.8	3.2	1	04/22/19 08:19	04/24/19 14:27	50-32-8	
Benzo(b)fluoranthene	25.7	ug/kg	12.1	3.6	1	04/22/19 08:19		205-99-2	
Benzo(g,h,i)perylene	11.9	ug/kg	8.7	2.6	1	04/22/19 08:19	04/24/19 14:27	191-24-2	
Benzo(k)fluoranthene	7.8J	ug/kg	10.8	3.2	1	04/22/19 08:19			
Chrysene	30.6	ug/kg	14.5	4.4	1	04/22/19 08:19	04/24/19 14:27	218-01-9	
Dibenz(a,h)anthracene	3.3J	ug/kg	9.6	2.9	1	04/22/19 08:19	04/24/19 14:27	53-70-3	
Fluoranthene	39.4	ug/kg	22.5	6.7	1	04/22/19 08:19			
Fluorene	<5.3	ug/kg	17.8	5.3	1		04/24/19 14:27		
Indeno(1,2,3-cd)pyrene	6.3J	ug/kg	9.5	2.8	1	04/22/19 08:19			
1-Methylnaphthalene	100	ug/kg	17.3	5.2	1	04/22/19 08:19			
2-Methylnaphthalene	85.5	ug/kg	21.5	6.5	1	04/22/19 08:19			
Naphthalene	29.7J	ug/kg	36.3	10.9	1		04/24/19 14:27		
Phenanthrene	122	ug/kg	50.1	15.0	1	04/22/19 08:19			
Pyrene	37.0	ug/kg	19.4	5.8	1	04/22/19 08:19			
Surrogates		-99							
2-Fluorobiphenyl (S)	56	%	28-99		1	04/22/19 08:19	04/24/19 14:27	321-60-8	
Terphenyl-d14 (S)	54	%	10-107		1	04/22/19 08:19	04/24/19 14:27	1718-51-0	
8260 MSV Med Level Normal List	Analytical	Method: EP	A 8260 Prepar	ation Meth	od: EP	A 5035/5030B			
1,2,4-Trimethylbenzene	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 14:36	95-63-6	W
1,3,5-Trimethylbenzene	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 14:36	108-67-8	W
Benzene	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 14:36	71-43-2	W
Ethylbenzene	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 14:36	100-41-4	W
Methyl-tert-butyl ether	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 14:36	1634-04-4	W
Naphthalene	<40.0	ug/kg	250	40.0	1	04/18/19 08:15	04/18/19 14:36	91-20-3	W
Toluene	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 14:36	108-88-3	W
Xylene (Total)	<75.0	ug/kg	180	75.0	1		04/18/19 14:36		W
m&p-Xylene	<50.0	ug/kg	120	50.0	1	04/18/19 08:15			W
o-Xylene	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 14:36	95-47-6	W



ANALYTICAL RESULTS

Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

Sample: B-8 (1-2.5') Lab ID: 40185945013 Collected: 04/16/19 09:40 Received: 04/17/19 09:30 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual	
8260 MSV Med Level Normal List	Analytical	Method: EPA	A 8260 Prepar	ation Metho	od: EP/	A 5035/5030B				
Surrogates										
Dibromofluoromethane (S)	96	%	57-146		1	04/18/19 08:15	04/18/19 14:36	1868-53-7		
Toluene-d8 (S)	95	%	64-134		1	04/18/19 08:15	04/18/19 14:36	2037-26-5		
4-Bromofluorobenzene (S)	100	%	54-126		1	04/18/19 08:15	04/18/19 14:36	460-00-4		
Percent Moisture	Analytical Method: ASTM D2974-87									
Percent Moisture	22.6	%	0.10	0.10	1		04/23/19 09:19			



ANALYTICAL RESULTS

Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

Sample: TRIP BLANK Lab ID: 40185945014 Collected: 04/16/19 00:00 Received: 04/17/19 09:30 Matrix: Solid

Results reported on a "wet-weight" basis

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
8260 MSV Med Level Normal List	Analytical	Method: EPA	A 8260 Prepar	ation Metho	od: EP	A 5035/5030B			
1,2,4-Trimethylbenzene	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 12:17	95-63-6	W
1,3,5-Trimethylbenzene	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 12:17	108-67-8	W
Benzene	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 12:17	71-43-2	W
Ethylbenzene	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 12:17	100-41-4	W
Methyl-tert-butyl ether	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 12:17	1634-04-4	W
Naphthalene	<40.0	ug/kg	250	40.0	1	04/18/19 08:15	04/18/19 12:17	91-20-3	W
Toluene	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 12:17	108-88-3	W
Xylene (Total)	<75.0	ug/kg	180	75.0	1	04/18/19 08:15	04/18/19 12:17	1330-20-7	W
m&p-Xylene	<50.0	ug/kg	120	50.0	1	04/18/19 08:15	04/18/19 12:17	179601-23-1	W
o-Xylene	<25.0	ug/kg	60.0	25.0	1	04/18/19 08:15	04/18/19 12:17	95-47-6	W
Surrogates									
Dibromofluoromethane (S)	89	%	57-146		1	04/18/19 08:15	04/18/19 12:17	1868-53-7	
Toluene-d8 (S)	88	%	64-134		1	04/18/19 08:15	04/18/19 12:17	2037-26-5	
4-Bromofluorobenzene (S)	107	%	54-126		1	04/18/19 08:15	04/18/19 12:17	460-00-4	



Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

QC Batch: 319053 Analysis Method: EPA 7471

QC Batch Method: EPA 7471 Analysis Description: 7471 Mercury

Associated Lab Samples: 40185945009, 40185945011, 40185945012, 40185945013

METHOD BLANK: 1854354 Matrix: Solid

Associated Lab Samples: 40185945009, 40185945011, 40185945012, 40185945013

Blank Reporting

Parameter Units Result Limit Analyzed Qualifiers

Mercury mg/kg <0.010 0.035 04/23/19 10:06

LABORATORY CONTROL SAMPLE: 1854355

Spike LCS LCS % Rec Parameter Units Conc. Result % Rec Limits Qualifiers Mercury mg/kg 0.83 0.84 101 85-115

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 1854356 1854357

MS MSD 40185957001 Spike Spike MS MSD MS MSD % Rec Max Parameter Units Result Conc. Conc. Result Result % Rec % Rec Limits RPD RPD Qual 85-115 20 Mercury < 0.012 0.92 0.91 0.94 0.94 101 103 mg/kg

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.



Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

QC Batch: 319244 Analysis Method: EPA 7471

QC Batch Method: EPA 7471 Analysis Description: 7471 Mercury

Associated Lab Samples: 40185945010

METHOD BLANK: 1854981 Matrix: Solid

Associated Lab Samples: 40185945010

Blank Reporting
Parameter Units Result Limit Analyzed Qualifiers

Mercury mg/kg <0.010 0.035 04/25/19 09:08

LABORATORY CONTROL SAMPLE: 1854982

Spike LCS LCS % Rec Parameter Units Conc. Result % Rec Limits Qualifiers Mercury mg/kg 0.83 0.85 102 85-115

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 1854983 1854984

MS MSD 40186156001 Spike Spike MS MSD MS MSD % Rec Max Parameter Units Result Conc. Conc. Result Result % Rec % Rec Limits RPD RPD Qual 85-115 20 Mercury mg/kg 0.051 0.92 0.91 0.98 0.97 101 101

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.



Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

QC Batch: 318766 Analysis Method: EPA 6010
QC Batch Method: EPA 3050 Analysis Description: 6010 MET

Associated Lab Samples: 40185945009, 40185945011, 40185945012, 40185945013

METHOD BLANK: 1852423 Matrix: Solid

Associated Lab Samples: 40185945009, 40185945011, 40185945012, 40185945013

		Blank	Reporting		
Parameter	Units	Result	Limit	Analyzed	Qualifiers
Arsenic	mg/kg	<1.0	5.0	04/22/19 14:12	
Barium	mg/kg	<0.15	0.50	04/22/19 14:12	
Cadmium	mg/kg	< 0.13	0.50	04/22/19 14:12	
Chromium	mg/kg	<0.28	1.0	04/22/19 14:12	
Lead	mg/kg	< 0.60	2.0	04/22/19 14:12	
Selenium	mg/kg	1.6J	4.4	04/22/19 14:12	
Silver	mg/kg	< 0.34	1.0	04/22/19 14:12	

		Spike	LCS	LCS	% Rec	
Parameter	Units	Conc.	Result	% Rec	Limits	Qualifiers
Arsenic	mg/kg	50	47.9	96	80-120	
Barium	mg/kg	50	49.0	98	80-120	
Cadmium	mg/kg	50	50.2	100	80-120	
Chromium	mg/kg	50	48.7	97	80-120	
Lead	mg/kg	50	49.5	99	80-120	
Selenium	mg/kg	50	50.0	100	80-120	
Silver	mg/kg	25	25.8	103	80-120	

MATRIX SPIKE & MATRIX SP	IKE DUPLICA	TE: 18524	25		1852426							
			MS	MSD								
	40	0185943002	Spike	Spike	MS	MSD	MS	MSD	% Rec		Max	
Parameter	Units	Result	Conc.	Conc.	Result	Result	% Rec	% Rec	Limits	RPD	RPD	Qual
Arsenic	mg/kg	10.9	59.3	59.2	64.5	59.8	90	82	75-125	8	20	
Barium	mg/kg	52.3	59.3	59.2	122	120	117	114	75-125	1	20	
Cadmium	mg/kg	0.50J	59.3	59.2	59.0	56.4	99	94	75-125	4	20	
Chromium	mg/kg	22.7	59.3	59.2	81.8	77.6	100	93	75-125	5	20	
Lead	mg/kg	13.0	59.3	59.2	68.9	64.2	94	86	75-125	7	20	
Selenium	mg/kg	<1.6	59.3	59.2	57.6	54.3	97	92	75-125	6	20	
Silver	mg/kg	0.43J	29.7	29.7	30.5	30.2	101	100	75-125	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.



Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

QC Batch: 319136 Analysis Method: EPA 6010
QC Batch Method: EPA 3050 Analysis Description: 6010 MET

Associated Lab Samples: 40185945010

METHOD BLANK: 1854569 Matrix: Solid

Associated Lab Samples: 40185945010

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Arsenic	mg/kg	<1.0	5.0	04/23/19 12:44	
Barium	mg/kg	<0.15	0.50	04/23/19 12:44	
Cadmium	mg/kg	<0.13	0.50	04/23/19 12:44	
Chromium	mg/kg	<0.28	1.0	04/23/19 12:44	
Lead	mg/kg	< 0.60	2.0	04/23/19 12:44	
Selenium	mg/kg	<1.3	4.4	04/23/19 12:44	
Silver	mg/kg	< 0.34	1.0	04/23/19 12:44	

LABORATORY CONTROL SAMPLE:	1854570					
		Spike	LCS	LCS	% Rec	
Parameter	Units	Conc.	Result	% Rec	Limits	Qualifiers
Arsenic	mg/kg	50	46.9	94	80-120	
Barium	mg/kg	50	48.4	97	80-120	
Cadmium	mg/kg	50	48.2	96	80-120	
Chromium	mg/kg	50	51.6	103	80-120	
Lead	mg/kg	50	46.9	94	80-120	
Selenium	mg/kg	50	48.8	98	80-120	
Silver	mg/kg	25	26.3	105	80-120	

MATRIX SPIKE & MATRIX S	SPIKE DUPLICA	TE: 18545	71		1854572							
			MS	MSD								
	40	0185945010	Spike	Spike	MS	MSD	MS	MSD	% Rec		Max	
Parameter	Units	Result	Conc.	Conc.	Result	Result	% Rec	% Rec	Limits	RPD	RPD	Qual
Arsenic	mg/kg	4.9J	67.7	67.6	65.8	67.4	90	92	75-125	2	20	
Barium	mg/kg	107	67.7	67.6	286	177	264	104	75-125	47	20	M0,R1
Cadmium	mg/kg	0.45J	67.7	67.6	64.4	63.6	94	93	75-125	1	20	
Chromium	mg/kg	17.4	67.7	67.6	87.7	86.5	104	102	75-125	1	20	
Lead	mg/kg	81.5	67.7	67.6	133	94.9	76	20	75-125	34	20	M0,R1
Selenium	mg/kg	<1.8	67.7	67.6	64.8	64.9	94	95	75-125	0	20	
Silver	mg/kg	0.54J	33.8	33.8	34.8	34.7	101	101	75-125	0	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.



Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

QC Batch: 318800 Analysis Method: EPA 8260

QC Batch Method: EPA 5035/5030B Analysis Description: 8260 MSV Med Level Normal List

Associated Lab Samples: 40185945001, 40185945003, 40185945005, 40185945007, 40185945009, 40185945011, 40185945012,

40185945013, 40185945014

METHOD BLANK: 1852604 Matrix: Solid

Associated Lab Samples: 40185945001, 40185945003, 40185945005, 40185945007, 40185945009, 40185945011, 40185945012,


40185945013, 40185945014

		Blank	Reporting		
Parameter	Units	Result	Limit	Analyzed	Qualifiers
1,2,4-Trimethylbenzene	ug/kg	<12.2	50.0	04/18/19 09:52	
1,3,5-Trimethylbenzene	ug/kg	<14.5	50.0	04/18/19 09:52	
Benzene	ug/kg	<9.2	20.0	04/18/19 09:52	
Ethylbenzene	ug/kg	<12.4	50.0	04/18/19 09:52	
m&p-Xylene	ug/kg	<34.4	100	04/18/19 09:52	
Methyl-tert-butyl ether	ug/kg	<12.7	50.0	04/18/19 09:52	
Naphthalene	ug/kg	<40.0	250	04/18/19 09:52	
o-Xylene	ug/kg	<14.0	50.0	04/18/19 09:52	
Toluene	ug/kg	<11.2	50.0	04/18/19 09:52	
Xylene (Total)	ug/kg	<48.4	150	04/18/19 09:52	
4-Bromofluorobenzene (S)	%	108	54-126	04/18/19 09:52	
Dibromofluoromethane (S)	%	97	57-146	04/18/19 09:52	
Toluene-d8 (S)	%	96	64-134	04/18/19 09:52	

LABORATORY CONTROL SAMPLE:	1852605					
Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Benzene	ug/kg	2500	2410	96	70-130	
Ethylbenzene	ug/kg	2500	2510	101	82-122	
m&p-Xylene	ug/kg	5000	5130	103	70-130	
Methyl-tert-butyl ether	ug/kg	2500	2560	102	70-130	
o-Xylene	ug/kg	2500	2520	101	70-130	
Toluene	ug/kg	2500	2350	94	80-121	
Xylene (Total)	ug/kg	7500	7660	102	70-130	
4-Bromofluorobenzene (S)	%			114	54-126	
Dibromofluoromethane (S)	%			103	57-146	
Toluene-d8 (S)	%			97	64-134	

MATRIX SPIKE & MATRIX S	SPIKE DUPLICA	ATE: 18526	06		1852607							
	4	0185959004	MS Spike	MSD Spike	MS	MSD	MS	MSD	% Rec		Max	
Parameter	Units	Result	Conc.	Conc.	Result	Result	% Rec	% Rec	Limits	RPD		Qual
Benzene	ug/kg	<25.0	1280	1280	1280	1260	100	98	70-130	2	20	
Ethylbenzene	ug/kg	<25.0	1280	1280	1320	1250	103	97	80-122	5	20	
m&p-Xylene	ug/kg	<50.0	2570	2570	2740	2590	107	101	70-130	6	20	
Methyl-tert-butyl ether	ug/kg	<25.0	1280	1280	1290	1310	101	102	70-130	2	20	
o-Xylene	ug/kg	<25.0	1280	1280	1370	1310	107	102	70-130	4	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.





Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

MATRIX SPIKE & MATRIX SPI	IKE DUPLICA	TE: 18526	06		1852607							
Parameter	40 Units	0185959004 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Toluene	ug/kg	<25.0	1280	1280	1240	1160	96	90	80-121	7	20	
Xylene (Total)	ug/kg	<75.0	3850	3850	4110	3900	107	101	70-130	5	20	
4-Bromofluorobenzene (S)	%						123	119	54-126			
Dibromofluoromethane (S)	%						107	107	57-146			
Toluene-d8 (S)	%						104	103	64-134			

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.



Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

QC Batch: 319216 Analysis Method: EPA 8260

QC Batch Method: EPA 5035/5030B Analysis Description: 8260 MSV Med Level Normal List

Associated Lab Samples: 40185945002, 40185945004, 40185945006, 40185945008, 40185945010

METHOD BLANK: 1854870 Matrix: Solid

Associated Lab Samples: 40185945002, 40185945004, 40185945006, 40185945008, 40185945010

		Blank	Reporting			
Parameter	Units	Result	Limit	Analyzed	Qualifiers	
1,2,4-Trimethylbenzene	ug/kg	<12.2	50.0	04/23/19 18:12		
1,3,5-Trimethylbenzene	ug/kg	<14.5	50.0	04/23/19 18:12		
Benzene	ug/kg	<9.2	20.0	04/23/19 18:12		
Ethylbenzene	ug/kg	<12.4	50.0	04/23/19 18:12		
m&p-Xylene	ug/kg	<34.4	100	04/23/19 18:12		
Methyl-tert-butyl ether	ug/kg	<12.7	50.0	04/23/19 18:12		
Naphthalene	ug/kg	<40.0	250	04/23/19 18:12		
o-Xylene	ug/kg	<14.0	50.0	04/23/19 18:12		
Toluene	ug/kg	<11.2	50.0	04/23/19 18:12		
Xylene (Total)	ug/kg	<48.4	150	04/23/19 18:12		
4-Bromofluorobenzene (S)	%	114	54-126	04/23/19 18:12		
Dibromofluoromethane (S)	%	100	57-146	04/23/19 18:12		
Toluene-d8 (S)	%	98	64-134	04/23/19 18:12		

LABORATORY CONTROL SAMPLE:	1854871					
		Spike	LCS	LCS	% Rec	
Parameter	Units	Conc.	Result	% Rec	Limits	Qualifiers
Benzene	ug/kg	2500	2640	105	70-130	
Ethylbenzene	ug/kg	2500	2600	104	82-122	
m&p-Xylene	ug/kg	5000	5300	106	70-130	
Methyl-tert-butyl ether	ug/kg	2500	2590	104	70-130	
o-Xylene	ug/kg	2500	2640	106	70-130	
Toluene	ug/kg	2500	2450	98	80-121	
Xylene (Total)	ug/kg	7500	7940	106	70-130	
4-Bromofluorobenzene (S)	%			115	54-126	
Dibromofluoromethane (S)	%			102	57-146	
Toluene-d8 (S)	%			96	64-134	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.



Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

QC Batch: 319038 Analysis Method: EPA 8270 by SIM

QC Batch Method: EPA 3546 Analysis Description: 8270/3546 MSSV PAH by SIM

Associated Lab Samples: 40185945001, 40185945003, 40185945007, 40185945009, 40185945011, 40185945012, 40185945013

METHOD BLANK: 1854300 Matrix: Solid

Associated Lab Samples: 40185945001, 40185945003, 40185945007, 40185945009, 40185945011, 40185945012, 40185945013

Doromotor	Units	Blank	Reporting Limit	Analyzad	Qualifiers
Parameter		Result		Analyzed	
1-Methylnaphthalene	ug/kg	<4.0	13.4	04/22/19 14:59	
2-Methylnaphthalene	ug/kg	<5.0	16.7	04/22/19 14:59	
Acenaphthene	ug/kg	<3.9	12.9	04/22/19 14:59	
Acenaphthylene	ug/kg	<3.3	11.0	04/22/19 14:59	
Anthracene	ug/kg	<5.7	19.0	04/22/19 14:59	
Benzo(a)anthracene	ug/kg	<3.2	10.6	04/22/19 14:59	
Benzo(a)pyrene	ug/kg	<2.5	8.4	04/22/19 14:59	
Benzo(b)fluoranthene	ug/kg	<2.8	9.4	04/22/19 14:59	
Benzo(g,h,i)perylene	ug/kg	<2.0	6.8	04/22/19 14:59	
Benzo(k)fluoranthene	ug/kg	<2.5	8.4	04/22/19 14:59	
Chrysene	ug/kg	<3.4	11.2	04/22/19 14:59	
Dibenz(a,h)anthracene	ug/kg	<2.2	7.5	04/22/19 14:59	
Fluoranthene	ug/kg	<5.2	17.4	04/22/19 14:59	
Fluorene	ug/kg	<4.1	13.8	04/22/19 14:59	
Indeno(1,2,3-cd)pyrene	ug/kg	<2.2	7.3	04/22/19 14:59	
Naphthalene	ug/kg	<8.4	28.1	04/22/19 14:59	
Phenanthrene	ug/kg	<11.7	38.9	04/22/19 14:59	
Pyrene	ug/kg	<4.5	15.0	04/22/19 14:59	
2-Fluorobiphenyl (S)	%	69	28-99	04/22/19 14:59	
Terphenyl-d14 (S)	%	65	10-107	04/22/19 14:59	

LABORATORY CONTROL SAMPLI	E: 1854301					
		Spike	LCS	LCS	% Rec	
Parameter	Units	Conc.	Result	% Rec	Limits	Qualifiers
1-Methylnaphthalene	ug/kg	333	204	61	47-104	
2-Methylnaphthalene	ug/kg	333	216	65	50-100	
Acenaphthene	ug/kg	333	225	67	56-113	
Acenaphthylene	ug/kg	333	228	68	55-113	
Anthracene	ug/kg	333	248	74	59-103	
Benzo(a)anthracene	ug/kg	333	236	71	55-102	
Benzo(a)pyrene	ug/kg	333	257	77	59-114	
Benzo(b)fluoranthene	ug/kg	333	251	75	53-124	
Benzo(g,h,i)perylene	ug/kg	333	296	89	48-114	
Benzo(k)fluoranthene	ug/kg	333	237	71	61-118	
Chrysene	ug/kg	333	239	72	62-108	
Dibenz(a,h)anthracene	ug/kg	333	277	83	51-114	
Fluoranthene	ug/kg	333	245	73	59-113	
Fluorene	ug/kg	333	234	70	56-117	
Indeno(1,2,3-cd)pyrene	ug/kg	333	283	85	52-115	
Naphthalene	ug/kg	333	225	67	54-95	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.



Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

LABORATORY CONTROL SAMPLE: 1854301

LABORATORY CONTROL SAMPLE.	1004301	Spike	LCS	LCS	% Rec	
Parameter	Units	Conc.	Result	% Rec	Limits	Qualifiers
Phenanthrene	ug/kg	333	247	74	58-101	
Pyrene	ug/kg	333	243	73	56-105	
2-Fluorobiphenyl (S)	%			63	28-99	
Terphenyl-d14 (S)	%			63	10-107	

MATRIX SPIKE & MATRIX SPIKE	DUPLICA	TE: 185430	02		1854303							
			MS	MSD								
	4	0186050008	Spike	Spike	MS	MSD	MS	MSD	% Rec		Max	
Parameter	Units	Result	Conc.	Conc.	Result	Result	% Rec	% Rec	Limits	RPD	RPD	Qual
1-Methylnaphthalene	ug/kg	11.5J	430	432	289	332	64	74	39-104	14	29	
2-Methylnaphthalene	ug/kg	14.5J	430	432	279	350	62	78	40-100	22	32	
Acenaphthene	ug/kg	<5.0	430	432	283	322	66	75	50-113	13	21	
Acenaphthylene	ug/kg	<4.3	430	432	291	324	67	75	42-114	11	27	
Anthracene	ug/kg	<7.4	430	432	280	318	64	73	33-105	13	21	
Benzo(a)anthracene	ug/kg	<4.1	430	432	285	315	66	73	43-102	10	21	
Benzo(a)pyrene	ug/kg	3.3J	430	432	302	337	69	77	34-117	11	22	
Benzo(b)fluoranthene	ug/kg	3.9J	430	432	314	335	72	77	35-124	6	35	
Benzo(g,h,i)perylene	ug/kg	9.5	430	432	279	308	63	69	10-120	10	30	
Benzo(k)fluoranthene	ug/kg	<3.2	430	432	278	319	64	74	31-128	14	27	
Chrysene	ug/kg	8.9J	430	432	286	321	64	72	39-108	12	20	
Dibenz(a,h)anthracene	ug/kg	<2.9	430	432	292	327	67	75	19-114	11	28	
Fluoranthene	ug/kg	<6.7	430	432	296	327	68	75	45-113	10	22	
Fluorene	ug/kg	<5.4	430	432	299	331	69	76	48-117	10	21	
Indeno(1,2,3-cd)pyrene	ug/kg	4.1J	430	432	289	322	66	74	10-123	11	28	
Naphthalene	ug/kg	15.2J	430	432	263	321	58	71	32-101	20	27	
Phenanthrene	ug/kg	19.4J	430	432	303	340	66	74	40-101	11	20	
Pyrene	ug/kg	<5.8	430	432	302	329	69	75	35-105	8	26	
2-Fluorobiphenyl (S)	%						61	69	28-99			
Terphenyl-d14 (S)	%						58	63	10-107			

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.



Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

QC Batch: 319182 Analysis Method: EPA 8270 by SIM

QC Batch Method: EPA 3546 Analysis Description: 8270/3546 MSSV PAH by SIM

Associated Lab Samples: 40185945002, 40185945006, 40185945008, 40185945010

METHOD BLANK: 1854705 Matrix: Solid

Associated Lab Samples: 40185945002, 40185945006, 40185945008, 40185945010

Davastas	l la ta	Blank	Reporting	A se a luma d	O I::::
Parameter	Units	Result	Limit	Analyzed	Qualifiers
1-Methylnaphthalene	ug/kg	<4.0	13.4	04/23/19 11:37	
2-Methylnaphthalene	ug/kg	<5.0	16.7	04/23/19 11:37	
Acenaphthene	ug/kg	<3.9	12.9	04/23/19 11:37	
Acenaphthylene	ug/kg	<3.3	11.0	04/23/19 11:37	
Anthracene	ug/kg	<5.7	19.0	04/23/19 11:37	
Benzo(a)anthracene	ug/kg	<3.2	10.6	04/23/19 11:37	
Benzo(a)pyrene	ug/kg	<2.5	8.4	04/23/19 11:37	
Benzo(b)fluoranthene	ug/kg	<2.8	9.4	04/23/19 11:37	
Benzo(g,h,i)perylene	ug/kg	<2.0	6.8	04/23/19 11:37	
Benzo(k)fluoranthene	ug/kg	<2.5	8.4	04/23/19 11:37	
Chrysene	ug/kg	<3.4	11.2	04/23/19 11:37	
Dibenz(a,h)anthracene	ug/kg	<2.2	7.5	04/23/19 11:37	
Fluoranthene	ug/kg	<5.2	17.4	04/23/19 11:37	
Fluorene	ug/kg	<4.1	13.8	04/23/19 11:37	
Indeno(1,2,3-cd)pyrene	ug/kg	<2.2	7.3	04/23/19 11:37	
Naphthalene	ug/kg	<8.4	28.1	04/23/19 11:37	
Phenanthrene	ug/kg	<11.7	38.8	04/23/19 11:37	
Pyrene	ug/kg	<4.5	15.0	04/23/19 11:37	
2-Fluorobiphenyl (S)	%	62	28-99	04/23/19 11:37	
Terphenyl-d14 (S)	%	64	10-107	04/23/19 11:37	

LABORATORY CONTROL SAMPLE:	1854706					
		Spike	LCS	LCS	% Rec	
Parameter	Units	Conc.	Result	% Rec	Limits	Qualifiers
1-Methylnaphthalene	ug/kg	333	181	54	47-104	_
2-Methylnaphthalene	ug/kg	333	174	52	50-100	
Acenaphthene	ug/kg	333	221	66	56-113	
Acenaphthylene	ug/kg	333	205	61	55-113	
Anthracene	ug/kg	333	264	79	59-103	
Benzo(a)anthracene	ug/kg	333	215	65	55-102	
Benzo(a)pyrene	ug/kg	333	267	80	59-114	
Benzo(b)fluoranthene	ug/kg	333	228	68	53-124	
Benzo(g,h,i)perylene	ug/kg	333	224	67	48-114	
Benzo(k)fluoranthene	ug/kg	333	298	90	61-118	
Chrysene	ug/kg	333	272	82	62-108	
Dibenz(a,h)anthracene	ug/kg	333	234	70	51-114	
Fluoranthene	ug/kg	333	268	81	59-113	
Fluorene	ug/kg	333	226	68	56-117	
Indeno(1,2,3-cd)pyrene	ug/kg	333	228	69	52-115	
Naphthalene	ug/kg	333	200	60	54-95	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.



Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

 LABORATORY CONTROL SAMPLE:
 1854706
 Spike
 LCS
 LCS
 % Rec
 Limits
 Qualifiers

 Phenanthrene
 ug/kg
 333
 228
 68
 58-101

 Phyropo
 ug/kg
 333
 240
 75
 56 105

Phenanthrene	ug/kg	333	228	68	58-101	
Pyrene	ug/kg	333	249	75	56-105	
2-Fluorobiphenyl (S)	%			55	28-99	
Terphenyl-d14 (S)	%			60	10-107	

MATRIX SPIKE & MATRIX SI	PIKE DUPLICA	TE: 18547	07		1854708							
			MS	MSD								
	4	0186129002	Spike	Spike	MS	MSD	MS	MSD	% Rec		Max	
Parameter	Units	Result	Conc.	Conc.	Result	Result	% Rec	% Rec	Limits	RPD	RPD	Qual
1-Methylnaphthalene	ug/kg	<4.8	403	401	223	214	56	53	39-104	5	29	
2-Methylnaphthalene	ug/kg	<6.0	403	401	212	216	53	54	40-100	2	32	
Acenaphthene	ug/kg	<4.7	403	401	278	258	69	64	50-113	7	21	
Acenaphthylene	ug/kg	<4.0	403	401	259	241	64	60	42-114	7	27	
Anthracene	ug/kg	<6.9	403	401	243	292	60	73	33-105	18	21	
Benzo(a)anthracene	ug/kg	<3.8	403	401	267	239	66	59	43-102	11	21	
Benzo(a)pyrene	ug/kg	<3.0	403	401	328	260	82	65	34-117	23	22	R1
Benzo(b)fluoranthene	ug/kg	<3.4	403	401	304	258	75	64	35-124	16	35	
Benzo(g,h,i)perylene	ug/kg	<2.4	403	401	262	227	65	57	10-120	14	30	
Benzo(k)fluoranthene	ug/kg	<3.0	403	401	356	320	89	80	31-128	11	27	
Chrysene	ug/kg	<4.1	403	401	343	309	85	77	39-108	10	20	
Dibenz(a,h)anthracene	ug/kg	<2.7	403	401	254	213	63	53	19-114	18	28	
Fluoranthene	ug/kg	<6.3	403	401	341	301	85	75	45-113	12	22	
Fluorene	ug/kg	<5.0	403	401	286	260	71	65	48-117	9	21	
Indeno(1,2,3-cd)pyrene	ug/kg	<2.7	403	401	266	222	66	55	10-123	18	28	
Naphthalene	ug/kg	<10.2	403	401	250	250	62	62	32-101	0	27	
Phenanthrene	ug/kg	<14.0	403	401	287	255	71	64	40-101	12	20	
Pyrene	ug/kg	<5.4	403	401	305	277	76	69	35-105	10	26	
2-Fluorobiphenyl (S)	%						53	55	28-99			
Terphenyl-d14 (S)	%						59	55	10-107			

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.



Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

QC Batch: 319423 Analysis Method: EPA 8270 by SIM

QC Batch Method: EPA 3546 Analysis Description: 8270/3546 MSSV PAH by SIM

Associated Lab Samples: 40185945004

METHOD BLANK: 1856067 Matrix: Solid

Associated Lab Samples: 40185945004

		Blank	Reporting		
Parameter	Units	Result	Limit	Analyzed	Qualifiers
1-Methylnaphthalene	ug/kg	<4.0	13.4	04/25/19 12:42	
2-Methylnaphthalene	ug/kg	<5.0	16.7	04/25/19 12:42	
Acenaphthene	ug/kg	<3.9	12.9	04/25/19 12:42	
Acenaphthylene	ug/kg	<3.3	11.0	04/25/19 12:42	
Anthracene	ug/kg	<5.7	19.0	04/25/19 12:42	
Benzo(a)anthracene	ug/kg	<3.2	10.6	04/25/19 12:42	
Benzo(a)pyrene	ug/kg	<2.5	8.4	04/25/19 12:42	
Benzo(b)fluoranthene	ug/kg	<2.8	9.4	04/25/19 12:42	
Benzo(g,h,i)perylene	ug/kg	<2.0	6.8	04/25/19 12:42	
Benzo(k)fluoranthene	ug/kg	<2.5	8.4	04/25/19 12:42	
Chrysene	ug/kg	<3.4	11.2	04/25/19 12:42	
Dibenz(a,h)anthracene	ug/kg	<2.2	7.4	04/25/19 12:42	
Fluoranthene	ug/kg	<5.2	17.4	04/25/19 12:42	
Fluorene	ug/kg	<4.1	13.8	04/25/19 12:42	
Indeno(1,2,3-cd)pyrene	ug/kg	<2.2	7.3	04/25/19 12:42	
Naphthalene	ug/kg	<8.4	28.1	04/25/19 12:42	
Phenanthrene	ug/kg	<11.6	38.8	04/25/19 12:42	
Pyrene	ug/kg	<4.5	15.0	04/25/19 12:42	
2-Fluorobiphenyl (S)	%	70	28-99	04/25/19 12:42	
Terphenyl-d14 (S)	%	66	10-107	04/25/19 12:42	

LABORATORY CONTROL SAMPLE	: 1856068					
		Spike	LCS	LCS	% Rec	
Parameter	Units	Conc.	Result	% Rec	Limits	Qualifiers
1-Methylnaphthalene	ug/kg	333	256	77	47-104	
2-Methylnaphthalene	ug/kg	333	260	78	50-100	
Acenaphthene	ug/kg	333	265	79	56-113	
Acenaphthylene	ug/kg	333	267	80	55-113	
Anthracene	ug/kg	333	281	84	59-103	
Benzo(a)anthracene	ug/kg	333	262	79	55-102	
Benzo(a)pyrene	ug/kg	333	285	85	59-114	
Benzo(b)fluoranthene	ug/kg	333	276	83	53-124	
Benzo(g,h,i)perylene	ug/kg	333	324	97	48-114	
Benzo(k)fluoranthene	ug/kg	333	266	80	61-118	
Chrysene	ug/kg	333	264	79	62-108	
Dibenz(a,h)anthracene	ug/kg	333	307	92	51-114	
Fluoranthene	ug/kg	333	268	81	59-113	
Fluorene	ug/kg	333	270	81	56-117	
ndeno(1,2,3-cd)pyrene	ug/kg	333	312	94	52-115	
Naphthalene	ug/kg	333	265	80	54-95	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.



67

10-107

Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Terphenyl-d14 (S)

Date: 05/01/2019 01:13 PM

LABORATORY CONTROL SAMPLE: 1856068 Spike LCS LCS % Rec Parameter Units Conc. Result % Rec Limits Qualifiers 276 58-101 Phenanthrene ug/kg 333 83 80 56-105 Pyrene ug/kg 333 267 2-Fluorobiphenyl (S) % 80 28-99

%

MATRIX SPIKE & MATRIX SI	PIKE DUPLICA	TE: 18560	69		1856070							
			MS	MSD								
	4	0185998013	Spike	Spike	MS	MSD	MS	MSD	% Rec		Max	
Parameter	Units	Result	Conc.	Conc.	Result	Result	% Rec	% Rec	Limits	RPD	RPD	Qual
1-Methylnaphthalene	ug/kg	<4.9	406	406	280	311	69	76	39-104	10	29	
2-Methylnaphthalene	ug/kg	<6.1	406	406	290	315	71	77	40-100	8	32	
Acenaphthene	ug/kg	<4.7	406	406	280	309	69	76	50-113	10	21	
Acenaphthylene	ug/kg	<4.0	406	406	284	302	70	74	42-114	6	27	
Anthracene	ug/kg	<7.0	406	406	292	307	71	75	33-105	5	21	
Benzo(a)anthracene	ug/kg	6.1J	406	406	274	299	66	72	43-102	9	21	
Benzo(a)pyrene	ug/kg	6.9J	406	406	293	315	70	76	34-117	7	22	
Benzo(b)fluoranthene	ug/kg	6.1J	406	406	303	326	73	79	35-124	7	35	
Benzo(g,h,i)perylene	ug/kg	5.6J	406	406	299	324	72	78	10-120	8	30	
Benzo(k)fluoranthene	ug/kg	7.2J	406	406	265	295	63	71	31-128	11	27	
Chrysene	ug/kg	8.9J	406	406	285	306	68	73	39-108	7	20	
Dibenz(a,h)anthracene	ug/kg	<2.7	406	406	297	332	73	81	19-114	11	28	
Fluoranthene	ug/kg	14.1J	406	406	289	324	68	76	45-113	11	22	
Fluorene	ug/kg	<5.0	406	406	286	309	70	76	48-117	7	21	
Indeno(1,2,3-cd)pyrene	ug/kg	4.3J	406	406	298	331	72	80	10-123	11	28	
Naphthalene	ug/kg	<10.3	406	406	279	305	68	74	32-101	9	27	
Phenanthrene	ug/kg	<14.2	406	406	292	310	69	74	40-101	6	20	
Pyrene	ug/kg	12.5J	406	406	273	289	64	68	35-105	5	26	
2-Fluorobiphenyl (S)	%						61	60	28-99			
Terphenyl-d14 (S)	%						49	51	10-107			

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.



Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

QC Batch: 319857 Analysis Method: EPA 8270 by SIM

QC Batch Method: EPA 3546 Analysis Description: 8270/3546 MSSV PAH by SIM

Associated Lab Samples: 40185945005

METHOD BLANK: 1858437 Matrix: Solid

Associated Lab Samples: 40185945005

		Blank	Reporting		
Parameter	Units	Result	Limit	Analyzed	Qualifiers
1-Methylnaphthalene	ug/kg	<4.0	13.4	04/30/19 15:04	
2-Methylnaphthalene	ug/kg	<5.0	16.7	04/30/19 15:04	
Acenaphthene	ug/kg	<3.9	12.9	04/30/19 15:04	
Acenaphthylene	ug/kg	<3.3	11.0	04/30/19 15:04	
Anthracene	ug/kg	<5.7	19.0	04/30/19 15:04	
Benzo(a)anthracene	ug/kg	<3.2	10.6	04/30/19 15:04	
Benzo(a)pyrene	ug/kg	<2.5	8.4	04/30/19 15:04	
Benzo(b)fluoranthene	ug/kg	<2.8	9.4	04/30/19 15:04	
Benzo(g,h,i)perylene	ug/kg	<2.0	6.8	04/30/19 15:04	
Benzo(k)fluoranthene	ug/kg	<2.5	8.4	04/30/19 15:04	
Chrysene	ug/kg	<3.4	11.2	04/30/19 15:04	
Dibenz(a,h)anthracene	ug/kg	<2.2	7.4	04/30/19 15:04	
Fluoranthene	ug/kg	<5.2	17.4	04/30/19 15:04	
Fluorene	ug/kg	<4.1	13.8	04/30/19 15:04	
Indeno(1,2,3-cd)pyrene	ug/kg	<2.2	7.3	04/30/19 15:04	
Naphthalene	ug/kg	<8.4	28.1	04/30/19 15:04	
Phenanthrene	ug/kg	<11.6	38.8	04/30/19 15:04	
Pyrene	ug/kg	<4.5	15.0	04/30/19 15:04	
2-Fluorobiphenyl (S)	%	57	28-99	04/30/19 15:04	
Terphenyl-d14 (S)	%	60	10-107	04/30/19 15:04	

LABORATORY CONTROL SAMPLE:	1858438					
		Spike	LCS	LCS	% Rec	
Parameter	Units	Conc.	Result	% Rec	Limits	Qualifiers
1-Methylnaphthalene	ug/kg	333	259	78	47-104	
2-Methylnaphthalene	ug/kg	333	261	78	50-100	
Acenaphthene	ug/kg	333	225	68	56-113	
Acenaphthylene	ug/kg	333	226	68	55-113	
Anthracene	ug/kg	333	231	69	59-103	
Benzo(a)anthracene	ug/kg	333	223	67	55-102	
Benzo(a)pyrene	ug/kg	333	246	74	59-114	
Benzo(b)fluoranthene	ug/kg	333	220	66	53-124	
Benzo(g,h,i)perylene	ug/kg	333	285	86	48-114	
Benzo(k)fluoranthene	ug/kg	333	260	78	61-118	
Chrysene	ug/kg	333	236	71	62-108	
Dibenz(a,h)anthracene	ug/kg	333	274	82	51-114	
Fluoranthene	ug/kg	333	228	69	59-113	
Fluorene	ug/kg	333	227	68	56-117	
Indeno(1,2,3-cd)pyrene	ug/kg	333	279	84	52-115	
Naphthalene	ug/kg	333	229	69	54-95	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.



Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

LABORATORY CONTROL SAMPLE: 1858438

LABORATORY CONTROL SAMPLE:	1858438	Spike	LCS	LCS	% Rec	
Parameter	Units	Conc.	Result	% Rec	Limits	Qualifiers
Phenanthrene	ug/kg	333	227	68	58-101	
Pyrene	ug/kg	333	234	70	56-105	
2-Fluorobiphenyl (S)	%			66	28-99	
Terphenyl-d14 (S)	%			59	10-107	

MATRIX SPIKE & MATRIX S	PIKE DUPLICA	TE: 18584	39		1858440							
			MS	MSD								
	4	0186295009	Spike	Spike	MS	MSD	MS	MSD	% Rec		Max	
Parameter	Units	Result	Conc.	Conc.	Result	Result	% Rec	% Rec	Limits	RPD	RPD	Qual
1-Methylnaphthalene	ug/kg	<4.0	333	333	182	198	55	59	39-104	8	29	
2-Methylnaphthalene	ug/kg	<5.0	333	333	187	204	56	61	40-100	9	32	
Acenaphthene	ug/kg	<3.9	333	333	177	192	53	58	50-113	8	21	
Acenaphthylene	ug/kg	<3.3	333	333	177	193	53	58	42-114	9	27	
Anthracene	ug/kg	<5.7	333	333	193	203	58	61	33-105	5	21	
Benzo(a)anthracene	ug/kg	<3.2	333	333	190	198	57	59	43-102	4	21	
Benzo(a)pyrene	ug/kg	<2.5	333	333	205	211	61	63	34-117	3	22	
Benzo(b)fluoranthene	ug/kg	<2.8	333	333	204	201	61	60	35-124	1	35	
Benzo(g,h,i)perylene	ug/kg	<2.0	333	333	230	234	69	70	10-120	2	30	
Benzo(k)fluoranthene	ug/kg	<2.5	333	333	187	203	56	61	31-128	8	27	
Chrysene	ug/kg	<3.4	333	333	200	206	60	62	39-108	3	20	
Dibenz(a,h)anthracene	ug/kg	<2.2	333	333	221	229	66	69	19-114	4	28	
Fluoranthene	ug/kg	<5.2	333	333	192	201	58	60	45-113	5	22	
Fluorene	ug/kg	<4.1	333	333	184	198	55	59	48-117	7	21	
Indeno(1,2,3-cd)pyrene	ug/kg	<2.2	333	333	223	229	67	69	10-123	3	28	
Naphthalene	ug/kg	<8.4	333	333	164	181	49	54	32-101	10	27	
Phenanthrene	ug/kg	<11.6	333	333	190	199	57	60	40-101	4	20	
Pyrene	ug/kg	<4.5	333	333	193	201	58	60	35-105	4	26	
2-Fluorobiphenyl (S)	%						49	53	28-99			
Terphenyl-d14 (S)	%						47	50	10-107			

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.



QUALITY CONTROL DATA

Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

QC Batch: 319194 Analysis Method: ASTM D2974-87

QC Batch Method: ASTM D2974-87 Analysis Description: Dry Weight/Percent Moisture

Associated Lab Samples: 40185945001, 40185945003, 40185945005, 40185945007, 40185945009, 40185945010, 40185945011,

40185945012, 40185945013

SAMPLE DUPLICATE: 1854741

Date: 05/01/2019 01:13 PM

		40185944001	Dup		Max	
Parameter	Units	Result	Result	RPD	RPD	Qualifiers
Percent Moisture	%	13.8	13.5	2	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.



QUALITY CONTROL DATA

Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

QC Batch: 319403 Analysis Method: ASTM D2974-87

QC Batch Method: ASTM D2974-87 Analysis Description: Dry Weight/Percent Moisture

Associated Lab Samples: 40185945002, 40185945004, 40185945006, 40185945008

SAMPLE DUPLICATE: 1856004

Date: 05/01/2019 01:13 PM

ParameterUnits40186323001 ResultDup ResultMax ResultMax RPDQualifiersPercent Moisture%5.65.5110

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.



QUALIFIERS

Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.

ND - Not Detected at or above LOD.

J - Estimated concentration at or above the LOD and below the LOQ.

LOD - Limit of Detection adjusted for dilution factor, percent moisture, initial weight and final volume.

LOQ - Limit of Quantitation adjusted for dilution factor, percent moisture, initial weight and final volume.

S - Surrogate

1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.

Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.

LCS(D) - Laboratory Control Sample (Duplicate)

MS(D) - Matrix Spike (Duplicate)

DUP - Sample Duplicate

RPD - Relative Percent Difference

NC - Not Calculable.

SG - Silica Gel - Clean-Up

U - Indicates the compound was analyzed for, but not detected at or above the adjusted LOD.

N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.

Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.

TNI - The NELAC Institute.

WORKORDER QUALIFIERS

WO: 40185945

[1] Revised - PM - PAH was missed at login for sample -005. Sample analysis added and revised report generated. SVM

ANALYTE QUALIFIERS

Date: 05/01/2019 01:13 PM

B Analyte was detected in the associated method blank.

M0 Matrix spike recovery and/or matrix spike duplicate recovery was outside laboratory control limits.

R1 RPD value was outside control limits.

W Non-detect results are reported on a wet weight basis.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

40185945009 B-5 (1-2.5') EPA 3050 318766 EPA 6010 40185945010 B-5 (4-5') EPA 3050 319136 EPA 6010 40185945011 B-6 (1-2') EPA 3050 318766 EPA 6010 40185945012 B-7 (1-2.5') EPA 3050 318766 EPA 6010 40185945013 B-8 (1-2.5') EPA 3050 318766 EPA 6010 40185945009 B-5 (1-2.5') EPA 3050 318766 EPA 6010 40185945010 B-5 (4-5') EPA 7471 319053 EPA 7471 40185945011 B-6 (1-2') EPA 7471 319053 EPA 7471 40185945013 B-7 (1-2.5') EPA 7471 319053 EPA 7471 40185945013 B-8 (1-2.5') EPA 7471 319053 EPA 7471 40185945013 B-8 (1-2.5') EPA 7471 319053 EPA 7471 40185945001 B-1 (1-2') EPA 3546 319038 EPA 8270 by SIM 40185945002 B-1 (4-5') EPA 3546 319038 EPA 8270 by SIM 40185945003	318862 319236 318862 318862 318862 319125 319125 319125 319125 319119 319217
### ### ### ### ### ### ### ### ### ##	318862 318862 318862 319125 319337 319125 319125 319125 319119 319217
### ### ##############################	318862 318862 319125 319337 319125 319125 319125 319119 319217
### ##################################	319337 319125 319125 319125 319119 319217
### Back (1-2')	319125 319125 319125 319119 319217
B-7 (1-2.5')	319125 319125 319119 319217
### ### ##############################	319217
#40185945003 B-2 (1-2') EPA 3546 319038 EPA 8270 by SIM 40185945004 B-2 (4-5') EPA 3546 319423 EPA 8270 by SIM 40185945005 B-3 (1-2') EPA 3546 319857 EPA 8270 by SIM 40185945006 B-3 (4-5') EPA 3546 319182 EPA 8270 by SIM 40185945007 B-4 (1-2') EPA 3546 319038 EPA 8270 by SIM 40185945008 B-4 (4-5') EPA 3546 319182 EPA 8270 by SIM 40185945009 B-5 (1-2.5') EPA 3546 319038 EPA 8270 by SIM 40185945010 B-5 (4-5') EPA 3546 319182 EPA 8270 by SIM 40185945010 B-6 (1-2') EPA 3546 319038 EPA 8270 by SIM 40185945011 B-6 (1-2') EPA 3546 319038 EPA 8270 by SIM 40185945012 B-7 (1-2.5') EPA 3546 319038 EPA 8270 by SIM 40185945013 B-8 (1-2.5') EPA 3546 319038 EPA 8270 by SIM 40185945013 B-8 (1-2.5') EPA 3546 319038 EPA 8270 by SIM 40185945013 B-8 (1-2.5') EPA 3546 319038 EPA 8270 by SIM	
#0185945004 B-2 (4-5') EPA 3546 319423 EPA 8270 by SIM 40185945005 B-3 (1-2') EPA 3546 319857 EPA 8270 by SIM 40185945006 B-3 (4-5') EPA 3546 319182 EPA 8270 by SIM 40185945007 B-4 (1-2') EPA 3546 319038 EPA 8270 by SIM 40185945008 B-4 (4-5') EPA 3546 319182 EPA 8270 by SIM 40185945009 B-5 (1-2.5') EPA 3546 319038 EPA 8270 by SIM 40185945010 B-5 (4-5') EPA 3546 319182 EPA 8270 by SIM 40185945010 B-6 (1-2') EPA 3546 319038 EPA 8270 by SIM 40185945011 B-6 (1-2') EPA 3546 319038 EPA 8270 by SIM 40185945012 B-7 (1-2.5') EPA 3546 319038 EPA 8270 by SIM 40185945013 B-8 (1-2.5') EPA 3546 319038 EPA 8270 by SIM 40185945013 B-8 (1-2.5') EPA 3546 319038 EPA 8270 by SIM 40185945013 B-8 (1-2.5') EPA 3546 319038 EPA 8270 by SIM 40185945013 B-8 (1-2.5') EPA 3546 319038 EPA 8270 by SIM 40185945013 B-8 (1-2.5') EPA 3546 319038 EPA 8270 by SIM	240440
#0185945005 B-3 (1-2') EPA 3546 319857 EPA 8270 by SIM 40185945006 B-3 (4-5') EPA 3546 319182 EPA 8270 by SIM 40185945007 B-4 (1-2') EPA 3546 319038 EPA 8270 by SIM 40185945008 B-4 (4-5') EPA 3546 319182 EPA 8270 by SIM 40185945009 B-5 (1-2.5') EPA 3546 319038 EPA 8270 by SIM 40185945010 B-5 (4-5') EPA 3546 319182 EPA 8270 by SIM 40185945011 B-6 (1-2') EPA 3546 319038 EPA 8270 by SIM 40185945012 B-7 (1-2.5') EPA 3546 319038 EPA 8270 by SIM 40185945013 B-8 (1-2.5') EPA 3546 319038 EPA 8270 by SIM 40185945013 B-8 (1-2.5') EPA 3546 319038 EPA 8270 by SIM 40185945013 B-8 (1-2.5') EPA 3546 319038 EPA 8270 by SIM 40185945013 B-8 (1-2.5') EPA 3546 319038 EPA 8270 by SIM 40185945013 B-8 (1-2.5') EPA 3546 319038 EPA 8270 by SIM	319119
#0185945006 B-3 (4-5') EPA 3546 319182 EPA 8270 by SIM #0185945007 B-4 (1-2') EPA 3546 319038 EPA 8270 by SIM #0185945008 B-4 (4-5') EPA 3546 319182 EPA 8270 by SIM #0185945009 B-5 (1-2.5') EPA 3546 319038 EPA 8270 by SIM #0185945010 B-5 (4-5') EPA 3546 319182 EPA 8270 by SIM #0185945011 B-6 (1-2') EPA 3546 319038 EPA 8270 by SIM #0185945012 B-7 (1-2.5') EPA 3546 319038 EPA 8270 by SIM #0185945013 B-8 (1-2.5') EPA 3546 319038 EPA 8270 by SIM #0185945013 B-8 (1-2.5') EPA 3546 319038 EPA 8270 by SIM #0185945013 B-8 (1-2.5') EPA 3546 319038 EPA 8270 by SIM #0185945013 B-8 (1-2.5') EPA 3546 319038 EPA 8270 by SIM #0185945013 B-8 (1-2.5')	319479
B-4 (1-2') EPA 3546 319038 EPA 8270 by SIM	319926
8-4 (4-5') EPA 3546 319182 EPA 8270 by SIM 90185945009 B-5 (1-2.5') EPA 3546 319038 EPA 8270 by SIM 90185945010 B-5 (4-5') EPA 3546 319182 EPA 8270 by SIM 90185945011 B-6 (1-2') EPA 3546 319038 EPA 8270 by SIM 90185945012 B-7 (1-2.5') EPA 3546 319038 EPA 8270 by SIM 90185945013 B-8 (1-2.5') EPA 3546 319038 EPA 8270 by SIM	319217
0185945009 B-5 (1-2.5') EPA 3546 319038 EPA 8270 by SIM 0185945010 B-5 (4-5') EPA 3546 319182 EPA 8270 by SIM 0185945011 B-6 (1-2') EPA 3546 319038 EPA 8270 by SIM 0185945012 B-7 (1-2.5') EPA 3546 319038 EPA 8270 by SIM 0185945013 B-8 (1-2.5') EPA 3546 319038 EPA 8270 by SIM	319119
0185945010 B-5 (4-5') EPA 3546 319182 EPA 8270 by SIM 0185945011 B-6 (1-2') EPA 3546 319038 EPA 8270 by SIM 0185945012 B-7 (1-2.5') EPA 3546 319038 EPA 8270 by SIM 0185945013 B-8 (1-2.5') EPA 3546 319038 EPA 8270 by SIM	319217
0185945011 B-6 (1-2') EPA 3546 319038 EPA 8270 by SIM 0185945012 B-7 (1-2.5') EPA 3546 319038 EPA 8270 by SIM 0185945013 B-8 (1-2.5') EPA 3546 319038 EPA 8270 by SIM	319119
0185945012 B-7 (1-2.5') EPA 3546 319038 EPA 8270 by SIM 0185945013 B-8 (1-2.5') EPA 3546 319038 EPA 8270 by SIM	319217
B-1 (1-2') EPA 5035/5030B 318800 EPA 8260	319119 319119 319119
	318802
D185945002 B-1 (4-5') EPA 5035/5030B 319216 EPA 8260	319219
D185945003 B-2 (1-2') EPA 5035/5030B 318800 EPA 8260	318802
B-2 (4-5') EPA 5035/5030B 319216 EPA 8260	319219
B-3 (1-2') EPA 5035/5030B 318800 EPA 8260	318802
B-3 (4-5') EPA 5035/5030B 319216 EPA 8260	319219
B-4 (1-2') EPA 5035/5030B 318800 EPA 8260	318802
D185945008 B-4 (4-5') EPA 5035/5030B 319216 EPA 8260	319219
D185945009 B-5 (1-2.5') EPA 5035/5030B 318800 EPA 8260	318802
B-5 (4-5') EPA 5035/5030B 319216 EPA 8260	319219
40185945011 B-6 (1-2') EPA 5035/5030B 318800 EPA 8260 40185945012 B-7 (1-2.5') EPA 5035/5030B 318800 EPA 8260	= .0= .0

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full, without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: 1690012791 HARTMEYER

Pace Project No.: 40185945

Date: 05/01/2019 01:13 PM

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytica Batch
40185945013 40185945014	B-8 (1-2.5') TRIP BLANK	EPA 5035/5030B EPA 5035/5030B	318800 318800	EPA 8260 EPA 8260	318802 318802
40185945001	B-1 (1-2')	ASTM D2974-87	319194	2.710200	010002
40185945002	B-1 (4-5')	ASTM D2974-87	319403		
40185945003	B-2 (1-2')	ASTM D2974-87	319194		
40185945004	B-2 (4-5')	ASTM D2974-87	319403		
40185945005	B-3 (1-2')	ASTM D2974-87	319194		
0185945006	B-3 (4-5')	ASTM D2974-87	319403		
0185945007	B-4 (1-2')	ASTM D2974-87	319194		
10185945008	B-4 (4-5')	ASTM D2974-87	319403		
10185945009	B-5 (1-2.5')	ASTM D2974-87	319194		
10185945010	B-5 (4-5')	ASTM D2974-87	319194		
0185945011	B-6 (1-2')	ASTM D2974-87	319194		
40185945012	B-7 (1-2.5')	ASTM D2974-87	319194		
40185945013	B-8 (1-2.5')	ASTM D2974-87	319194		

1			MN: 612-607-1700 WI	WI: 920-469-2436	i .
Company Name: Ramboll		Supply the			1
Branch/Location: Branch/eld, US		MACE AN IDJULICAN) ()		() () () () () () () () () ()
Project Contact: Adam Straiffer		FEFFER DOCCOMINGNOS WATER	X T	Quote #:	
Phone: (אבא) אכו-350%		CHAIN OF CUSTO		Mail To Contact:	MENDALENCE OF THE STATE OF THE
Project Number: 1690013791	A≃None B≍l	*Preservation Codes SO4 D=HNO3 E=DI Water	nol G=NaOH	Mail To Company:	
Project Name:	H=Sodium Bisulfate Solution	fate Solution =Sodium Thiosulfate J=Other		Mail To Address:	
Project State:	FILTERED? (YES/NO)	ZZZ			THE REAL PROPERTY OF THE PROPE
Sampled By (Print): Tuples Burget	PRESERVATION (CODE)*	Pick A A A		Invoice To Contact:	
Sampled By (Sign): Tuley Swallet			action and a second	Invoice To Company:	
a		ests		Invoice To Address:	
Data Package Options MS/MSD M	Matrix Codes				
On your sample	W = Water DW = Drinking Water	\$ \$		Invoice To Phone:	
	SW = Surface Water WW = Waste Water WP = Wipe	YAM CRA		CLIENT	LAB COMMENTS Profile #
PACE LAB # CLIENT FIELD ID DATE	COLLECTION MATRIX TE TIME	6		COMMENTS	(Lab Use Only)
DD 3-1 (1-2)	3 CM 3 S	X X			
002 8-1 (2-5)	5580	X		Evato	
003 8-2 (1-21)	5/80	× ×			
004 8-2 (4-5)	0815	\ \ \		HOLD	
ODS 3-3 (1-2')	0 855	\ \			
006 3-3 (4-5)	25%0	× ×		IOO	
007 3-4 (1-21)	0910	X X			A CONTRACTOR OF THE CONTRACTOR
008 3-4 (4-5)	0910	×		HOU	
(,s.t-1) s-8 b00	G ₁ 38	X X X			
010 8-5 (4-5)	0928	Х Х Х		106	
011 8-6 (1-21)	g 8	メメ			
012 8-7 (1-2.5)	5	\ \ \			
V13 13-8 (1-2.5')	GP40 de	X X X			
Rush Turnaround Time Requested - Prelims Rush TAT subject to approval/surcharge)	2	Date/Time: 1300	Received By:	Date/Time:	10192010
	Relinquished By:	7 2/17/0 09%	Received By:	(a) Date/Time:	
Email #1: Re	Relinquished By:	Date/Time:	Received By	Date/Time:	Nacaib
Email #2:					Sample Receipt pri
phone:	Relinquished By:	Date/Time:	Received By:	Date/Time:	Cooler Custody Seal
	Relinquished By:	Date/Time:	Received By:	Date/Time:	Present / Not Present
special pricing and release of liability				ANGERSTANDERSTANDERSTANDERSTANDERSTANDERSTANDERSTANDERSTANDERSTANDERSTANDERSTANDERSTANDERSTANDERSTANDERSTANDER	Version 6.0 (05/14/06
					ORIGINAL

റ്

UPPER MIDWEST REGION

MN: 612-607-1700 WI: 920-469-2436

Branch/Location: Company Name:

Brookfield, wit

Face Analytical®

(Please Print Clearly)

Ramball

Page of

46 of 48

AG5U AG4U AG1H AG4S AG1U BG3U AG2S 250 mL clear glass unpres 500 mL amber glass H2SO4 100 mL amber glass unpres 120 mL amber glass unpres 125 mL amber glass H2SO4 1 liter amber glass HCL 1 liter amber glass

Sample Preservation Receipt Form

Project #

Client Name:

All containers needing preservation have been checked and noted below: _Yes _No _AN/A 4018942

Pace Analytical Services, L&C 1241 Bellevue Street, Suit잘 9 Green Bay, WI 54국원2 e e Date/

_		ace	2	92	03	24	05	6	9	80	09	10	1	2	13	14	15	16	17	18	19	20
1		AG1U																				
		AG1H																				
		AG4S																				
	Glass	AG4U																				
		AG5U																				
	Section and the Section Sectio	AG2S																				
		BG3U																				
		BP1U																				
		BP2N																				
Lab		BP2Z																				
O# C	Plastic	BP3U																				
Lab Lot# of pH paper	Ċ	врзс																				
paper		BP3N																				
		BP3S																				
		DG9A																				
		DG9T																				
Гa	<	VG9U	\dashv																			
b Std	Vials	VG9H	-									,										
# D o		VG9M	-	Ī	-	1			-	_		_		-	- CONTROL OF	رو						
_ab Std #ID of preservation (if pH adjusted):	L	VG9D	-																			
ervati		JGFU		-					-	_	_				_							
on (≆	Jars	WGFU	-																			
pH ac	ß	WPFU									_		_									
Juste																						
ļ.	General	SP5T																				
	eral	ZPLC																				
┨		GN																				
4	(>6mm) '	VOA Vials																				
┨,	≤2	H2SO4 pH									_								_			
completed.	Act pH ≥9	NaOH+Zn /																				
	:12	NaOH pH ≥																				
	 52	HNO3 pH ≤																				
1 11116.	justed	pH after adj	Ħ										-									
	Volume	(mL)	2.5 / 5 / 10	2.5/5/10	2.5 / 5 / 10	2.5/5/10	2.5 / 5 / 10	2.5/5/10	2.5 / 5 / 10	2.5/5/10	2.5/5/10	2.5/5/10	2.5 / 5 / 10	2.5/5/10	2.5 / 5 / 10	2.5/5/10	2.5 / 5 / 10	2.5/5/10	2.5 / 5 / 10	2.5/5/10	2.5 / 5 / 10	2.5/5/10

Page $\frac{1}{2}$ of $\frac{1}{2}$

BP3U

BP2Z BP2N

500 mL plastic NaOH, Znact 500 mL plastic HNO3

WGFU WPFU

4 oz plastic jar unpres 4 oz clear jar unpres 4 oz amber jar unpres

JGFU

врзс

250 mL plastic NaOH 250 mL plastic unpres

VG9M VG9H VG9U DG9T DG9A

VG9D

40 mL clear vial DI 40 mL clear vial MeOH 40 mL clear vial HCL 40 mL clear vial unpres 40 mL amber Na Thio 40 mL amber ascorbic

ZPLC SP5T

ziploc bag

120 mL plastic Na Thiosulfate

S.

BP3S BP3N

250 mL plastic H2SO4

250 mL plastic HNO3

BP1U

liter plastic unpres

Pace Analytical 1241 Bellevue Street, Green Bay, WI 54302

Document Name:
Sample Condition Upon Receipt (SCUR)

Document No.: F-GB-C-031-Rev.07

Document Revised: 25Apr2018

Issuing Authority: Pace Green Bay Quality Office

Sample Condition Upon Receipt Form (SCUR)

D 1 1	١		Project #:	7 -	
Client Name: Kanbol				MO# ·	10185945
Courier: CS Logistics Fed Ex Speed	lee 「UPS	T W	altco	WUT · -	
Client Pace Other:					
Tracking #: 7866 8836	2760		_	40185945	}{81 8181 811
Custody Seal on Cooler/Box Present: yes	no Seals	intact:	yes no		
Custody Seal on Samples Present: 🦵 yeş 🏲			yes no		
Packing Material: Bubble Wrap Bub	ble Bags	None	Other	-6.	
Thermometer Used SR - 1/2	Type of Ice:	Wet	Blue Dry None	Samples on	ice, cooling process has begun
Cooler Temperature Uncorr: KOD /Corr:	Biolog	nical T	issue is Frozen:	ves no	Person examining contents:
Temp Blank Present: yes no Temp should be above freezing to 6°C.	210.05	g.00. 1	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	, 00 **	Date: 4-17-19
Biota Samples may be received at ≤ 0°C.					Initials:
Chain of Custody Present:	ZYes □No	□n/a	1. t CC		4-17-4 JK
Chain of Custody Filled Out:	□Yes ⊿ No	□n/a	2. NUMA: 1/:	100:00	4-17-19 JK
Chain of Custody Relinquished:	Z Yes □No	□n/a	3.		
Sampler Name & Signature on COC:	∠ Yes □No	□n/a	4.		
Samples Arrived within Hold Time:	Z Yes □No		5.		
- VOA Samples frozen upon receipt	□Yes □No		Date/Time:		
Short Hold Time Analysis (<72hr):	□Yes ∠ No		6.		
Rush Turn Around Time Requested:	□Yes ØNo		7.		
Sufficient Volume:			8.		
For Analysis: ☑ es ☐ No MS/MSI	D: □Yes ☑No	□n/a			
Correct Containers Used:	ZYes □No		9.		
-Pace Containers Used:	ZYes □No	□n/a			
-Pace IR Containers Used:	□Yes □No	6 _{N/A}			
Containers Intact:	Yes □No		10.		
Filtered volume received for Dissolved tests	□Yes □No	Z N/A	11.		
Sample Labels match COC:	□Yes ☑No	□n/a	12. No fate ex	10 on 014	U-17.47h
-Includes date/time/ID/Analysis Matrix:	5				
Trip Blank Present:	⊡ Yes □No	.□n/a	13. Me0 H		4-17-19/4
Trip Blank Custody Seals Present	✓ Yes □ No	□n/a	(NCOI)		
Pace Trip Blank Lot # (if purchased):					
Client Notification/ Resolution:		Date 1		necked, see attac	hed form for additional comments
Person Contacted: Comments/ Resolution:		_Date/	tuffe.		
Commenter Recordant.					
					/
			\longrightarrow		1//10/10
					4117119
Project Manager Review:				Date:	
					Page Page 18 di