

# Project Quantities

Rosenthal  
2381 108th Street

	Materials	Quantity		
<b>Rock Pit</b>				
8 ounce, 6' wide	Filter fabric - linear feet	60		
8 ounce, 15' wide	Filter fabric - linear feet	30		
3/4 - 1 1/2" rock	Pit Rock (yards)	33.4	15X30X2/27	
1/4 to 3/4" rock	Surface Rock (yards)	5.5	15X30X.33/27	
<b>Ramp Removal</b>				
	concrete	remove		
Revegetate	grass seed			
topsoil	topsoil (yards)	2.72	.34X4X36x1.5/27	
	netless excelsior blanket			
<b>Berm</b>				
above boathouse	topsoil for berm (yards)	4.5	8X30X.34X1.5/27	
by lake	topsoil for berm (yards)	5	3X60X0.5X1.5/27	
	grass seed			
	netless excelsior blanket			
<b>Silt Fence</b>				
	feet	60		

Stabilize all disturbed areas by seeding and covering with netless excelsior blanket

Quantities to be verified by bidder from plan and site review

Install silt fence between disturbed areas and Bone Lake